

NOTICE

All drawings located at the end of the document.

INFORMATION
ONLY

Controlled Copy No. 665



ROCKY FLATS

RFP/ER-SAF-94-GMP

ADMIN RECORD

**Final
Health and Safety Plan
Groundwater Monitoring Program**



April 1995

DOCUMENT CLASSIFICATION
REVIEW WAIVER PER
CLASSIFICATION OFFICE

A-SW-002228

**FINAL
HEALTH AND SAFETY PLAN (HASP)
GROUNDWATER MONITORING PROGRAM**

VERSION 0.1

*Rocky Flats Environmental Technology Site
Golden, Colorado*

FINAL
GROUNDWATER MONITORING PROGRAM HEALTH AND SAFETY PLAN

EG&G ROCKY FLATS PLANT

Manual:

RFP/ER-SAF-94-GMP

Revision No.:

0

Page:

Effective Date:

3/15/95

Organization:

Environmental Management


"Health And Safety Plan (HASP), Groundwater Monitoring Program, Rocky Flats Plant," prepared by Golder Associates Inc.

This site-specific Health And Safety Plan has been written for the use of EG&G-Rocky Flats, Inc., its employees and subcontractors. Personnel associated with this Project will comply with all aspects of this plan.

REVIEW AND APPROVAL


EG&G Project Manager

1/26/95
Date


Health and Safety Liaison Officer

2-15-95
Date


Environmental Restoration Health and Safety Officer

1/26/95
Date

**ROCKY FLATS ENVIRONMENTAL
TECHNOLOGY SITE**

**Manual No.:
Section No.
Page:**

**RFP/ER-SAF-94-GMP
Table of Contents, R0
1 of 1**

**GROUNDWATER MONITORING
PROGRAM HEALTH & SAFETY PLAN**

**Effective Date: 03/15/95
Organization: Environmental Restoration Mgmt**

**TABLE OF CONTENTS
HEALTH AND SAFETY PLAN (HASP)
GROUNDWATER MONITORING PROGRAM**

Section No.	Title	Rev. No.	Effective Date
	Table of Contents	0	03/15/95
1.0	Project Identification	0	03/15/95
2.0	Staff Organization	0	03/15/95
3.0	Site History and Nature of Contamination	0	03/15/95
4.0	Work Activities	0	03/15/95
5.0	Hazard Assessment	0	03/15/95
6.0	General Site-Specific Health and Safety Requirements	0	03/15/95
7.0	Site-Specific Personal Protective Equipment Requirements	0	03/15/95
8.0	Emergency Response Procedures	0	03/15/95
9.0	Logs, Reports, and Recordkeeping	0	03/15/95
10.0	References	0	03/15/95
LT	List of Tables	0	03/15/95
LF	List of Figures	0	03/15/95
APPA	Appendix A: Responsibilities and Authority of Health and Safety Personnel	0	03/15/95
APPB	Appendix B: Characteristics of Radioisotopes Found at Rocky Flats	0	03/15/95
APPC	Appendix C: List of Chemical Substances Found at Rocky Flats	0	03/15/95
APPD	Appendix D: Example On-the-Job Training	0	03/15/95
APPE	Appendix E: Air Monitoring Survey Results	0	03/15/95
APPF	Appendix F: Special Task Health and Safety Plan	0	03/15/95

DOCUMENT CLASSIFICATION REVIEW
PER R.B. HOFFMAN, CLASSIFICATION OFFICER
JUNE 11, 1991

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: i of viii
Effective Date: 3/15/95
Organization: Environmental Management

TABLE OF CONTENTS

	<u>Page</u>
1.0 PROJECT IDENTIFICATION	1
2.0 STAFF ORGANIZATION	2
3.0 SITE HISTORY AND NATURE OF CONTAMINATION	3
3.1 Rocky Flats	3
3.1.1 Physical Setting	3
3.1.2 Site Background	3
3.1.3 Rocky Flats Operations	4
3.1.4 Previous Investigations	4
3.1.5 Groundwater Monitoring Program	5
3.2 Creation of the Operable Units and Individual Hazardous Substance Sites (IHSS's)	7
3.3 Operable Unit 1 - 881 Hillside	8
3.4 Operable Unit 2 - 903 Pad, Mound, and East Trenches	9
3.5 Operable Unit 3 - Off-Site Releases	11
3.6 Operable Unit 4 - Solar Evaporation Ponds	13
3.7 Operable Unit 5 - Woman Creek Priority Drainage	13
3.8 Operable Unit 6 - Walnut Creek Priority Drainage	14
3.9 Operable Unit 7 - Present Landfill and Inactive Hazardous Waste Storage Area	16
3.10 Operable Unit 8 - 700 Area	17
3.11 Operable Unit 9 - Original Process Waste Lines	18
3.12 Operable Unit 10 - Other Outside Closures	19
3.13 Operable Unit 11 - West Spray Field	21
3.14 Operable Unit 12 - 400/800 Area	21
3.15 Operable Unit 13 - 100 Area	22
3.16 Operable Unit 14 - Radioactive Sites	24
3.17 Operable Unit 15 - Inside Building Closures	24
3.18 Operable Unit 16 - Low-Priority Sites	25
3.19 Buffer Zone	26

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: ii of viii
Effective Date: 3/15/95
Organization: Environmental Management

TABLE OF CONTENTS--Continued

	<u>Page</u>
4.0 WORK ACTIVITIES.....	27
4.1 Introduction.....	27
4.2 Activities	27
5.0 HAZARD ASSESSMENT.....	29
5.1 Overview	29
5.2 Hazard Assessment Methodologies and Results	30
5.2.1 Methodology Employed to Assess Encounters with Wildlife, Environmental Extremes, Physical Injuries, and Electrical Shock When Working With Equipment	30
5.2.2 Methodology Employed to Assess Exposures to Radioisotopes and Nonradioactive Potentially Hazardous Chemicals	30
5.2.2.1 The Absorption, Injection, and Ingestion Routes of Exposure	31
5.2.2.2 The Inhalation Route of Exposure	31
6.0 GENERAL SITE-SPECIFIC HEALTH AND SAFETY REQUIREMENTS	33
6.1 Medical Surveillance.....	33
6.2 Safety Training	33
6.2.1 40-hour Basic Training	34
6.2.2 Three-Day On-Site Supervision	34
6.2.3 Radiation Worker Training	34
6.2.4 On-Site Project Manager.....	35
6.2.5 Site Safety Officer (SSO)	35
6.2.6 Health & Safety Specialist (HSS)	35
6.2.7 Site-Specific Safety Orientation Meeting	36
6.2.8 Periodic Safety Meetings	37

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: iii of viii
Effective Date: 3/15/95
Organization: Environmental Management

TABLE OF CONTENTS--Continued

	<u>Page</u>
6.2.9 Lifting	37
6.3 Visitor Clearances	38
6.4 Buddy System	38
6.5 Work Zones.....	39
6.5.1 Exclusion Zone (EZ).....	39
6.5.2 Contamination Reduction Zone (CRZ)	41
6.5.2.1 RCA Step-off Pad Requirements	41
6.5.2.2 Non-RCA Step-off Pad Requirements	43
6.5.3 Support Zone	43
6.6 Field Activities	44
6.6.1 Personnel Requirements/Prohibitions	44
6.6.2 Contamination/Exposure Prevention.....	46
6.6.3 On-Site Travel	47
6.6.4 Housekeeping.....	48
6.7 Personal Protective Equipment (PPE)	48
6.7.1 Clothing	49
6.7.2 Protective-toe Footware, Safety Glasses, and Hard Hats	50
6.7.3 Respirators	50
6.8 Emergency Equipment.....	50
6.9 Temperature Stress	51
6.9.1 Heat Stress	51
6.9.2 Heat Stress Monitoring	53
6.9.3 Cold Stress	56
6.9.4 Cold Stress Monitoring	56

**FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM**

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: iv of viii
Effective Date: 3/15/95
Organization: Environmental Management

TABLE OF CONTENTS--Continued

	<u>Page</u>
6.9.5 Training	58
6.10 Work During Darkness	58
6.11 Confined Space Work	59
6.12 Thunderstorms and Tornadoes	60
6.13 Hand Tools and Portable Power Tools	60
6.13.1 General Requirements	61
6.13.2 Hand Tool Requirements	61
6.13.3 Power Tool Requirements	62
6.14 Electrical Safety	64
6.15 Laboratory Safety	66
6.15.1 Base Laboratory	66
6.15.2 General Safety	67
6.15.3 Storage and Handling of Chemicals	68
7.0 SITE-SPECIFIC PERSONAL PROTECTIVE EQUIPMENT REQUIREMENTS	70
7.1 Introduction	70
7.2 Monitoring Instruments	71
7.2.1 Radioactive Substance Monitoring Instruments	71
7.2.2 Chemical Substance Monitoring Instruments	72
7.3 Monitoring Strategies	73
7.3.1 Monitoring for Radioactive Substances	73
7.3.2 Monitoring for Chemical Substances	74
7.3.2.1 Photoionization Detector Monitoring	75
7.3.2.2 Colormetric Detector Tube Monitoring	75

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: v of viii
Effective Date: 3/15/95
Organization: Environmental Management

TABLE OF CONTENTS--Continued

	<u>Page</u>
7.3.2.3 Combustible Gas Indicator Monitoring	76
7.4 Personal Protective Equipment	77
7.4.1 Clothing	78
7.4.2 Respirators	79
7.4.2.1 Respiratory Protection Program	81
7.4.2.2 Respirator Decision Logic	81
7.4.2.3 Respirator Action Levels	82
7.4.3 Personal Protective Equipment Ensembles	83
7.4.3.1 Level D	84
7.4.3.2 Modified Level D	85
7.4.3.3 Level C	86
7.5 Required Levels of Personal Protective Equipment Per Task.....	87
7.5.1 SOP GW.1: Water Level Measurements in Wells and Piezometers	87
7.5.2 SOP GW.2: Well Development.....	88
7.5.3 SOP GW.3: Pump-in Borehole Packer Testing	89
7.5.4 SOP GW.4: Slug Tests	90
7.5.5 SOP GW.5: Field Measurement of Groundwater Field Parameters	91
7.5.6 SOP GW.6: Groundwater Sampling.....	92
7.5.7 SOP GW.8: Aquifer Pumping Tests.....	92
7.5.8 SOP FO.01: Air Monitoring and Dust Control	93
7.5.9 SOP FO.02: Transmittal of Field QA Records	94
7.5.10 SOP FO.03: General Equipment Decontamination	94
7.5.11 SOP FO.05: Handling of Purge and Development Water	97
7.5.12 SOP FO.06: Handling Personal Protective Equipment	98

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: vi of viii
Effective Date: 3/15/95
Organization: Environmental Management

TABLE OF CONTENTS--Continued

	<u>Page</u>
7.5.13 SOP FO.07: Handling of Decontamination Water and Wash Water	98
7.5.14 SOP FO.11: Field Communications	99
7.5.15 SOP FO.12: Decontamination Facility Operations	100
7.5.16 SOP FO.13: Containerization, Preserving, Handling and Shipping of Soil and Water Samples	101
7.5.17 SOP FO.14: Field Data Management.....	102
7.5.18 SOP FO.15: Photoionization Detectors (PID) and Flame Ionization Detectors (FID)	103
7.5.19 SOP FO.16: Field Radiological Measurements	103
7.5.20 SOP FO.18: Environmental Sample Radioactivity Content Screening	104
7.5.21 SOP FO.19: Base Laboratory Work	105
7.5.22 SOP FO.25: Shipment of Radioactive Materials Samples	105
7.5.23 Special Tasks Conducted by the Groundwater Monitoring Program Subcontractor	106
 8.0 EMERGENCY RESPONSE PROCEDURES	 107
8.1 Radio Communications	107
8.2 Emergency Telephone	107
8.3 Medical Facilities	108
8.4 Emergency Response Procedures	109
8.4.1 Fire/Explosion	110
8.4.2 Physical Injury	111
8.4.3 Injury Due to Heat	111
8.4.4 Injury Due to Cold	112
8.4.5 Reporting and Notification	114
8.4.6 Thunderstorms and Tornadoes	114
8.4.7 Other Adverse Weather	115
8.4.8 Electric Shock.....	115

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: vii of viii
Effective Date: 3/15/95
Organization: Environmental Management

TABLE OF CONTENTS--Continued

	<u>Page</u>
9.0 LOGS, REPORTS, AND RECORDKEEPING	117
9.1 General	117
9.2 Personnel Records	117
9.3 Calibration Records	117
9.4 Occupational Safety and Health Administration Form 200	118
9.5 Health and Safety Logbook.....	118
9.6 Accident/Incident Reporting	119
9.6.1 Subcontractor Procedures	119
9.6.2 Rocky Flats Procedures	119
10.0 REFERENCES	121

LIST OF TABLES

Table 6-1	Signs and Symptoms of Heat Stress
Table 6-2	Permissible Heat Exposure Limits
Table 7-1	Environmental Management Radiological Guidelines
Table 7-2	Action Levels for Nonradioactive Issues
Table 7-3	Task-Specific PPE Requirements
Table 8-1	Emergency Telephone Numbers
Table 8-2	Emergency Alarms

LIST OF FIGURES

Figure 3-1	Rocky Flats Site Map
Figure 3-2	Groundwater Monitoring Well and Piezometer Locations
Figure 8-1	Medical Facility Map

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: viii of viii
Effective Date: 3/15/95
Organization: Environmental Management

TABLE OF CONTENTS--continued

LIST OF APPENDICES

- Appendix A Responsibilities and Authority of Health and Safety Personnel
- Appendix B Characteristics of Radioisotopes Found at Rocky Flats
- Appendix C List of Chemical Substances Found at Rocky Flats
- Appendix D Example On-the-Job Training (OJT) Form
- Appendix E Air Monitoring Survey Results
- Appendix F Special Task Health and Safety Plan

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 3 of 123
Effective Date: 3/15/95
Organization: Environmental Management

3.0 SITE HISTORY AND NATURE OF CONTAMINATION

3.1 Rocky Flats

3.1.1 Physical Setting

The Rocky Flats Environmental Technology Site is located in northern Jefferson County, Colorado, approximately 16 miles northwest of Denver. The cities of Boulder, Broomfield, Westminster, and Arvada are located less than 10 miles to the north, northeast, east, and southeast, respectively. Rocky Flats consists of approximately 6,550 acres of federal land and occupies Sections 1 through 4 and 9 through 15 of Township 2 South, Range 70 West, 6th Principal Meridian. Major plant buildings are located within the Rocky Flats security area of approximately 400 acres. The security area is surrounded by a Buffer Zone of approximately 6,150 acres. Rocky Flats is generally bounded on the north by State Highway 128. To the east is Jefferson County Highway 17, also known as Indiana Street; to the south are agricultural and industrial properties, and State Highway 72; and to the west is State Highway 93. A general map of the site is provided in Figure 3-1.

3.1.2 Site Background

Rocky Flats is a government-owned and contractor-operated facility that is part of the nationwide nuclear weapons production complex. Rocky Flats was operated for the U. S. Atomic Energy Commission (AEC) from Rocky Flats' inception in 1951 until the AEC was dissolved in January 1975. At that time, responsibility for Rocky Flats was assigned to the Energy Research and Development Administration (ERDA), which was succeeded by the Department of Energy (DOE) in 1977. Dow Chemical USA, an operating unit of the Dow Chemical Company, was the

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 4 of 123
Effective Date: 3/15/95
Organization: Environmental Management

managing and operating contractor of the facility from 1951 until June 30, 1975. Rockwell International succeeded Dow Chemical USA from July 1, 1975 to January 1, 1990, when EG&G-Rocky Flats, Inc. succeeded Rockwell International.

3.1.3 Rocky Flats Plant Operations

Until 1992, Rocky Flat's primary mission was to produce metal components for nuclear weapons. These components were fabricated from plutonium, uranium, and nonradioactive metals, principally beryllium and stainless steel. Parts made at the plant were shipped elsewhere for final assembly. When a nuclear weapon is determined to be obsolete, components of these weapons which had been fabricated at Rocky Flats are returned for special processing which recovers plutonium. Other activities at Rocky Flats include research and development in metallurgy, machining, nondestructive testing, coatings, remote engineering, chemistry, and physics.

3.1.4 Previous Investigations

Various studies have been conducted at Rocky Flats to characterize environmental media and to assess the extent of radiological and chemical contaminant releases to the environment. These have included geological studies, surface water and groundwater studies, and geophysical and radiometric surveys. Several environmental, ecological, and public health studies culminated in the Final Site-wide Environmental Impact Statement (DOE 1980).

In 1986, two major environmental investigations were completed at Rocky Flats. The first was the Comprehensive Environmental Assessment and Response Program (CEARP) Installation Assessment (DOE 1986a), which included analyses and identification of current operational

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 5 of 123
Effective Date: 3/15/95
Organization: Environmental Management

activities, active and inactive waste sites, current and past waste management practices, and potential environmental pathways through which contaminants could be transported. A number of sites that could potentially have adverse impacts on the environment were identified. These sites were divided into three categories:

- Hazardous waste management units that will continue to operate and need a Resource Conservation and Recovery Act (RCRA) Part A operating permit;
- Hazardous waste management units that will be closed under RCRA interim status; and,
- Inactive waste management units that will be investigated and cleaned up under Section 3004 (u) of RCRA or under CERCLA.

The second major environmental investigation completed at Rocky Flats in 1986 involved a hydrogeologic and hydrochemical characterization of the entire Rocky Flats site. Results of these investigations were reported by Rockwell International in 1986. Investigation results indicated four areas to be significant contributors to environmental contamination, with each area containing several sites. Those areas are commonly referred to as the 881 Hillside Area, the 903 Pad Area, the Mound Area, and the East Trenches Area.

3.1.5 Groundwater Monitoring Program

The Groundwater Monitoring Program at Rocky Flats currently includes 510 wells. The actual number of wells monitored varies according to specific program requirements. The program has been designed to protect groundwater, measure the concentrations and rate of transport of hazardous constituents, and to define the extent of any contaminant plumes in the uppermost aquifer within the Rocky Flats boundaries. Three Operable Units (OUs) (the Solar Evaporation

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 6 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Ponds [OU4], the Present Landfill [OU7], and the West Spray Field [OU11]) at Rocky Flats are subject to Interim Status groundwater monitoring requirements under the Resource Conservation and Recovery Act (RCRA). The remainder of the Rocky Flats OUs are sampled to characterize the groundwater during the Remedial Field Investigation (RFI) activities or do not require a specific groundwater monitoring system, but have been included in the Rocky Flats Groundwater Monitoring Program to supply hydrogeologic and analytical data needed to characterize other areas of Rocky Flats. Groundwater monitoring is currently being accomplished within 12 OUs and the Buffer Zone and at Rocky Flats. The twelve areas are listed below and discussed in subsequent subsections of the Section.

- OU1: 881 Hillside;
- OU2: 903 Pad, Mound, and East Trenches;
- OU3: Off-Site Releases;
- OU4: Solar Evaporation Ponds;
- OU5: Woman Creek Priority Drainage;
- OU6: Walnut Creek Priority Drainage;
- OU7: Present Landfill and Inactive Hazardous Waste Storage Areas;
- OU9: Original Process Waste Lines;
- OU11: West Spray Field;
- OU12: 400/800 Area;
- OU13: 100 Area; and,
- OU14: Radioactive Sites.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 7 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Wells at Rocky Flats are classified into one of six categories, determined by their specific function in the Groundwater Protection and Monitoring Program. The locations of each well and piezometer are shown in Figure 3-2. The six types are defined as follows:

- **RCRA Wells** - Wells that monitor the uppermost aquifer and which are capable of (1) immediately detecting any statistically significant amounts of hazardous waste or hazardous waste constituents that migrate into the uppermost aquifer, and (2) determining the rate and extent of migration of hazardous waste or hazardous waste constituents in the groundwater;
- **CERCLA Wells** - Wells that are used for the characterization of RFI activities as stated in 40 CFR Section 430;
- **Boundary Wells** - The on-site monitoring wells located furthest downgradient of Rocky Flats-affected areas;
- **Background Wells** - Wells that monitor the groundwater in areas upgradient or cogradient of Rocky Flats and that are unaffected by Rocky Flats operations;
- **RCRA-Characterization Wells** - Additional wells in the groundwater monitoring program are used to characterize the groundwater. For example, wells within a RCRA-regulated unit that monitor a hydrostratigraphic unit which is not the uppermost aquifer are characterization wells; and,
- **Special Purpose Wells** - Wells that are sampled at the discretion of EG&G-Geosciences.

3.2 Creation of the Operable Units and Individual Hazardous Substance Sites (IHSS's)

The Draft Installation Assessment under the Comprehensive Environmental Restoration Program (CERP), formerly the Comprehensive Environmental Assessment and Response Program (CEARP) (DOE 1986a), appears to have been the first document to compile a list of potential

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 8 of 123
Effective Date: 3/15/95
Organization: Environmental Management

hazardous waste sites at Rocky Flats. The Assessment also attempted to prioritize the sites on the basis of EPA's Hazard Ranking System (HRS) and DOE's Modified HRS scoring. High priority sites, such as the 881 Hillside, were recommended for further investigation. In response to the recommendation, remedial investigations commenced at the high priority sites. The RCRA Part B Permit Application (DOE 1986b, DOE 1986c) for Rocky Flats was completed in November 1986 for Rocky Flats hazardous waste management units that would continue to operate. Appendix 1 of the permit application (DOE 1987), RCRA 3004 (u) Waste Management Units, defined the inactive waste sites as solid waste management units (SWMUs). A plan for investigating the remaining sites, referred to as the low priority sites, was prepared in 1988. This plan identified 103 low priority SWMUs and recommended appropriate additional investigations. The plan also presented groups of SWMUs based on their geographical locations, similar contaminants, and applicable pathways. The SWMUs were combined into ten Operable Units (OUs) in the Draft Interagency Agreement (IAG) (IAG 1990).

Additional SWMUs were added to the IAG based on the Part B RCRA application and independent reviews of aerial photographs and facility submittals. A total of 178 SWMUs were identified. The ten OUs were reprioritized and divided into sixteen OUs (Operable Units 1 through 16) in the final IAG (1991). The SWMUs were also renamed Individual Hazardous Substances Sites (IHSS's) in the final IAG. The term IHSS is used in the remainder of this Section.

3.3 Operable Unit 1 - 881 Hillside

Information on the nature and extent of contamination is taken from the Final Phase III RFI/RI Work Plan, Rocky Flats Plant, 881 Hillside Area Operable Unit No. 1 (DOE 1990). Section 2.3.1

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 9 of 123
Effective Date: 3/15/95
Organization: Environmental Management

of that Work Plan describes how background levels of chemical constituents were calculated. Section 2.3 and the Appendixes of that Work Plan present available analytical data.

Phase I and Phase II soils investigations indicated tetrachloroethane, trichloroethene, and 1,1,1-trichloroethane contamination in some samples at the 881 Hillside. Plutonium and americium were detected above background in soil samples that include the ground surface; however, windblown dust from the 903 Pad (OU2) is the suspected source of these radionuclides. Tetrachloroethane and trichloroethene are the principle volatile organic compounds which have been detected in surface water samples in the area. Numerous metals and other inorganic compounds have occasionally been above background. Gross alpha, gross beta, uranium, and plutonium exceed background in many of the surface water samples.

Groundwater is contaminated in both the eastern and western portion of the 881 Hillside. The most pronounced organic contamination is in the eastern portion of the Hillside area, with tetrachloroethane, trichloroethene, 1,1-dichloroethene, 1,1-dichloroethane, 1,1,1-trichloroethane, 1,1,2-trichloroethane, and carbon tetrachloride reaching several thousand micrograms per liter in many samples. Organic contamination in the western portion of the 881 Hillside area occurs at much lower concentrations. Concentrations of metals and inorganic constituents in the eastern portion of the study area include numerous occurrences of nickel, strontium, selenium, zinc, copper, and uranium above background.

3.4 Operable Unit 2 - 903 Pad, Mound, and East Trenches

Information on the nature and extent of contamination is taken from the Phase II RFI/RI Work Plans for Alluvial and Bedrock, 903 Pad, Mound, and East Trenches Areas (Operable Unit 2)

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 10 of 123
Effective Date: 3/15/95
Organization: Environmental Management

(DOE 1991a, DOE 1991b). Section 2.3 of the Work Plan describes how background levels of chemical constituents were calculated. Section 2.3 and the Appendixes of the Work Plan present available analytical data.

Plutonium and americium occur above background in surface soils. Other radionuclides and trace metals occur at low concentrations and are infrequently above background but may also be soil contaminants. Data suggest plutonium and americium were released to soils in the area via wind dissemination during clean-up efforts at the 903 Drum Storage Site.

Based on existing results, carbon tetrachloride, tetrachloroethane, and trichloroethene are the primary volatile organic contaminants found in the upper hydrostratigraphic unit groundwater flow system. Trace elements commonly occurring above background in groundwater include strontium, barium, copper, and nickel, and to a lesser extent, chromium, manganese, selenium, lead, zinc, and molybdenum. Also, major cations and anions and total dissolved solids are somewhat elevated above background throughout and downgradient of the OU. Uranium-238 is the predominant radionuclide occurring above background in the upper groundwater, but a few samples indicate plutonium and americium downgradient of the 903 Pad and possibly north of the Mound.

There is considerable interaction between surface water and groundwater. As a result, organic contamination is observed in seeps downgradient of the 903 Pad and in the upper reaches of South Walnut Creek at the Mound Area. Also, somewhat elevated concentrations of total dissolved solids, major ions, strontium, zinc, and uranium are present at many of the surface water stations. Plutonium and americium are also observed in two seeps downgradient of the 903 Pad and in the

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 11 of 123
Effective Date: 3/15/95
Organization: Environmental Management

upper reaches of South Walnut Creek. This may be attributed to the water from the seeps coming in contact with surface soils exhibiting elevated concentrations of these radionuclides.

3.5 Operable Unit 3 - Off-Site Releases

Information on the nature and extent of contamination is taken from Final RFI/RI Work Plan for Operable Unit 3, Rocky Flats Plant (DOE 1991c).

IHSS 199, Contamination of the Land's Surface, is comprised of 350 acres of land with concentrations of plutonium greater than 0.9 picocuries per gram. Hot spots may occur outside the designated acreage; however, it is reasonable to assume that areas outside the designated acreage contain lower concentrations of plutonium than the designated areas. Remediation has been implemented on 120 of the 250 acres of contaminated land owned by Jefferson County. Tilling of the 120 acres resulted in soil concentrations below the mandated cleanup level. Revegetation of this land is in progress. Very few data exist for contaminants other than plutonium.

Sampling at Great Western Reservoir (IHSS 200) indicates that layers of sediment containing plutonium above background levels are present in the bottom of the reservoir. Plutonium exists in discrete sediment horizons (at depths of 17 inches and 7.5 inches) corresponding to historical releases from Rocky Flats. The highest concentrations are found in the deepest areas of the reservoir. There is no evidence of plutonium migration through the sediment column. Concentrations of plutonium and other radionuclides in water at the reservoir are below background levels and/or EPA drinking water standards.

**FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM**

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 12 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Radioactive materials released from Rocky Flats may have been transported to Standley Lake (IHSS 201) through surface water and/or airborne particulates. Plutonium has been measured in sediment in the lake. The concentrations in the sediment layers exceeded baseline levels beginning in the 1966 layer, peaked in 1969, and declined after 1969. The time period correlates with the known period of windblown plutonium release from the 903 Pad at Rocky Flats. Studies of the sediments concluded that plutonium rapidly and almost irreversibly attaches itself to clay sediments. In 1974, Battelle conducted an investigation of radionuclide concentrations in reservoirs and streams near Rocky Flats. Concentrations of plutonium-239, plutonium-240, and americium-241 in the water at the lake were above the expected atmospheric fallout background, which was not specifically quantified in the study, but were more than four orders of magnitude below EPA National Primary Drinking Water Regulation of 15 pCi/L for total long-lived alpha activity.

Only very limited data have been collected to characterize Mower Reservoir (IHSS 202). Rocky Flats-derived contaminants in the reservoir are believed to have been transported primarily as airborne particulates, and, to a lesser degree, by surface water through the Woman Creek drainage. It can be inferred that contaminant concentrations resulting from releases into Woman Creek would be similar for Mower Reservoir and Standley Lake, while concentrations resulting from airborne releases and from erosion and transport of contaminated soils by surface runoff would be similar for Mower Reservoir and Great West Reservoir. It is expected that Mower Reservoir received similar amounts of plutonium through airborne transport as the nearby land surface.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 13 of 123
Effective Date: 3/15/95
Organization: Environmental Management

3.6 Operable Unit 4 - Solar Evaporation Ponds

Information on the nature and extent of contamination is taken from the Draft Final Phase I RFI/RI Work Plan (DOE 1991d) and Environmental Assessment, Dewatering and RCRA Partial Closure Action on Solar Evaporation Ponds, Rocky Flats Plant (DOE 1991e). Section 2.5 of the Work Plan describes the calculation of background concentration and summarizes the chemical data for OU4.

Liquids and sludges in the Solar Evaporation Ponds contain detectable levels of the radionuclides plutonium, americium, tritium and uranium. Metals of interest in the liquids and sludges include beryllium, cadmium, chromium and nickel. Nitrates are also a major constituent of the liquids and sludges. Soil samples in the vicinity of the solar ponds contain concentrations of chromium, nickel, nitrate, potassium, sodium, calcium, magnesium, and radionuclides that are likely attributable to the Solar Ponds. Low levels of nitrates and radionuclides have been detected in both alluvial and bedrock groundwater. Surface water in the form of seeps near the solar ponds contains nitrate, metal and radionuclides.

3.7 Operable Unit 5 - Woman Creek Priority Drainage

Information on the nature and extent of contamination is taken from Section 2.0 of the Final Phase I RFI/RI Work Plan, Woman Creek Priority Drainage (Operable Unit No. 5) (DOE 1991f).

The Original Landfill (IHSS 115) received numerous materials during its operation. Chemicals that may have been placed in the Original Landfill include commonly used solvents, such as

**FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM**

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 14 of 123
Effective Date: 3/15/95
Organization: Environmental Management

trichloroethylene, carbon tetrachloride, tetrachloroethylene, petroleum distillates, 1,1,1-trichloroethane, dichloromethane, benzene, paint and paint thinners. Metals such as beryllium, uranium, lead, and chromium may also be present. Radiological surveys of the area have indicated the presence of radionuclides, and some soil containing uranium was previously removed from the Original Landfill. Metals and radionuclides have been detected in groundwater near the Original Landfill.

The nature and extent of contamination at the Ash Pits, Incinerator and Concrete Wash Pad (IHSS's 133.1 through 133.6) are not well known. General combustible wastes from Rocky Flats were burned in the incinerator along with as estimated 100 grams of depleted uranium. Metals were detected in Ash Pit 3. Metals and radionuclides have been detected in groundwater wells near the Ash Pits.

Detention ponds C-1 and C-2 have been regularly sampled in recent years. Water in the ponds is known to contain detectable concentrations of metals and radionuclides, but background levels have not been determined for the Woman Creek area. Sediment samples also contain measurable metals and radionuclides.

3.8 Operable Unit 6 - Walnut Creek Priority Drainage

Information on the nature and extent of contamination is taken from Section 2.0 of the Final Phase I RFI/RI Work Plan, Walnut Creek Priority Drainage (Operable Unit No. 6) (DOE 1991g).

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 15 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Ponds A-1 and A-2 contain radionuclides including plutonium and uranium in both the water and the sediments. Pond A-3 is reported to contain elevated uranium-233/234 and uranium-238 concentrations like Pond A-2. Water quality in Pond A-4 is similar to background levels.

Pond B-1 has moderately elevated uranium-233/234 and uranium-238 concentrations, and plutonium is reported in both the water and the sediments. Pond B-2 water contains background levels for the various radionuclides except plutonium. Pond B-3 has detectable plutonium as well as zinc and nitrates. Ponds B-4 and B-5 have detectable levels of uranium-233/234 and 238. Ground water in the vicinity of the A- and B-series ponds contain several metals and radionuclides above detection limits but these concentrations could represent background levels.

No previous studies have been conducted at the four spray fields. However, analytical results from water samples collected from the East and West Landfill Ponds provide significant data regarding the North, South and Pond Area Spray Fields (IHSS's 167.1-3). Strontium and tritium were detected in the Landfill Ponds water. In addition, minor organics and several metals and radionuclides have been reported in surface water and groundwater samples collected near the spray fields. Analytical data from Pond B-3 water provides data regarding the East Area Spray Field (IHSS 216.1). Radionuclides and metals have been detected in the water from Pond B-3.

Only one previous soils investigation has reportedly been conducted at Trench A. Uranium-233/234 and 238, and several volatile organics were detected in the soils. Metals, radionuclides and one volatile organic compound have been detected in groundwater in the vicinity of the trenches. No previous studies have been conducted at the Sludge Dispersal Area (IHSS 141). A potential for contamination within the drying beds by a variety of chemicals in the sludge, particularly plutonium, is possible. Volatile organics, metals, and radionuclides have been detected in groundwater and surface water samples downgradient of the IHSS.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 16 of 123
Effective Date: 3/15/95
Organization: Environmental Management

At the Triangle Area (IHSS 165), previous radiometric soil surveys have indicated the presence of radionuclides. The contaminated soils were removed on several occasions following the soil surveys. Metals, radionuclides and organic compounds have been detected in groundwater near the area.

Previous soils investigations at the Old Outfall (IHSS 143) reported elevated levels of plutonium and organics. Contaminated soils were removed from the site in 1971. Metals and radionuclides have been detected in surface water samples taken downgradient of the IHSS.

No previous investigations have been completed at the Soil Dump Area. The soils may contain plutonium.

3.9 Operable Unit 7 - Present Landfill and Inactive Hazardous Waste Storage Area

Since little direct characterization of the types of contaminants in the landfill or inactive storage area has been conducted to date, most of what is known is based on waste stream identification studies and groundwater and surface water quality monitoring (DOE 1991h). Previous evaluations of groundwater quality from wells at the periphery of the landfill indicate the landfill contributes calcium, bicarbonate, and, to a lesser extent, sulfate, iron, manganese, zinc, and strontium to the groundwater. Volatile contamination, primarily trichloroethylene and 1,1,1-trichloroethane, has been found sporadically and at low concentrations in groundwater in some areas at the landfill periphery. Elevated uranium and tritium levels also exist in some areas. Soil contamination has not been characterized, but it may be reasonable to assume that the nature of contamination is similar to the groundwater contamination.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 17 of 123
Effective Date: 3/15/95
Organization: Environmental Management

The primary mechanism for release of contaminants from the Present Landfill into the affected media appears to be by percolation of groundwater (leachate) through the wastes and then out of the landfill. Groundwater flow exiting the wastes can potentially distribute contamination vertically downward and laterally downgradient.

3.10 Operable Unit 8 - 700 Area

Since previous investigations have not been conducted at these units, the nature and extent of contamination is based on materials stored at the sites and on previous site uses. (Rockwell International 1988, DOE 1987, DOE 1992a, DOE 1992b.)

Materials stored in the tanks involved in the Multiple Solvent Spills (IHSS's 118.1 and 188.2) included carbon tetrachloride, petroleum distillates, paint thinners, 1,1,1-trichloroethane and methyl ethyl ketone. Process wastes, typically containing uranium, solvents, oils, beryllium, nitric acid, hydrochloric acid, and fluoride, were released from Valve Vault 7 (IHSS 123.1). Cooling Tower Blowdown from IHSS's 135, 137, and 138 typically contained algicides and chromates. The 1976 spill from IHSS 138 also contained some radioactivity. The 1990 spill from IHSS 138 contained phosphates. Materials stored in the tanks involved in the Caustic/Acid Spills (IHSS's 139.1 and 139.2) included hydrochloric, hydrofluoric, nitric and sulfuric acids, and sodium hydroxide and potassium hydroxide. Spills of #2 fuel oil were the cause of IHSS 151, Fuel Oil Leak. A spill of a mixture of nitric and hydrochloric acid was the cause of the Acid Leak (IHSS 188).

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 18 of 123
Effective Date: 3/15/95
Organization: Environmental Management

The Sewer Line Break (IHSS 144) involved the release of radioactive laundry wastewater. The radioactive Liquid Leaks (IHSS 150.1-8) were primarily releases of liquid process wastes containing radioactive compounds and solutions containing caustics and acids.

The Radioactive Sites - 700 Area (IHSS 163.1 and 163.2) and Radioactive Sites - 900 Area (IHSS 173) may have been contaminated with radioactive compounds including americium. No radioactivity above background levels has been detected by radiometric surveys of the IHSS 163 locations. Radioactivity has been measured at IHSS 173. Radiometric surveys have not detected radioactivity above background levels at the Building 991 Steam Cleaning Area (IHSS 184). The Central Avenue Waste spill (IHSS 172) consisted of less than 100 gallons of plutonium contaminated oils and oils with lathe coolant (hydraulic oil and carbon tetrachloride).

3.11 Operable Unit 9 - Original Process Waste Lines (OPWL)

Information on the nature and extent of contamination is taken from Draft Final Phase I RFI/RI Work Plan, Original Process Waste Lines (Operable Unit No. 9) (DOE 1991i).

Low-level radioactive aqueous wastes with high nitrate concentrations were a primary OPWL waste stream. Volatile and semivolatile organics were transferred through the OPWL in small quantities. Numerous acids were discharged to the OPWL, as well as bases, metals, and small quantities of other liquids, including pickling liquor from foundry operations, medical decontamination fluids, miscellaneous laboratory wastes, and laundry effluent. Releases from the OPWL and associated IHSS's may have occurred as a results of leakage, deterioration of pipes,

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 19 of 123
Effective Date: 3/15/95
Organization: Environmental Management

breakage, and overflows. The lateral and vertical extent of releases are not precisely known but are expected to be largely confined to the pipeline trench backfill materials and adjacent soils.

3.12 Operable Unit 10 - Other Outside Closures

Information on the nature and extent of contamination is taken from Draft Final Phase I RFI/RI Work Plan, Rocky Flats Plant, Other Outside Closures (Operable Unit No. 10) (DOE 1991j).

Analytical results for soil samples taken in the vicinity of the Oil Leak (IHSS 129) indicate the presence of organics including 1,1,1-trichloroethane, methylene chloride, benzene, toluene, ethylbenzene, 2-butanone, and total xylenes, and metals including mercury, cadmium, copper, and lead. Radionuclides were not tested. Groundwater data are not available for this site.

No previous investigations have been performed at the P.U.&D. Storage Yard (IHSS 170) so the nature and extent of contamination is unknown. Soil sampling has been conducted at the Waste Spills (IHSS 174). Soils contain concentrations of volatile organics, metals, nitrates, and radionuclides above background levels. Acetone, methylene chloride and nitrate/nitrite were detected in a groundwater sample from a well northeast of IHSS's 170 and 174.

Soil samples were collected in the S&W Building 980 Container Storage Facility (IHSS 175) area in 1988. Volatile organics, metals, nitrate, and radionuclides were detected above background levels in the samples. No groundwater data are known to have been collected.

Analysis of soil samples taken from borings in the S&W Contractor Storage Yard (IHSS 176) indicate levels of volatile organics, metals, nitrate, and radionuclides above background

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 20 of 123
Effective Date: 3/15/95
Organization: Environmental Management

concentrations. Groundwater data from an upgradient well indicate the presence of metals, other inorganics, and radionuclides above background levels.

Potential contaminants at IHSS 207, Former Building 444 Acid Dumpsters, are cadmium, chromium, lead, silver, and radionuclides. No previous soil or water sampling investigations have been performed at the IHSS.

No previous investigations have been conducted at the Inactive 444/447 Waste Storage Area (IHSS 208) or Unit 16, Building 980 Cargo Container (IHSS 210), so no information is available concerning the nature and extent of contamination.

Analysis of soil samples taken in the area of the Unit 15, 904 Pad Pondcrete Storage Area (IHSS 213) indicated levels above background for gross alpha, gross beta, total plutonium, total uranium, uranium-234, uranium-238, americium-241, and plutonium-239. In addition, analysis of surface water samples taken in the area of IHSS 213 indicates levels above background for nitrate, cyanide, and cadmium. Further data are needed to assess groundwater contamination.

Soil samples taken from the Unit 25, 750 Pad Pondcrete and Saltcrete Storage Area (IHSS 214) indicate levels above background for gross alpha and gross beta. Surface water samples have levels above background for nitrate, cyanide, and cadmium. Further data are needed to assess groundwater contamination.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 21 of 123
Effective Date: 3/15/95
Organization: Environmental Management

3.13 Operable Unit 11 - West Spray Field

Information on the nature and extent of contamination is taken from Final Phase I RFI/RI Work Plan for OU11 (West Spray Field), Rocky Flats Plant (DOE 1991k).

The source of contamination to the West Spray Field is the liquids from the Solar Evaporation Ponds that were sprayed at the spray field. The liquids are known to contain major ions, radionuclides, metals, and some organics. Previous sampling has been done at the West Spray Field, and the results have been compared to background levels in the area.

Soil samples from the spray field show slightly elevated levels of arsenic, lead, manganese, mercury, zinc and several volatile organic compounds. Gross alpha, plutonium, uranium-233, -234, and -238 are also above background levels in soils. Groundwater monitoring wells have been installed in the West Spray Field. Alluvial groundwater quality is affected sporadically by several metals, radionuclides, nitrate, and tetrachloroethylene. Two of the three bedrock wells have occasionally exhibited above-background concentrations of magnesium, strontium, and manganese. The radionuclides and volatile organic compounds were not elevated. Surface water sampling has not been done at the West Spray Field.

3.14 Operable Unit 12 - 400/800 Area

Since previous investigations have not been conducted at these units, the nature and extent of contamination is based on materials stored at the sites and previous site uses (Rockwell International 1988, DOE 1992a).

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 22 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Releases of radionuclides from buildings adjacent to the Multiple Solvent Sites (IHSS's 116.1 and 116.2) may have resulted in soil contamination at these sites. Since the actual contents of the drums stored on the loading docks are unknown, it is assumed that volatile organic compounds may have been stored and may have leaked in the dock areas.

At the Building 664 Fiberglassing Areas (IHSS's 120.1 and 120.2), the chemicals of interest are believed to be polyester resins (styrene monomer) and cleaning solvents. Also, an area of significantly high radiation was measured directly west and overlapping the site.

The potential contaminant at the Cooling Tower Ponds (IHSS's 136.1 and 136.2) is chromium. Blowdown discharged to the ponds contained chromium and algicides. Uranium may also be buried at the pond sites.

The Process Waste Leaks (IHSS 147.2) area may have been contaminated by infiltration of water that contacted equipment stored at the site. The Radioactive Site South Area (IHSS 157.2) may be contaminated by uranium, beryllium and solvents. Plutonium may also be present. Contamination is not expected at the Acid Leak sites (IHSS 187) or the Multiple Acid Spills (IHSS 189) since the acid was likely neutralized in the soil.

3.15 Operable Unit 13 - 100 Area

Since previous investigations have not been conducted at these units, the nature and extent of contamination is based on materials stored at the sites and previous site uses (Rockwell International 1988, DOE 1992a).

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 23 of 123
Effective Date: 3/15/95
Organization: Environmental Management

The Chemical Storage Sites (IHSS 117.1-3) were used for storage of acids, organic solvents, soaps, and oils. These materials are assumed to be the potential contaminants at these IHSS's.

The Oil Burn Pit No. 1 Waste Leak (IHSS 128) is a pit area that contains approximately 70 cubic feet of depleted uranium. The Lithium Metal Destruction Site (IHSS 134) may contain residues of lithium and small amounts of sodium, calcium, and magnesium. The lithium has likely reacted with the soil to form lithium carbonate. Radionuclides may have been spilled at the Waste Spill (IHSS 148) site, although radioactive surveys of the area have found radioactivity levels consistent with background levels.

Fuel oil is the potential contaminant at the Fuel Oil Tank Spill (IHSS 152). The Radioactive Site South Area (IHSS 157.1) may be contaminated by uranium, beryllium and solvents. Plutonium may also be present. The Radioactive Site - Building 551 (IHSS 158) is suspected of being contaminated with uranium. The Waste Drum Peroxide Burial (IHSS 169) may still contain peroxide, which can be an explosion hazard. The site is not considered to be a chemical hazard. Residues of the burning of waste solvents are the concern at the Solvent Burning Ground (IHSS 171).

Radioactive process waste may have contaminated the Valve Vault 12 (IHSS 186) area. Sodium hydroxide is the potential contaminant at IHSS 190, the Caustic Leak. However, it is likely that any sodium hydroxide remaining in the environment would have been neutralized by the buffering action of the soil. The soil also would have buffered any remaining hydrogen peroxide from the Hydrogen Peroxide Spill (IHSS 191).

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 24 of 123
Effective Date: 3/15/95
Organization: Environmental Management

3.16 Operable Unit 14 - Radioactive Sites

Since previous investigations have not been conducted at these units, the nature and extent of contamination is based on materials stored at the sites and previous site uses (Rockwell International 1988, DOE 1992a).

Radioactive Site #1 - 700 Area (IHSS 131) and Radioactive Burial Site - Building 334 Parking Lot (IHSS 156.1) may have been contaminated by plutonium. Small amounts of plutonium and uranium may have remained at the Building 444 Parking Lot (IHSS 160) and Building 664 (IHSS 161); however, no radioactivity above background levels was detected during the radiometric survey of the area. The radioactive hot spots in the pavement on 8th Street may still exist as Radioactive Site #2 - 700 Area (IHSS 162). Radioactivity may also exist at the Radioactive Sites in the 800 Area (IHSS 164.1-3).

3.17 Operable Unit 15 - Inside Building Closures

Since previous investigations have not been conducted at these units, the nature and extent of contamination is based on materials stored at the sites and previous site uses (DOE 1988, DOE 1987, DOE 1992a).

Hazardous wastes such as volatile organic compounds and low-level radioactive waste oil have been stored in the Building 881 Drum Storage Area (IHSS 178). Waste oil contaminated with beryllium, and chlorinated solvents have been stored in the Building 865 Drum Storage Area (IHSS 179). Waste oil contaminated with volatile organic compounds, beryllium and radioactivity have been stored at the Building 883 Drum Storage Area (IHSS 180).

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 25 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Uranium chips, coated with freon TF and 1,1,1-trichloroethane, were handled in the Original Chip Roaster (IHSS 204). The freon and 1,1,1-trichloroethane burned away during the roasting process.

Low-level radioactive mixed wastes, including low-level combustibles, low-level metal and glass, low-level combustible hazardous waste and low-level glass and metal hazardous waste, were stored at Unit 26, Building 881 Drum Storage (IHSS 211). Transuranic wastes and solvents such as carbon tetrachloride, 1,1,1-trichloroethane, and toluene are stored in Unit 63, Building 371 Drum Storage (IHSS 212). Up to 4 liters of cyanide- contaminated laboratory wastes were stored in Unit 32, Building 881 Cyanide Bench Scale Treatment (IHSS 217).

3.18 Operable Unit 16 - Low-Priority Sites

Since previous investigations have not been conducted at these units, the nature and extent of contamination is based on materials stored at the sites and previous site uses (Rockwell International 1988, DOE 1992a).

The Solvent Spill (IHSS 185) was a spill of 1,1,1-trichloroethane. The Antifreeze Discharge (IHSS 192) was a spill of ethylene glycol. The spill was contained in Pond B-1. The Steam Condensate Leak (IHSS 193) contained amines. The Steam Condensate Leaks (IHSS 194) contained tritium. Nickel carbonyl is highly volatile and long-term environmental hazard would not result from the Nickel Carbonyl Disposal (IHSS 195).

Based on past uses, the water in the Water Treatment Plant Backwash Pond (IHSS 196) would have contained flocculants (aluminum sulfates and lime), residual chlorine, and suspended solids. Transformers containing PCBs may have been disposed at the Scrap Metal Sites (IHSS 197).

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 26 of 123
Effective Date: 3/15/95
Organization: Environmental Management

3.19 Buffer Zone

For the purposes of this Health and Safety Plan, the Buffer Zone is considered to be an area that is not located within either an IHSS or a RCRA-regulated area, does not contain a groundwater contamination plume, and is not considered to be a radiologically controlled area due to surficial soil contamination.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 27 of 123
Effective Date: 3/15/95
Organization: Environmental Management

4.0 WORK ACTIVITIES

4.1 Introduction

This Health And Safety Plan (HASP) covers the Groundwater Monitoring Program activities listed in Subsection 4.2 when they are accomplished at Rocky Flats.

4.2 Activities

Procedures for accomplishing the activities covered by this HASP are contained in the EG&G Environmental Management Department (EMD) Operating Procedures Manual (OPM) Number 5-21000-OPS-FO, Volume I: Field Operations; and EMD OPM Number 5-21000-OPS-GW, Volume II: Groundwater. This HASP addresses activities described in the following EMD OPM standard operating procedures (SOPs) as listed below. Additional SOPs related to the Groundwater Sampling Program will be added to the following list as they are developed and approved. The listed SOPs are incorporated in this HASP by reference.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

EG&G ROCKY FLATS PLANT

Manual:

RFP/ER-SAF-94-GMP

Revision No.:

0

Page:

28 of 123

Effective Date:

3/15/95

Organization:

Environmental Management

PROCEDURE NUMBER	TITLE
SOP FO.01	Air Monitoring and Dust Control
SOP FO.02	Field Document Control
SOP FO.03	General Equipment Decontamination
SOP FO.05	Handling of Purge and Development Water
SOP FO.06	Handling Personal Protective Equipment
SOP FO.07	Handling of Decontamination Water and Wash Water
SOP FO.11	Field Communication
SOP FO.12	Decontamination Facility Operations
SOP FO.13	Containerization, Preserving, Handling, and Shipping of Soil and Water Samples
SOP FO.14	Field Data Management
SOP FO.15	Photoionization Detectors (PIDs) and Flame Ionization Detectors (FIDs)
SOP FO.16	Field Radiological Measurements
SOP FO.18	Environmental Sample Radioactivity Content Screening
SOP FO.19	Base Laboratory Work
SOP FO.25	Shipment of Radioactive Materials Samples
SOP GW.01	Water Level Measurements in Wells and Piezometers
SOP GW.02	Well Development
SOP GW.03	Pump-in Borehole Packer Testing
SOP GW.04	Slug Tests
SOP GW.05	Field Measurements of Groundwater Field Parameters
SOP GW.06	Groundwater Sampling
SOP GW.08	Aquifer Pumping Tests

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 29 of 123
Effective Date: 3/15/95
Organization: Environmental Management

5.0 HAZARD ASSESSMENT

5.1 Overview

A review of Rocky Flats history, previous studies of the regional animal life and climate, results of previous site investigations, and the general industry-wide experience with using heavy equipment indicate that there are several sources of potential hazards to be assessed. The potential hazards have been placed into one of six classifications listed below.

- Encounters with native wildlife including insects.
- Climatic conditions such as temperature extremes, thunderstorms (lightning), and high winds.
- Physical injury when working with light equipment, handling drums, and operating vehicles.
- Electrical shock when working with equipment.
- Exposure to radioisotopes such as plutonium, americium, and uranium in groundwater and wind-blown dust via absorption, injection, ingestion and inhalation. Appendix B provides information regarding the characteristics of radioisotopes that may be encountered. Appendix B also contains Table B-1, which includes the maximum and minimum radioactivity concentration per radioisotope that has been reported at Rocky Flats.
- Exposure to nonradioactive potentially hazardous substances such as metals and volatile organic compounds in groundwater and wind-blown dust via absorption, injection, ingestion and inhalation. Appendix C contains Table C-1, which includes the maximum and minimum concentration of individual metals and volatile organic compounds reported in groundwater and soils at Rocky Flats.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 30 of 123
Effective Date: 3/15/95
Organization: Environmental Management

5.2 Hazard Assessment Methodologies and Results

The following is a brief summary of hazard assessment methodology and the assessment results. Detailed information regarding how hazard assessments were accomplished is presented in various attachments as specified in the text below.

5.2.1 Methodology Employed to Assess Encounters with Wildlife, Environmental Extremes, Physical Injuries, and Electrical Shock When Working With Equipment

There is a certain likelihood for each of the potential hazard classifications listed in Subsection 5.1 above to become a true hazard. An estimate of the likelihood of such occurrences for all classification of potential hazards has not been attempted. The assessment of the first four classifications of potential hazard (encounters with native wildlife, environmental extremes, physical injuries and electrical shock) is subjective and indicates that they will exist at each work site, and, therefore, that steps must be taken to minimize the hazard. (See Section 6.0, General Health and Safety Requirements; Section 7.0, Site-Specific Health and Safety Requirements; and various SOPs as listed in Section 4.2 and included in this HASP by reference.

5.2.2 Methodology Employed to Assess Exposures to Radioisotopes and Nonradioactive Potentially Hazardous Chemicals

The assessments of the last two classifications of potential hazards (radioisotopes and nonradioactive potentially hazardous chemicals in various environmental media) are presented by discussing the four potential routes of exposure. The routes of exposure discussed are absorption, injection (through the skin), ingestion, and inhalation.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 31 of 123
Effective Date: 3/15/95
Organization: Environmental Management

5.2.2.1 The Absorption, Injection, and Ingestion Routes of Exposure

A subjective manner of evaluation was used to assess the absorption, injection, and ingestion routes of exposure. The assessment indicates that these three routes of exposure will exist at each work site, and, therefore, that steps must be taken to minimize exposures by these routes. Methods of decreasing the likelihood of an exposure occurring via these routes are provided in Section 6.0, General Health and Safety Requirements; Section 7.0, Site-Specific Health and Safety Requirements; and various SOPs listed in Section 4.2 and included in this HASP by reference.

5.2.2.2 The Inhalation Route of Exposure

The potential for radioisotopes and nonradioactive metals in surface or groundwater to become airborne during the tasks listed in Section 4 is very low. The potential for these compounds to become airborne has been calculated from Derived Air Concentration (DAC) guidelines set forth in DOE Order 5480.11, "Radiation Protection for Workers." The DAC equation is as follows:

$$\begin{aligned} \text{Maximum Expected Airborne Concentration} = \\ \text{Soil Concentration} \times \text{Mass Loading} \times 30. \end{aligned}$$

Predictions based on application of the DAC equation to historical site data indicate that worker exposures greater than the applicable occupational exposure limit are very unlikely when working with surface or groundwater. However, prudent work practices, occupational exposure monitoring, and respiratory protection requirements to minimize exposures are established in Sections 6 and 7.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 32 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Worker exposures to materials such as volatile and semivolatile organic compounds (VOCs and SVOCs) in concentrations greater than the applicable occupational exposure limit are very unlikely when working with liquids, soils or sediments. In certain instances, airborne concentrations of these compounds may exceed Permissible Exposure Limits (PELs). Prudent work practices, environmental monitoring and respiratory protection requirements to address potential exposures are established in Sections 6 and 7.

The following list of chemicals has been identified as having the highest potential for exposure while working on the project.

Chemical	Predicted Maximum Airborne Concentration in ppm	PEL* in ppm	Percent Concentration of the PEL*
1,1-Dichloroethene	7.5	1	750%
Benzene	0.082	0.1	82%
Carbon Tetrachloride	0.0153	2	0.77
Methylene Chloride	0.434	25	1.74
Tetrachloroethylene	1.14	25	4.56
Vinyl Chloride	0.291	1	29.1

* PEL = Permissible Exposure Limit

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 33 of 123
Effective Date: 3/15/95
Organization: Environmental Management

**6.0 GENERAL SITE-SPECIFIC HEALTH AND SAFETY
REQUIREMENTS**

6.1 Medical Surveillance

All persons assigned to work at Rocky Flats on the groundwater monitoring program shall be active participants in a medical surveillance program as required by the Rocky Flats Health and Safety Practices Manual (HSP) Section 4.0, and equivalent to the requirements established by 29 CFR 1910.120. All medical examinations and procedures shall be performed by or under the supervision of a licensed physician, preferably an occupational physician. Each subcontractor shall submit a medical surveillance program to EG&G for approval prior to initiating Groundwater Monitoring Program work.

Radiation dosimeters and a Radiological Bioassay Program will be furnished by Rocky Flats and are required for all field workers conducting tasks in Radiologically-Controlled Areas (RCAs), in accordance with the requirements of HSP Sections 18.07 and 18.20.

6.2 Safety Training

Employees shall not participate in field activities until they have been trained to a level required by their job function and responsibility. Trainers will be trained in accordance with the requirements of Environmental Restoration Program Division - Training and Qualification (ERPD-T&Q). All training and field experience shall be documented and records of training documentation will be retained in the subcontractor Base Laboratory office. Training and training records shall meet the

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 34 of 123
Effective Date: 3/15/95
Organization: Environmental Management

requirements of Procedure ER-ADM-2.01, Training. Minimum training requirements are discussed below.

6.2.1 40-hour Basic Training

All on-site employees must have completed the 40-hour basic health and safety training, including Hazard Communication training, for Hazardous Waste Operations required under 29 CFR 1910.120 and receive 8-hour annual refresher training thereafter.

6.2.2 Three-Day On-Site Supervision

All on-site employees shall be required to receive a minimum of 3 days of on-site field experience in compliance with 29 CFR 1910.120 under the supervision of a trained and experienced supervisor. The trained and experienced supervisor will be experienced in the work that the employee is actually being trained in. On-site time under supervision shall be documented using an EG&G-approved form. An example of the EG&G On-the-Job Training (OJT) form is provided in Appendix D.

6.2.3 Radiation Worker Training

All field employees shall be required to receive Radiation Worker Training as required by HSP 18.02.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 35 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.2.4 On-Site Project Manager

The on-site subcontractor Project Manager (PM) must have completed the basic 40-hour training course, 3 days of on-site supervision and at least 8 hours of specialized training in an OSHA-approved course on managing hazardous waste operations. The 8 hours of specialized training shall include instruction covering this Health And Safety Plan, employee training program, personal protective equipment program, spill containment procedures, and health hazard monitoring procedures.

6.2.5 Site Safety Officer (SSO)

The Site Safety Officer must have completed the 40-hour training, 8-hour OSHA Supervisor training, 3-day on-site supervision, first aid training, and training required by 29 CFR 1910.1030, Bloodborne Pathogens. The SSO will be approved as a Health and Safety Specialist (HSS) by Radiological Engineering (RE). The SSO shall also possess current certificates of training in adult CPR and the Standard American Red Cross First Aid.

6.2.6 Health & Safety Specialist (HSS)

The Health and Safety Specialist (HSS) must have completed the 40-hour training, 8-hour OSHA Supervisor training, 3-day on-site supervision, and 3-day Radiation Worker Training. The HSS will be approved by Radiological Engineering and Industrial Hygiene representatives after demonstration of proficiency at HSS tasks. The HSS shall also possess current certificates of training in adult CPR and the Standard American Red Cross First Aid.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 36 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.2.7 Site-Specific Safety Orientation Meeting

Each contractor, subcontractor, and Rocky Flats employee will receive a site-specific safety orientation prior to participation in the Groundwater Monitoring Program. The following topics will be discussed at this meeting:

- Names of health and safety personnel and alternates responsible for site health and safety;
- Health and safety organization;
- Location of Material Safety Data Sheets (MSDSs);
- Hazards at the site;
- Electrocuting;
- Exposure risk;
- Personal protective equipment to be used;
- Personnel and equipment decontamination procedures;
- Air monitoring;
- Emergency procedures/contingency plans; and,
- Training requirements to perform tasks.

A copy of this Health and Safety Plan must be made available to all project personnel. At the end of the meeting, attendees should be informally quizzed to assess their understanding of the health and safety requirements, and should sign a safety compliance agreement form stating that they have

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 37 of 123
Effective Date: 3/15/95
Organization: Environmental Management

read, understand, and agree to comply with the provisions of the plan. Anyone refusing to sign the form will be prohibited from working at the site.

If a new employee who has not gone through the site-specific safety orientation meeting is assigned to the site, the SSO must present a similar briefing to the new employee before he or she participates in any field activities. All new employees must sign the safety compliance agreement form before beginning work. A copy of the signed safety compliance agreement will be provided to the SSO prior to beginning work.

6.2.8 Periodic Safety Meetings

Daily tailgate briefings are desirable but, as a minimum, weekly health and safety briefings will be conducted. Additional health and safety briefings will be conducted when the site manager and the SSO agree that a given topic warrants immediate attention.

6.2.9 Lifting

When lifting or carrying items is part of the job, it is each individual's responsibility to use the following guidelines:

- Make sure there are no nails or other items protruding which may cause injury in the lifting and carrying procedure;
- Use a lifting belt when lifting heavy objects;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 38 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Do not attempt to lift more than 50 pounds without assistance. Items weighing more than 50 pounds should be lifted by two people, or with a fork lift or hand truck;
- When lifting, crouch as close to the object as practical, get a good grip on it, and keep feet apart, bending at the knees;
- Lift slowly by straightening legs;
- Keep back relatively straight when lifting; and,
- Use leg muscles, not back muscles.

6.3 Visitor Clearances

All visitors to Rocky Flats must be cleared by Rocky Flats security personnel. Visitors will be escorted at all times by site personnel. They will be trained, at a minimum, in hazard recognition and personal protective equipment requirements appropriate for the activities in which they are to participate. In general, visitors will be restricted to support zones; entrance into exclusion zones will require additional training in accordance with 29 CFR 1910.120 and Rocky Flats site- and task-specific training, as described in Section 6.2.

6.4 Buddy System

The "buddy system" and radio communications will be used during all field activities at Rocky Flats. No field activities will be conducted on a "solo" basis.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 39 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.5 Work Zones

Work zones pertaining the to groundwater program will be established around each well when conducting Groundwater Monitoring Program tasks at the location. International orange cones will be set out to delineate the work zone and include the truck and well in the work zone. The decon tub(s) will be laid on visqueen or equivalent and will mark the line of most to least clean. Two work zones (exclusion zone [EZ] and support zone [SZ]) will be established for areas which are not Radiologically Controlled Areas (RCAs) or in areas where airborne volatile organic compound (VOC) concentrations do not exceed respiratory protection action levels, as discussed in Section 7.4.2.3.

The three work zones (exclusion zone [EZ], contamination reduction zone [CRZ], and the support zone [SZ], modified to imply the back, or shell of the truck, inclusive of the cab) shall be established and used in RCAs and in areas with airborne VOC concentrations exceeding respiratory protection action levels as described in Section 7.4.2.3. Environmental Management Radiological Guidance 1.3, Section 5.1.1, will be consulted for posting requirements applicable to areas and equipment contaminated or potentially contaminated with radioactive materials.

6.5.1 Exclusion Zone (EZ)

The Exclusion Zone (EZ) is a known contaminated or potentially contaminated area. Exclusion zones established around wells will be clearly marked with international orange cones and be of a sufficient size to permit easy movement of personnel or equipment within the zone. Access control points will be established at the periphery of each EZ to regulate and control the flow of personnel

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 40 of 123
Effective Date: 3/15/95
Organization: Environmental Management

and equipment into and out of the zone and to help verify that proper procedures for entering and exiting are followed.

When work is to be accomplished within a radiologically controlled area (RCA) or areas with VOC contamination potentially exceeding action levels, the SSO will be notified and will ensure the following actions are taken:

- Identify the area in which work is to be accomplished;
- Determine the radiological contamination or VOC level;
- Prepare a radiological work permit (RWP) if appropriate and contact EG&G Radiological Engineering;
- If appropriate, close off the work area with yellow and magenta tape or rope and post as a RCA with appropriate entrance and exit signs;
- Establish a step-off pad for exiting the area;
- Don appropriate PPE;
- Seal and transport items that cannot be radiologically decontaminated at the step-off pad, per Field Operating Procedure F.O.4, Section 6.4;
- When the item arrives at the decontamination facility, remove material used to seal contaminated area while wearing level of personal protective equipment specified in the RWP;
- Decontaminate item;
- Survey contaminated area to verify decontamination;
- Survey decontamination pad to verify decontamination;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 41 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- SSO will complete forms necessary to remove signs posted to mark the RCA; and,
- Depost the area after proper notification.

6.5.2 Contamination Reduction Zone (CRZ)

In general, the CRZ is established immediately outside the exclusion zone to minimize the migration of contaminants from the exclusion zone to clean or support areas, and to reduce the exposure potential of individuals leaving the exclusion zone. Personnel decontamination will require establishing a step-off pad. Minimum step-off pad requirements differ for radiologically-controlled areas (RCAs) and non-RCAs.

6.5.2.1 RCA Step-off Pad Requirements

Specific personnel decontamination procedures for radiological contamination are outlined in EMRG 2.1 and 2.3. Minimum requirements for a step-off pad such as is required at each radiologically controlled area (RCA) are listed below:

- Place a sign with the proper warnings/notices so that persons cannot enter the RCA without observing the sign. Procedures for exiting the RCA will be posted on the rear of the sign for review by persons exiting the RCA;
- Lay visqueen or other heavy gauge plastic sheeting on the ground so that a few feet of it extends into the RCA;
- Set up a table beside the visqueen so that half of the table is in the RCA and the other half is outside of the RCA;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 42 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Position two personal protective equipment (PPE) containers with plastic liners beside the table. One PPE container will be labeled "Contaminated PPE" and the other PPE container will be labeled "Uncontaminated PPE." Both containers shall be placed within the RCA;
- Cover the table top with visqueen or other heavy gauge plastic sheeting. Draw a line across the table top to indicate where the RCA boundary crosses the table. That half of the table inside the RCA will be used to place equipment that is to be screened for contamination. Equipment that has been screened and found free of contamination will be placed on the half of the table that is outside of the RCA. Equipment that has been screened and found to be contaminated will be examined for the presence of removable contamination. If contamination is removable, the equipment will be re-decontaminated and re-monitored. If the contamination is not removable, the equipment will be disposed of as radioactive waste and a EG&G Radiological Engineer will be notified to take appropriate action;
- The individual responsible for screening personnel as they depart the RCA will wear PPE appropriate for the task, as described in FO.06, and stand on the visqueen immediately outside of the RCA but near enough to the RCA boundary to conduct personnel screening activities;
- PPE found to be contaminated with radioactive materials will be placed inside the "Contaminated PPE" container; other PPE items will be placed in the "Uncontaminated PPE" container. Used PPE will be handled in accordance with the requirements of Standard Operating Procedure Field Operations 06, as summarized in Section 7.5.12;
- If radiological contamination is found, the PPE will be removed and the next layer of PPE monitored. That process will continue until contamination is no longer found. If radiologically-contaminated PPE is found, EG&G Radiological Engineering will be notified upon return from the field. If skin contamination is found, the HSS will notify EG&G Radiological Engineering and Occupational Medicine and provide steps necessary to remove that contamination; and,

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 43 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Respiratory protection will be the second to last PPE item monitored and removed if it was worn during the course of work within an RCA. Inner gloves will be the last PPE item removed.

6.5.2.2 Non-RCA Step-off Pad Requirements

In general, minimum step-off pad requirements for non-RCAs include:

- Place a sign restricting access to the CRZ to authorized personnel only;
- Position a personal protective equipment (PPE) container with a plastic liner in the CRZ. PPE will be handled in accordance with the requirements of FO.06, summarized in Section 7.5.12;
- Wash and rinse boots upon exiting the CRZ; and,
- Remove PPE, if worn, in the appropriate sequence. Respiratory protection, if worn, will be the second to last PPE item removed. Inner gloves will be the last item removed.

6.5.3 Support Zone

The support zone is located in a clean area, preferably upwind and immediately outside of the CRZ, or in the on-site vehicles. Supplies, first aid kit, eye wash, fire extinguisher, and support personnel are located in the support zone or in the on-site vehicles.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 44 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.6 Field Activities

6.6.1 Personnel Requirements/Prohibitions

- All personnel will carry radios for communication while in the field;
- All personnel will be issued a buffer zone pass by Environmental Operations Management at T891E prior to entry into the buffer zone or will log into the buffer zone daily prior to entry. Buffer zone rules will be obeyed;
- No running or horseplay;
- The required level of PPE must be worn by all on-site personnel;
- Eating, drinking, chewing gum or tobacco, smoking, or any practice that increases the probability of hand-to-mouth transfer and ingestion of material is prohibited in the EZ and the CRZ;
- Smoking is prohibited at the decontamination facility and in the buffer zone;
- No jewelry may be worn by personnel engaged in field work, except for watches, which will be disposed if they become contaminated;
- No facial hair which interferes with a satisfactory fit of the mask-to-face seal is allowed on personnel required to wear respirators;
- Medicine and alcohol can increase the effects from exposure to toxic chemicals. Personnel taking prescription drugs are required to notify EG&G Occupational Health and Safety, and the SSO. Alcoholic beverage intake will not be allowed on Rocky Flats Environmental Technology Site;
- All field personnel will wear occupational protective footwear to comply with ANSI Z41.1;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 45 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Any person who has a medical condition or allergy that could render them unconscious or result in a life-threatening situation will notify the Site Manager and the SSO and provide the appropriate response actions before beginning field work;
- Safety devices on equipment must be left intact and used as designed;
- Equipment and tools will be kept clean and in good repair and used only for their intended purpose. Operations and Maintenance manuals for equipment used as part of the Groundwater Monitoring Program shall be available at the subcontractor's Base Laboratory trailer;
- ANSI-approved safety glasses with side shields shall be worn in the exclusion zone and contamination reduction zone;
- Leather gloves must be worn when handling drums;
- Seat belts will be worn at all times while riding in a vehicle;
- Travel only on established roadways;
- Field laboratory type operations may not take place in the rear of the vehicle as the vehicle moves between sites; and,
- Drive slowly in the vicinity of the contractor facilities (5 mph maximum). When on site, park properly and within designated areas and watch for pedestrians and other vehicles.

**FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM**

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 46 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.6.2 Contamination/Exposure Prevention

On-site personnel may become contaminated by:

- Being splashed by contaminated liquids while sampling or handling liquids;
- Coming in contact with contaminated solids or liquids;
- Walking through contaminated materials, either in solid or liquid state;
- Being in contact with contaminated equipment;
- Being in contact with contaminated solid substances in waste piles or on the soil;
- Sitting or kneeling on the ground; and,
- Inhalation.

On-site team members will avoid becoming contaminated as much as possible. This will be accomplished by good work practices, as required by relevant SOPs, and by wearing Personal Protective Equipment (PPE), as described in Section 7.5.

On-site personnel will avoid exposure to hazardous chemicals by strictly adhering to the required personal protection equipment and decontamination procedures.

Care will be taken to prevent equipment damage from the elements or contamination as much as possible. Sampling and monitoring equipment will not be laid on contaminated surfaces. When decontaminating known radiologically-contaminated equipment, monitoring equipment and communication equipment may be bagged, with the bag taped and secured around the instrument. Openings will be made in the bag for sample intake and exhaust ports.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 47 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Surfaces will be considered radiologically contaminated if release limits for unrestricted use are exceeded. Release limits for unrestricted use are established in Rocky Flats Environmental Management Radiological Guidance (EMRG) 3.02. Currently, the release limits for unrestricted use are as set forth in the EMRGs.

6.6.3 On-Site Travel

All traffic regulations shall be observed. The following requirements will be observed at all times:

- Seat belt use is required when riding in any motorized vehicle;
- Authorized plant speeds will not be exceeded;
- A safe distance shall be maintained (a minimum of approximately three truck lengths) from the vehicle ahead, and the truck shall be kept under control at all times;
- The right of way shall be yielded to ambulances, fire trucks, or other vehicles in emergency situations;
- Under all travel conditions, the truck shall be operated at a speed that will permit it to be brought to a stop in a safe manner; and,
- No smoking is permitted in government-owned vehicles.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 48 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.6.4 Housekeeping

Housekeeping is an important aspect of an investigation program and will be strongly stressed in all aspects of field work. Good housekeeping plays a key role in occupational health protection and is a way of preventing dispersion of dangerous contaminants. All work areas will be kept as clean as possible at all times, and spills will be cleaned up immediately. Housekeeping will be the responsibility of all employees.

6.7 Personal Protective Equipment (PPE)

It is expected that there will be a tailoring of Personal Protective Equipment (PPE) requirements for specific sites and seasonal variations. Changes to PPE requirements established in this Health And Safety Plan shall be agreed upon by the On-site Project Manager and the SSO prior to review and approval for implementation by subcontractor HSO, Project Manager, and CHSO, and by the EG&G Project Manager, ERPD HSO, HS Liaison Officer, RE, and IH. A document authorizing such changes will be developed, dated, and signed by the On-site Project Manager and HSO. The SSO shall post PPE requirements in the crew trailer, announce changes and justification for those changes at a site safety meeting, and provide a copy of the change in PPE requirements to the HSO responsible for developing the Health And Safety Plan. Rocky Flats will publish a change to this plan if PPE changes are permanent and if the changes are considered substantive.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 49 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.7.1 Clothing

Personal protective equipment should be inspected before use. The following checks should be made before use:

- Determine that the clothing material is correct for the specific task at hand;
- Visually inspect for:
 - Imperfect seams;
 - Tears; and,
 - Malfunctioning closures.
- Hold up to light and check for pinholes.

During the work task, periodically inspect for the following:

- Evidence of chemical attack such as discoloration, swelling, stiffening, and softening. Keep in mind, however, that chemical permeation can occur without any visible effects;
- Closure failure;
- Tears;
- Punctures; and,
- Seam discontinuities.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 50 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.7.2 Protective-toe Footwear, Safety Glasses, and Hard Hats

Protective toe footwear requirements are identified in HSP 7.02, "Occupational Foot Protection." Appropriate footwear for Groundwater Monitoring Program activities are 16"-high steel toed boots as defined by ANSI Standard Z41.1. Safety glasses requirements are identified in HSP 7.01, "Eye and Face Protection Program," and include ANSI Standard Z87.1 safety glasses with site shields. Hard hats will comply with HSP 7.07, "Head Protection," satisfy ANSI Standard Z89.1, and be worn whenever overhead hazards are present.

6.7.3 Respirators

Respirators are to be inspected by looking for missing or damaged inhalation/exhalation valves, straps, buckles, and face shields, as well as their overall cleanliness. Respirators will be inspected according to an Rocky Flats-approved schedule established by the subcontractor, as outlined in Section 7.4.2.

6.8 Emergency Equipment

The following emergency equipment will be readily available at the subcontractor Base Laboratory trailer and in each field vehicle.

- First aid kit;
- Eye wash, 15 minute supply;
- Potable water, Gatorade™, or equivalent;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 51 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Fire extinguisher (10 lb. ABC); and,
- An extra full set of the appropriate PPE for each team member.

6.9 Temperature Stress

Temperature stress can be induced by both hot and cold environmental conditions.

6.9.1 Heat Stress

Heat stress is probably one of the most common illnesses experienced by outdoor workers wearing PPE. Health effects resulting from heat stress can range from transient heat fatigue to serious illness and death. Signs and symptoms of the stages of heat stress, presented in order of progression, are provide in the following paragraphs. This information is duplicated in Table 6-1 for easy reference.

Heat Rash

Heat rash may result from continuous exposure to heat or humid air. Signs of heat rash include reddening of the skin and increased sweating.

Heat Cramps

Heat cramps are caused by heavy sweating with inadequate electrolyte replacement. Signs and symptoms of heat cramps include muscle spasms and pain in the hands, feet, or abdomen.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 52 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Heat Exhaustion

Heat exhaustion occurs from increased stress on various body organs including inadequate blood circulation due to cardiovascular insufficiency or dehydration. Signs and symptoms of heat exhaustion include:

- Pale, cool, moist skin;
- Heavy sweating;
- Dizziness;
- Nausea; and,
- Fainting.

Heat Stroke

Heat stroke is the most serious form of heat stress. Temperature regulation fails and the body temperature rises to critical levels. Immediate action must be taken to cool the body before serious injury or death occur. Medical help must be obtained. Signs and symptoms of heat stroke include:

- Red, hot, usually dry skin;
- Lack of or reduced perspiration;
- Nausea;
- Dizziness and confusion;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 53 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Strong, rapid pulse; and,
- Coma.

Heat stress monitoring, as described in the following section, will assist in identify or preventing the progression of heat stress stages identified above.

6.9.2 Heat Stress Monitoring

A Wet Bulb Globe Temperature (WBGT) Instrument will be used to monitor employee exposure to heat stress condition, with the action level and work/rest regimen being based on the latest published values by the American Conference of Governmental Industrial Hygienists. Monitoring for heat stress will begin at 70 degrees Fahrenheit. Personnel should be alert for the signs and symptoms of heat stress, as described above and in Table 6-1.

Since measurement of deep body temperature is impractical for monitoring the employees' heat load, the measurement of environmental factors which most nearly correlate with deep body temperature and other physiological responses to heat is required. At the present time, WBGT Index is the simplest and most suitable technique to measure the environmental factors. WBGT values are calculated by the following equations:

- Outdoors with solar load:
$$WBGT = 0.7 \text{ NWB} + 0.2 \text{ GT} + 0.1 \text{ DB}$$

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 54 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Indoors or outdoors with no solar load:
WBGT = 0.7 NWB + 0.3 GT

where:

WBGT =	Wet Bulb Glove Temperature Index
NWB	= Natural Wet-Bulb Temperature
DB	= Dry-Bulb Temperature
GT	= Globe Temperature

The determination of WBGT requires the use of a black globe thermometer, a natural (static) wet-bulb thermometer, and a dry-bulb thermometer, such as the Reuter-Stokes Thermo-environmental Monitor. Calculated WBGT values will be compared to the permissible heat exposure limits provided in Table 6-2 (adapted from ACGIH 1993-1994 TLVs) and utilized to determine work/rest regimes, as described in the following paragraphs.

As previously stated, heat stress monitoring will begin when ambient air temperatures exceed 70°F. Heat stress will be monitored by checking Heart Rate during a 30 second period as early as possible in the rest period. If the heart rate exceeds 110 beats per minute or 75 beats per 30 seconds, the next work cycle will be shortened by one-third. Oral temperature will be taken with clinical thermometer (3 minutes under the tongue) at the end of each work cycle after appropriate documentation (before drinking water). If oral temperature exceeds 99.6°F, the next work cycle will be shortened by an additional one-third without changing the rest period. If at any time oral temperature exceed 100.4°F, work will be stopped and the person will not be allowed to work with impermeable PPE clothing such as Tyvek™.

Work schedules and work/rest schedules will be adjusted and modified according to monitoring requirements. Work slowdowns will be mandated as needed.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

**Manual:
Revision No.:**

RFP/ER-SAF-94-GMP

**Page:
Effective Date:**

**0
55 of 123**

Organization: Environmental Management

3/15/95

Personnel will be rotated to alternate job functions and minimize overexertion at one task. Additional personnel will be added to work teams as needed. Shelter will be provided during break periods; crew members may sit inside trucks with air conditioning going. Care will be taken to avoid shocking temperature extremes: workers will be instructed to gradually decrease temperature in air conditioned trucks at the initiation of break periods, and gradually increase the temperature before resuming work. Crew members will be required to drink plenty of water before going out into field and at break time. At lunch time, workers will be encouraged to salt their foods.

As many of the following control measures as are appropriate to site conditions shall be utilized to aid in controlling heat stress:

- Provide adequate liquids to replace lost body fluids and replace water and salt lost from sweating. Encourage personnel to drink more than the amount required to satisfy thirst. Thirst satisfaction is not an accurate indicator of adequate salt and fluid replacement;
- Replace fluids with water, commercial mixes such as Gatorade™ or Quick Kick™, or a combination of these;
- Establish a work regimen that will provide adequate rest periods for cooling down. This may require additional shifts of workers;
- Take all breaks in a cool rest area (approximately 77 degrees Fahrenheit);
- Remove impermeable protective garments such as Tyvek™ or Saranex™ during rest periods;
- Do not assign other tasks to personnel during rest periods; and,
- Inform personnel of the importance of adequate rest, acclimation, and proper diet in the prevention of heat stress.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 56 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.9.3 Cold Stress

Fatal exposure to cold among workers has almost always resulted from accidental exposures involving failure to escape from low air temperatures or immersion in low temperature water. The single most important aspect of life-threatening hypothermia is the fall in deep core temperature of the body. Employees should be protected from exposure to cold so that the deep core temperature does not fall below 97°F. Lower body temperature will very likely result in reduced mental alertness, reduction in rational decision making, or loss of consciousness with the threat of death. Adequate dry clothing must be provided to workers if work is to be performed in air temperatures below 40°F (4°C).

6.9.4 Cold Stress Monitoring

For exposed skin, continuous exposure should not be permitted when the air speed and temperature results in an equivalent chill temperature of 40°F (4°C). At temperatures of 36°F (2°C) or less, it is imperative that employees who become immersed in water or whose clothing becomes wet be immediately provided with a change of clothing and be treated for hypothermia. Special protection of the hands is required to maintain manual dexterity for the prevention of accidents.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 57 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Work Below 40 Degrees Fahrenheit (4°C) (including wind chill). Provisions for additional total body protection is required if work is performed at or below 40 degrees Fahrenheit as follows:
 - The employees shall wear cold-protective clothing appropriate for the level of cold and physical activity.
 - If the air velocity at the site is increased by wind or artificial ventilation, the cooling effect of the wind shall be reduced by wearing a removable outer windbreak garment.
 - If the clothing on the employee may become wet on the job site, the outer layer of the clothing used should be water repellent.
 - If the available clothing does not give adequate protection to prevent hypothermia or frostbite, work shall be modified or suspended until adequate clothing is made available or until weather conditions improve.
 - Employees handling evaporative liquids at temperatures below 4 degrees Celsius shall take special precautions to avoid soaking of clothing or gloves due to the added danger of cold injury due to the evaporative cooling.
- Work Below 10 Degrees Fahrenheit (-12°C) (including wind chill). For work practices at or below 10°F (-12°C), the following shall apply:
 - The worker shall be under constant protective observation (buddy system).
 - If work must be done, rest periods must be taken in heated shelters and opportunity for changing into dry clothing shall be provided.
 - New employees shall not be required to work full-time in cold the first few days until they become accustomed to the working conditions and required protective clothing.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual:
Revision No.:
Page:
Effective Date:
Organization:

RFP/ER-SAF-94-GMP

0

58 of 123

3/15/95

Environmental Management

- The work shall be arranged in such a way that sitting still or standing still for long periods is minimized.
- The workers shall be instructed in health and safety procedures.

6.9.5 Training

The training program for temperature stress shall include as a minimum, instruction in:

- Proper rewarming procedures and appropriate first aid treatment;
- Proper clothing practices;
- Proper eating and drinking habits;
- Recognition of impending frostbite;
- Recognition signs and symptoms of hypothermia or excessive cooling of the body even when shivering does not occur; and,
- Safe work practices.

6.10 Work During Darkness

This health and safety plan does not cover field work after daylight hours. Accordingly, no field work shall be conducted during darkness.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 59 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.11 Confined Space Work

No work in confined spaces or places with limited egress is permitted by this plan.

According to the final regulations from OSHA on confined spaces (29 CFR 1910.146), a "permit required" confined space is an enclosed space which:

- Is large enough and so configured that an employee can bodily enter and perform assigned work;
- Has limited or restricted means for entry and exit (e.g., tanks, vessels, silos, storage bins, hoppers, vaults, pits, and diked areas);
- Is not designed for continuous employee occupancy; and,
- Has one or more of the following characteristics:
 - Contains or has a known potential to contain a hazardous atmosphere
 - Contains a material with the potential for engulfment of an entrant
 - Has an internal configuration such that an entrant could be trapped or asphyxiated by inward converging walls, or a floor which slopes downward and tapers to a smaller cross-section
 - Contains any other recognized serious safety and health hazard

No confined spaces have been identified as work areas under this HASP. If additional sites are added, they will have to be evaluated for confined space entry requirements.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 60 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.12 Thunderstorms and Tornadoes

Meteorological conditions shall be closely watched, especially in the spring, when severe thunderstorms, lightning and tornadoes are most likely to occur. Thunderstorms, lightning and tornadoes often occur late in the afternoon on hot spring days, but can occur at any time of the day in any season of the year. Tornadoes are usually preceded by severe thunderstorms with frequent lightning, heavy rains, and strong winds.

A severe thunderstorm watch or a tornado watch announcement on the radio indicates that a severe thunderstorm or tornado is possible. Normally work will continue at the work site during severe thunderstorm watches or tornado watches. A severe thunderstorm warning or a tornado warning signifies that a severe thunderstorm or a tornado has been sighted or detected by radar and may be approaching. Normally, work on site shall cease during a severe thunderstorm warning or tornado warning. Decisions to cease work will be made after consultation between the SSO and the site manager. Emergency actions to be taken during a tornado are provided in Section 8.0. High wind warning levels, alarms, and responses are described in FO.01, "Air Monitoring and Dust Control," incorporated in this HASP by reference.

6.13 Hand Tools and Portable Power Tools

Hand tools are non-powered. They include anything from axes to wrenches. The greatest hazards posed by hand tools result from misuse and improper maintenance. Power tools can be hazardous when improperly used. There are several types of power tools, based on the power source they use: electric, pneumatic, liquid fuel, hydraulic, and power-actuated.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 61 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.13.1 General Requirements

- Hazardous moving parts must be covered/guarded if such parts are exposed to contact by workers. Safety guards will not be removed when a tool is being used;
- Keep all tools in good condition with regular maintenance;
- Use the right tool for the job;
- Examine each tool for damage before use;
- Operate according to the manufacturer's instructions;
- Provide and use the right protective equipment;
- Compressed air will not be used for cleaning purposes except where reduced to less than 30 pounds per square inch (psi) and then only with effective personal protective equipment;
- The use of compressed air for blowing dirt from hands, face, or clothing is prohibited; and,
- Liquid fueled tools will be shut off and allowed to cool before fuel is added.

6.13.2 Hand Tool Requirements

- All hand tools shall be in good repair and used only for the purpose for which designed;
- Tools having defects that will impair their strength or render them unsafe shall be removed from service;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 62 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- When work is being performed overhead, tools not in use shall be secured or placed in holders;
- Throwing tools or materials from one location to another, from one person to another, or dropping them to lower levels, shall not be permitted;
- Only nonsparking tools shall be used in locations where sources of ignition may cause a fire or explosion; and,
- Tools requiring heat treating shall be tempered, formed, dressed, and sharpened by personnel who are experienced in these operations.

6.13.3 Power Tool Requirements

- Rotating or reciprocating portable power tools shall be guarded with manufacturer provided guards;
- Power tools shall be inspected, tested, and determined to be in safe operating condition prior to use. Continued periodic inspections shall be made to ensure safe operating condition and proper maintenance;
- Rotating or reciprocating portable power tools shall have a constant pressure switch that will shut off the power when the tool is released by the operator. A portable power tool may have a lock-on control provided turn-off can be accomplished by a single motion of the same finger or fingers that turned it on;
- Loose and frayed clothing, loose long hair, dangling jewelry, rings, chains, and wrist watches shall not be worn while working with any power tool or machine;
- Never carry a tool by the cord or hose;
- Never yank the cord or the hose to disconnect it from the receptacle;
- Keep cords and hoses away from heat, oil, and sharp edges;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP

Revision No.: 0

Page: 63 of 123

Effective Date: 3/15/95

Organization: Environmental Management

- Disconnect tools when not in use, before servicing, and when changing accessories such as blades, bits and cutters;
- All observers should be kept at a safe distance away from the work area;
- Secure work with clamps or a vise, freeing both hands to operate the tool;
- Avoid accidental starting. The worker should not hold a finger on the switch button while carrying a plugged-in tool;
- Tools should be maintained with care. They should be kept sharp and clean for the best performance. Follow instructions in the user's manual for lubricating and changing accessories;
- Be sure to keep good footing and maintain good balance;
- The proper apparel should be worn. Loose clothing, ties, or jewelry can become caught in moving parts;
- All portable electric tools that are damaged shall be removed from use and tagged "Do Not Use";
- Electric tools must either have a three-wire cord with ground and be grounded or be double insulated. And, each electric tool used at the decontamination facility will have a ground-fault circuit interrupter placed in line between the tool and the power source; and,
- The pressurized steam cleaner at the decontamination facility shall be inspected prior to use for evidence of loose or frayed electrical connections, corroded or baking water connections, and fuel or oil leakage. The cleaner will not be used if any of these conditions exist; the conditions will be corrected prior to use. Care shall be taken when operating the steam cleaner, with special attention paid to hazards presented by high pressure and temperature. Operators shall be aware of burn and cut potentials associated with steam cleaner operation. Under no circumstances will the wand be pointed at any body part. Operators will be especially careful to avoid contacting extremities with the wash stream.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 64 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.14 Electrical Safety

The use of electrical energy always entails a potential for electrical shock. The use of electrical energy in a damp/moist environment such as outdoors during inclement weather or when processing water samples that could be spilled results in an increased potential for electrical shock. The following requirements will be implemented:

- All electrical wiring and equipment shall be a type listed by the Underwriters Laboratory (UL) or Factory Mutual Engineering Corporation (FM);
- Electrical wire or flexible cord passing through work areas shall be covered or elevated to protect it from damage by foot traffic, vehicles, sharp corners, projections, or pinching;
- Attachment plugs shall be constructed so that they will endure rough use and be equipped with a cord grip to prevent strain on the terminal screws;
- Flexible cord shall be used only in continuous lengths. Splicing of flexible cords is not permitted;
- Patched, oil soaked, worn, or frayed electrical cords shall not be used;
- Electrical cords will not be fastened with staples, hung from nails, or suspended by bare wire;
- Plugs and receptacles shall be of an approved submersible type;
- Ground fault circuit interrupters (GFCIs) are required in all circuits used for portable tools. GFCIs shall be trip tested before use (each day of use) by pressing the test button. If a test button is not present, the manufacturer instructions for testing will be followed;
- A ground strap will be used between the frame of portable generators and a grounding rod if required by the manufacturer. Grounding rods must be 5/8-inch

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 65 of 123
Effective Date: 3/15/95
Organization: Environmental Management

diameter steel or iron rods, 1/2-inch diameter copper clad steel, or 3/4-inch diameter galvanized pipe. They shall be in unbroken 8-foot lengths and driven to full depth;

- Grounding clamps/clips shall be attached before circuits are energized. A secure and positive metal-to-metal contact shall be made. Grounding clamps/clips shall not be removed until the circuits are de-energized;
- Weatherproof wiring shall be used. Receptacles shall be contained in a weatherproof enclosure the integrity of which is not affected when an attachment plug is inserted;
- Wiring used outdoors shall be hard usage or extra hard usage. Approved cords may be identified by the word "outdoor" or letters "WA" on the jacket;
- Flexible cords shall be connected to devices and fittings to provide strain relief to prevent pull from being transmitted to joints or terminal screws;
- Keep all electrical equipment and hands dry;
- Do not attempt to repair electrical equipment. Electrical equipment that fails will be disposed of or repaired by a qualified person;
- Never try to bypass any safety device on electrical equipment; and,
- In case of fire on or near any electrical equipment, use only a carbon dioxide or dry chemical fire extinguisher.

Emergency procedures for dealing with electrical shock are provided in Section 8.0.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 66 of 123
Effective Date: 3/15/95
Organization: Environmental Management

6.15 Laboratory Safety

6.15.1 Base Laboratory

Various analytical methods require that a preservative be added to the sample to be analyzed. These preservatives will be added to empty sample containers by the sample manager working in the Base Laboratory. Those preservatives being used are:

- Nitric Acid (HNO_3);
- Sulfuric Acid (H_2SO_4);
- Sodium Hydroxide pellets (NaOH);
- Sodium Thiosulfate granular ($\text{Na}_2\text{S}_2\text{O}_3$);
- Hydrochloric Acid (HCl);
- Ascorbic Acid powder ($\text{C}_6\text{H}_8\text{O}_6$); and,
- Zinc Acetate ($\text{Zn}(\text{C}_2\text{H}_3\text{O}_2)$).

Material Safety Data Sheets (MSDSs) for these preservatives will be retained on file in the subcontractor Base Laboratory trailer. Only those personnel directly involved in the process of adding the preservatives to the containers will be allowed in the properly ventilated clean room while this activity is being performed. No one shall handle preservatives while alone in the trailer. Preservatives will not be handled without the SSO being on site and knowledgeable that preservatives are being handled. All persons working with acids will wear chemical-resistant apron and gloves and Class III eye protection (chemical goggles and a face shield). Those responsible for dispensing the preservatives will be thoroughly trained by an experienced sample manager in the conduct of these operations, the safety aspects of the job, and in emergency procedures.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 67 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Sample containers made of glass require the wearing of protective eyewear whether they contain preservatives or not. All containers should be handled with protective gloves in order to prevent possible contamination of the container prior to sampling. Samples being brought in from the field for packaging and distribution will be handled only by personnel wearing protective eyewear and protective gloves.

Accuvactm reagent vials will be handled and disposed of according to SOP FO.21 (proposed).

6.15.2 General Safety

These general safety rules and precautions are applicable to all employees regardless of work areas. In addition to the general rules, employees who perform specialized jobs are to be thoroughly familiar with the safety rules pertaining to their unique tasks as outlined in the various sections.

- Warn a person in the immediate vicinity of unsafe conditions;
- No person shall proceed against or disregard any warning given by word of mouth, sign, or signal;
- Everyone is responsible for keeping his or her working place clean. Keep tripping hazards out of places where employees walk;
- Whenever stacking is part of your assigned task, it is your responsibility not only to stack material so that there is no danger of its falling, but also to stack it within prescribed areas allowing all aisles and work spaces to remain free;
- Always use the stair handrails and never jump from platforms, scaffolds, loading docks, or other elevations;

**FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM**

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 68 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Chemical labels shall be read and followed, particularly those which contain instructions in the use of the chemical to avoid harmful exposure to the employee;
- Employees must use a face shield when handling, pipetting, or pouring containers of acid, caustics, or other corrosive liquids;
- Eating or drinking in the laboratory areas is absolutely prohibited;
- At no time is a person to perform laboratory work while alone in the building;
- Never use mouth suction to pipette; a pipette bulb, or repeated use of a pipette will be used;
- Laboratory benches and aisles should not be used as storage areas;
- Fire extinguisher and eyewash fountains with 15-minute irrigation capacities are to be kept clear and readily accessible;
- Do not pick up broken glass with bare hands; use gloves or sweep it up. Fine glass particles should be picked up with wet paper towels; and,
- All preserved bottles will have full name or chemical formula written on the container.

6.15.3 Storage and Handling of Chemicals

- Generally, heavy items or large containers should be stored on or as near the floor as possible with smaller items and containers on the upper shelves;
- Chemicals which might react together to produce dangerous fumes, fire, or explosion must not be stored in the same container cabinet;
- Acids and bases should be stored separately in cabinets designed for such use;
- All containers must be labeled plainly;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 69 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- If exact information is not received with shipment of new or unfamiliar types and potencies of chemicals, request the manufacturer/supplier furnish a Material Safety Data Sheet (MSDS) with his recommendations before proceeding with laboratory use;
- When diluting acid, always pour the acid into water; never pour water into acid. Pouring water into acid may cause a reaction. In the case of field sampling, it has been determined that adding sample water to acid-prepared sample containers poses no significant risk, although care should be taken not to have sample containers and sample water near sampler's face during filling operations;
- Always flush or wipe down (with premoistened towelettes) the outside of acid bottles before opening them. Do not lay the stopper down on any surface where another person may rest his hand or arm. Keep acid bottles stoppered tightly, and flush and dry them before replacement on the reagent shelf. Make certain that no spillage remains on tables, floors, or bottles; and,
- Never carry open containers of dangerous chemicals from place to place; containers should always be covered or sealed.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 70 of 123
Effective Date: 3/15/95
Organization: Environmental Management

**7.0 SITE-SPECIFIC PERSONAL PROTECTIVE EQUIPMENT
REQUIREMENTS**

7.1 Introduction

This section describes the specific health and safety requirements of the Groundwater Monitoring Program operations. Activities conducted as regular part of the Groundwater Monitoring Program include water level measurements in wells and piezometers, well development, field measurement of groundwater field parameters, and groundwater sampling. Other, less common activities include packer tests, slug tests, and aquifer pumping tests. Procedures for the specific tasks are provided in the EMD Manual Operation Standard Operating Procedures (SOP) Groundwater (GW) guidance document. Additional procedures for general tasks are provided in the SOP Field Operations (FO) guidance document and include requirements for decontamination, instrument use, sample shipping, and other tasks. Described in the following sections are:

- Monitoring instruments utilized to detect the presence of radioactive and chemical substances potentially presenting a risk to human health and the environment;
- Outline monitoring strategies utilized by health and safety personnel;
- Explain personnel protective equipment (PPE) ensembles designed to protect field personnel from identified health risks; and,
- Provide specific information about personal protective equipment ensembles utilized while performing Groundwater Monitoring Program tasks as described in SOP GWs and FOs.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 71 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.2 Monitoring Instruments

7.2.1 Radioactive Substance Monitoring Instruments

Various instruments are used to monitor for the presence of radioactive substances on equipment and personnel conducting Groundwater Monitoring Program activities. The following instrumentation is used:

- A Bicron™ Field Instrument for the Detection of Low Energy Radiation (FIDLER) (or equivalent) is used to prescreen sites and monitor low level gamma radiation on PPE prior to disposal;
- A Ludlum™ Model 12-1A (or equivalent) is used to monitor alpha radiation on personnel exiting radiologically controlled areas (RCAs) or any other area of radiological concern;
- A Ludlum™ Model 31 (or equivalent) with a 44-9 "pancake" probe is used to monitor any beta or gamma radiation on personnel or sample coolers exiting RCAs or any other area of radiological concern;
- A Ludlum™ Model 2929 (or equivalent) is used to survey smear samples for alpha, beta, and gamma radiation contamination on various items for release to an unrestricted environment;
- A Bicron™ A-100 (or equivalent) is used to detect alpha contaminants during any survey of personnel or equipment; and,
- A Bicron™ B-50 (or equivalent) is used to detect beta contaminants during any survey of personnel or equipment.

The FIDLER is calibrated and source-checked by Rocky Flats Radiation Instrumentation (RI) on a 24-hour usage basis. All other instrumentation is calibrated and source-checked by the

FINAL HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 72 of 123
Effective Date: 3/15/95
Organization: Environmental Management

subcontractor HSS. Such calibration is approved and reviewed by RI or HPIC. Radiological instruments will be performance-checked against a radiation source of known radiation activity levels in accordance with the following schedule. All radiological instruments except the Ludlum™ 2929 are performance-checked by RI on a semiannual basis, or when calibration expires. The Ludlum™ 2929 is performance-checked on an annual basis by the manufacturer, or when calibration expires. All instruments except the FIDLER will be performance-checked, in accordance with EMRG 6.1, 6.3, 6.4, and 6.5, daily or when in use by the HSS.

A brief summary of EMRGs relevant to the use and operation of the radioactive substance monitoring equipment is provided in Section 7.3.1.

7.2.2 Chemical Substance Monitoring Instruments

Instruments utilized to monitor chemical substances include organic vapor detectors, colorimetric detector tubes, and combustible gas indicators:

- An HNU™ PA-101 (or equivalent such as a ThermoDynamic™ Organic Vapor Monitor or RAE Systems™ Mini-RAE) photoionization detector (PID) is utilized to detect organic vapors when opening well casings. The HNU™ is capable of ionizing compounds with an ionization potential of less than 11.27 eV (electron volts);
- Dräger™ colorimetric detector tubes (or equivalent) are utilized to detect the presence of and quantify volatile organic compounds of concern (see Table 5-1) in the event of positive readings observed during PID monitoring; and,
- A Bacharach™ Sentinel 44 (or equivalent) combustible gas indicator (CGI) is used to monitor oxygen and explosive gas concentrations in "methane wells" located in or near the site landfill.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 73 of 123
Effective Date: 3/15/95
Organization: Environmental Management

The use and operation of the PID is outlined in Field Operations guidance FO.15. The PID and the CGI are calibrated by the subcontractor HSS on a daily or as-needed basis.

7.3 Monitoring Strategies

The objectives of site monitoring are to provide a rational basis for the selection of appropriate levels of personal protective equipment and work practice controls, and to document and verify that the selected hazard control procedures are appropriate for actual site conditions.

Real-time monitoring activities conducted as part of the Groundwater Monitoring Program includes field screening of equipment and sample containers for the presence of radioactive substances. Additionally, wells are surveyed for the presence of volatile organic compounds (VOCs) inside the well casing prior to initiating any intrusive activities. Historical air monitoring data, as discussed in Section 7.4.2.2, will also be utilized to assess the potential for the presence of VOCs at well sites. Furthermore, the presence of explosive concentrations of gases is measured in "methane wells" located in or near the site landfill prior to initiating any intrusive activities. Health and safety practices to be utilized when conducting field screening are provided in the following subsections.

7.3.1 Monitoring for Radioactive Substances

Field screening for radioactive substances will be performed in accordance with appropriate Environmental Management Radiological Guidance (EMRG) documents. Detailed usage

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 74 of 123
Effective Date: 3/15/95
Organization: Environmental Management

methodologies and action levels are provided in the EMRGs. The HSS will maintain a set of current EMRGs to serve as ready reference; a listing of EMRGs is provided in Table 7-1.

Frequencies of radiological surveys will be determined by the subcontractor HSS in consultation with Radiological Engineering (RE), and in accordance with EMRG 3.1, EMRG 3.2, and HSP 18.01.

7.3.2 Monitoring for Chemical Substances

Real-time air monitoring will be conducted with the photoionization detector (PID) to provide an indication of potential volatile organic compound (VOC) hazards. Historical air monitoring data, as discussed in Section 7.4.2.2, will also be utilized to identify the potential for the presence of VOCs. The PID will be used as a screening device while performing activities having a reasonable potential for exposure to organic vapors, such as opening groundwater monitoring well casings. If levels of organic vapors above background levels are detected, Dräger™ colorimetric detector tubes (or equivalent) will be utilized to assist in the identification and quantification of the specific compounds. The results of the monitoring will be compared to action levels to determine the appropriate level of PPE according to the decision logic provided in Section 7.4.2.2. Action levels for chemical substances are discussed in Section 7.4.2.3 and provided in Table 7-2. The following paragraphs describe monitoring strategies used for detecting chemical substances. The reader is instructed to refer to Section 7.4.3 for definitions of PPE ensembles.

Field personnel will follow the monitoring procedures detailed below when opening well casings prior to conducting any intrusive activities. Available data will be reviewed for information about

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 75 of 123
Effective Date: 3/15/95
Organization: Environmental Management

potentially hazardous VOCs associated with the well. Data may be obtained from the previous laboratory analytical results, if prior sampling and analysis has been conducted. If no data is available, the "worst case" scenario will be assumed.

7.3.2.1 Photoionization Detector Monitoring

PID monitoring will be conducted only with a PID utilizing a lamp of at least 11.7 eV. Field personnel will verify the use of correct lamp prior to any monitoring.

The well will be approached from upwind while wearing Level D PPE and conducting continuous air monitoring with the PID. The well casing will be opened the minimum amount necessary to insert the PID probe and conduct headspace monitoring. Positive headspace readings will require immediate breathing zone monitoring. If PID readings indicate that breathing zone VOC levels are at or below background readings, work may proceed. Breathing zone VOC concentrations above background levels will warrant the workers exiting the work zone, contacting the HSS, and conducting colormetric detector tube monitoring for compounds of concern if requested, as described below.

7.3.2.2 Colormetric Detector Tube Monitoring

The following volatile organic compounds of concern have been identified as reasonably anticipated to be present:

- Benzene;
- Carbon Tetrachloride;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 76 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Chloroform;
- 1,1-Dichloroethene (vinylidene chloride);
- Methylene Chloride;
- Tetrachloroethane; and,
- Vinyl Chloride.

Colormetric detector tube monitoring will be conducted if requested by the HSS in order to verify or eliminate the presence of these compounds. Readings at concentrations which exceed action levels presented in Section 7.4.2.3 for these compounds will require workers to exit the work zone. Workers will contact the HSS for instruction on the procedures to follow. The HSS, at his discretion, may elect to either allow the well to vent, with periodic monitoring to measure VOC and compound of concern concentrations, or require workers to conduct activities in Level C respiratory protection. In no case will the HSS require Level C work if concentrations of compounds of concern exceed maximum use concentrations for air purifying respirators. The presence of compounds with poor warning qualities, such as benzene, carbon tetrachloride, methylene chloride, chloroform, or vinyl chloride, will require the utilization of Level B respiratory protection. Level C (or lower) respiratory protection may not be utilized in the presence of these compounds. If such conditions exist, the well will be allowed to vent until concentrations less than maximum use concentrations are attained prior to continuation of work at that site.

7.3.2.3 Combustible Gas Indicator Monitoring

When conducting Groundwater Monitoring Program activities at "methane wells" in or near the site landfill, the combustible gas indicator (CGI) will be utilized to measure the presence of explosive

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 77 of 123
Effective Date: 3/15/95
Organization: Environmental Management

gases in the well casing and breathing zone. The CGI measures percent oxygen and percent of lower explosive limit (LEL) of explosive gases, relative to a methane gas calibration standard. The presence of explosive gases in excess of 25% of the LEL will require field crews to allow the well to vent, to ensure that all equipment utilized in the immediate vicinity of the well is intrinsically safe, and that no potential ignition sources are located near the well.

It should be noted that oxygen-deficient atmospheres, such as those potentially encountered in the "methane wells," may adversely affect the performance of the CGI. Accordingly, the percent of oxygen concentration in the well should be measured prior to measurement of explosive gas concentrations. Oxygen concentrations less than 19.5% may render LEL readings invalid.

Intrusive tasks conducted at the "methane wells" are to be conducted only when local wind speed exceeds 15 miles per hour. Field crews will measure local wind speed with a handheld anemometer when conducting activities at "methane wells." If local wind speed drops below 15 miles per hour, work at that site will be terminated and resume only when the minimum threshold is reached. Only intrinsically safe instruments will be used in the methane wells. A PID and CGI will be utilized to monitor air quality in the "methane wells" and the worker breathing zones.

7.4 Personal Protective Equipment

Personal Protective Equipment (PPE) comprises the "last line of defense" against health hazards, following engineering controls and good work practices. Engineering controls are not applicable to intrusive activities conducted as part of the Groundwater Monitoring Program. Good work

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 78 of 123
Effective Date: 3/15/95
Organization: Environmental Management

practices are identified in appropriate SOP GWs and FOs. PPE for Groundwater Monitoring Program activities consists of clothing to protect the workers from physical, radiological, or chemical hazards, and respiratory protection to reduce or eliminate the potential for inhalation of hazardous substances.

The following subsections describe general PPE clothing and respirator requirements for Groundwater Monitoring Program operations. PPE ensembles (complementary clothing and respirator requirements) are outlined in Section 7.4.3. PPE requirements for Groundwater Monitoring Program tasks are provided in Section 7.5.

7.4.1 Clothing

PPE clothing consists of items designed to protect the worker from physical, radiological, and chemical hazards. The basic field work uniform consists of Department of Energy (DOE) cotton coveralls, steel-toed work boots, and safety glasses. Cotton surgical "scrubs" may be worn as an alternative to DOEs. A personal radiation dosimetry badge will be worn when conducting any RCA activities. Hard hats are to be worn in situations presenting a potential hazard from falling objects, and leather gloves may be warranted for activities with the potential for cuts or puncture wounds to the hands.

Upgrading the basic uniform will provide additional protection from dust and liquid hazards. Disposable chemical-resistant coveralls, such as Tyvek™ or equivalent, protect the worker from skin contact with airborne contaminants. If a splash hazard is present, the coveralls may be further upgraded to a coated material such as Saranex™ or equivalent. Alternatively, splash protection may be afforded by wearing an apron.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 79 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Hand, foot, and face protection may be similarly upgraded. Surgical rubber inner gloves, possibly combined with nitrile or butyl outer gloves, provide hand protection from dust or liquid chemical hazards. Foot protection may be upgraded with chemical-resistant boots. The face may be protected from splash hazards by a face shield or a full-face respirator.

It should be noted that coverall sleeves and legs will be worn over or under the cuffs of gloves and boots depending on the specific hazard presented by a given task. If a splash hazard exists, sleeves and pant legs will be worn outside gloves and boot covers. If a dust hazard is present, the coverall sleeves and pant legs will be worn inside glove cuffs and boot covers. Tape will be used to seal the joints between coveralls, protective gloves, and cuffs.

7.4.2 Respirators

Respirators provide workers with protection from the inhalation of hazardous substances.

Respiratory protection at Rocky Flats includes half- or full-face air-purifying respirators (APR), and self-contained breathing apparatus (SCBA) or supplied-air line with escape SCBA. For Groundwater Monitoring Program operations, respiratory protection is generally not necessary unless air monitoring, as described above, indicates that respiratory protection is required. A full-face respirator with organic vapor/acid gas and radionuclide cartridges will be utilized if air monitoring indicates that action levels for compounds of concern (listed in Table 7-2) are exceeded.

APRs will be maintained in accordance with a Rocky Flats-approved Respiratory Protection Program maintenance schedule. Respirators will be inspected on a semi-annual basis at a minimum. If used as part of an Emergency Response program, respirators will be inspected on a

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 80 of 123
Effective Date: 3/15/95
Organization: Environmental Management

monthly basis at a minimum. The respirations shall be stored properly: in a sealed plastic bag, facedown, and not stacked.

Before being taken in the field, each APR will be inspected, appropriate cartridges installed, a positive and negative pressure check conducted, and the entire APR assembly will be sealed in a plastic bag. The APR will remain in the sealed bag until needed. If the APR is not used and the sealed bag is not damaged, the respirator may remain at the work site inside an area protected from weather. The enclosed cab of a vehicle is considered to be one example of a protected area.

After the APR has been used, the following cleaning and maintenance procedures will be followed:

- Cartridges from the APR will be removed and disposed of as contaminated PPE weekly, or whenever monitoring indicates that the cartridges have been exposed to concentrations of contaminants above Permissible Exposure Limits (PELs);
- The APR interior and exterior will be wipe-tested for radioisotopes before being cleaned if radioactivity was detected while the APR was being used or whenever crew members exit on RCA. If the wipe test indicates the presence of radioactivity, EMRG 2.2 will be consulted for appropriate procedures to be utilized in response to potential inhalation of radioactive materials. The APR will be thoroughly cleaned with premoistened towellettes and wipe-tested again. The used towellettes will be disposed of as contaminated PPE;
- If the second wipe test indicates the presence of radioactivity, the APR will be sealed in a plastic bag, the bag will be labelled to indicate the presence of radioactivity on the APR, and the SSO notified. APRs found to be radiologically contaminated will not be placed in the cleaning and rinse solutions at the shower trailer;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 81 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- For APRs not exposed to radiological contamination, the APR facepiece interior and exterior will be wiped down with premoistened towellettes and subsequently sealed in a plastic bag for transport to the APR cleaning station at the shower trailer; and,
- After the APR has been cleaned and rinsed, it will be dried with a clean towel and stored in a clean, sealed plastic bag.

7.4.2.1 Respiratory Protection Program

Personnel performing tasks which require respiratory protection will be trained and fitted for respirators in accordance with a Rocky Flats-approved Respiratory Protection Program.

Subcontractors may either submit their own Respiratory Protection Programs for Rocky Flats approval or comply with the Rocky Flats Respiratory Protection Program provided in HSP 1-G2200-HSP-7.03. Subcontractors are responsible for ensuring that their employees comply with their respiratory program. Each individual is responsible for the cleaning, inspection, maintenance, and storage of any APR they use.

7.4.2.2 Respirator Decision Logic

The decision to wear respiratory protection is based on the potential for hazardous constituents to be present in the breathing zone of the worker. Situations with a known potential for the presence of such constituents, such as intrusive activities at wells with a previous history of compound of concern concentrations above permissible exposure limits in the breathing zone, require respiratory protection while conducting real-time monitoring with an PID. Other situations, such as intrusive activities at wells which have not yet been characterized by an analytical laboratory and are in locations reasonably anticipated to high concentrations of compounds of concern, have an

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 82 of 123
Effective Date: 3/15/95
Organization: Environmental Management

unknown potential for the presence of airborne hazardous constituents and may require respiratory protection. Finally, some situations have no potential for the presence of airborne hazardous constituents and require no respiratory protection. Situations with no potential for the presence of airborne hazardous constituents include well casing headspace and breathing zone analysis for wells with no history or reasonable likelihood of contamination, such as those located in the Buffer Zone.

Each of these situations requires a different response by the field worker. The field worker, in conjunction with the HSS, will utilize the monitoring strategies presented in Section 7.3 to determine appropriate respiratory protection.

Historical data detailing air monitoring results for well casing and breathing zone surveys are provided in Appendix E. These data will be utilized during pre-sampling planning to determine appropriate respiratory protection levels for each sampling location.

The data provided in Appendix E were obtained by air monitoring with a PID. In accordance with the action levels presented in Table 7-2, any well listed as exhibiting PID readings above background should be approached from upwind while monitoring air quality with colormetric detector tubes, following procedures outlined in Section 7.3.2.2.

7.4.2.3 Respirator Action Levels

Real-time air monitoring, as described in Section 7.3, will provide field workers with information necessary to determine appropriate respiratory protection. Certain threshold values have been established for particular compounds; the exceedance of these values requires a specific action.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 83 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Accordingly, these values are termed "action levels." Action levels have been set requiring the upgrade from no respiratory protection (Level D and Modified Level D) to APRs (Level C).

Action levels for radioisotopes are defined in EMRGs 3.1 and 3.2; action levels for organic compounds have been set at one half of the permissible exposure limits (PELs) for specific compounds as set by OSHA.

PIDs respond to various compounds according to the calibration standard for the instrument, the power of the instrument, and the compound's ionization potential. Because PIDs provide only a qualitative measure of the presence of volatile organic compounds, action levels for PID instrument use have been set at any reading in the breathing zone above background. The required action when this level is attained is to relocate upwind of the source, allow the well to vent, contact the HSS, and, if requested, conduct colormetric detector tube monitoring. Colormetric detector tubes provide quantitative data about concentrations of particular compounds of concern. Action levels for volatile organic compounds of concern are provided in Table 7-2.

7.4.3 Personal Protective Equipment Ensembles

PPE ensembles consist of certain clothing and respiratory protection elements which, in combination, protect the wearer against certain physical, radiological, and chemical hazards. Established PPE ensembles are summarized below; it should be noted that each ensemble may be modified slightly by task-specific requirements to address particular hazards associated with that task. Task-specific PPE requirements are provided in Section 7.5 and summarized in Table 7-3.

**FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM**

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP

Revision No.: 0

Page: 84 of 123

Effective Date: 3/15/95

Organization: Environmental Management

7.4.3.1 Level D

Level D PPE is worn while performing tasks with little or no potential for exposure to contaminants. It is the basic work uniform.

Level D PPE consists of:

- Rocky Flats-provided Department of Energy (DOE) cotton coveralls, to be changed daily;
- Minimum 16"-high steel-toed boots;
- Safety glasses with side shields or equivalent;
- Additional seasonal items, as necessary;
- Leather gloves (when handling sharp objects); and,
- Hard hat if an overhead hazard is present.

It should be noted that if a dust hazard is present in an RCA-environment, PPE should be upgraded to Level C if exposure limits established in EMRG 3.1 and 3.2 for radioactive materials are exceeded.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 85 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.4.3.2 Modified Level D

Modified Level D PPE represents an upgrade of Level D PPE to address possible skin contact with contaminants. Modified Level D PPE is to be worn when conducting tasks with the potential for splash or dust exposure to hazardous constituents, but when no respiratory protection is necessary.

Modified Level D PPE consists of Level D PPE and the following additional items:

- Disposable chemical-resistant gloves (nitrile or equivalent);
- Minimum 16"-high steel-toed, steel shank boots;
- Uncoated chemical-resistant disposable coveralls (Tyvek™ or equivalent) or coated chemical-resistant disposable coveralls (Saranex™ or equivalent);
- Coverall sleeves and legs will be worn over or under the cuffs of gloves and boots depending on the specific hazard presented by a given task. If a splash hazard exists, sleeves and pant legs will be worn outside gloves and boot covers. If a dust hazard is present, the coverall sleeves and pant legs will be worn inside glove cuffs and boot covers. Tape will be used to seal the joints between coveralls, protective gloves, and cuffs; and,
- Additional seasonal items, as necessary. Any such items will be worn under the disposable coverall.

It should be noted that if a dust hazard is present in an RCA-environment, PPE should be upgraded to Level C if exposure limits established in EMRG 3.1 and 3.2 for radioactive materials are exceeded.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 86 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.4.3.3 Level C

Level C PPE provides protection from contaminants by using chemical-resistant coveralls and respiratory protection. Level C PPE is to be worn when conducting operations with the potential for exposure to airborne hazardous constituents requiring respiratory protection.

Level C PPE consists of:

- Rocky Flats-supplied DOE cotton coveralls to be changed daily;
- Uncoated chemical-resistant disposable coveralls (Tyvek™ or equivalent), or coated chemical-resistant disposable coveralls (Saranex™ or equivalent);
- Coverall sleeves and legs will be worn over or under the cuffs of gloves and boots depending on the specific hazard presented by a given task. If a splash hazard exists, sleeves and pant legs will be worn outside gloves and boot covers. If a dust hazard is present, the coverall sleeves and pant legs will be worn inside glove cuffs and boot covers. Tape will be used to seal the joints between coveralls, protective gloves, and cuffs;
- Disposable chemical resistant inner gloves (as necessary);
- Butyl or nitrile outer gloves;
- Minimum 16"-high steel-toed, steel shank boots;
- Full-face APR with appropriate high-efficiency particulate air (HEPA) cartridges that provide protection against organic vapors, acid gases, and radioisotopes; and,
- Additional seasonal items, as necessary. Any such items will be worn under the disposable coverall.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 87 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.5 Required Levels of Personal Protective Equipment Per Task

Tasks performed at or associated with Groundwater Monitoring Program activities are conducted in accordance with appropriate SOP GWs and FOs. A listing of SOP GWs and FOs relevant to Groundwater Monitoring Program operations is provided in Table 7-3. Any task performed by the subcontractor not listed in Table 7-3 may be considered a special circumstance and require consultation with the HSO and EG&G PM to identify health and safety issues associated with the task. As described in Section 7.5.23, special circumstances will require preparation of a task-specific Health and Safety Plan by the subcontractor HSO.

This section briefly outlines activities associated with each task, and identifies PPE requirements to perform those activities. PPE requirements for each task are also presented in Table 7-3. In all cases where air monitoring is required, the monitoring strategies provided in Section 7.3 will be utilized prior to initiation of intrusive activities. Additionally, in all cases where intrusive activities involving designated "methane" wells, the monitoring strategies provided in Section 7.3.2.3 will be followed.

7.5.1 SOP GW.1: Water Level Measurements in Wells and Piezometers

Task Description

The Groundwater Monitoring Program subcontractor conducts water level measurements in site monitoring wells and piezometers on a scheduled basis. Air monitoring is conducted prior to water level measurement. Water level measurement consists of placing an electronic water level probe in the well and recording the depth to water based on an audible alarm which sounds when the probe contacts the water surface. The measurement is recorded on the appropriate field data form.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

**Manual:
Revision No.:
Page:
Effective Date:
Organization:**

RFP/ER-SAF-94-GMP

0

88 of 123

3/15/95

Environmental Management

Refer to Section 7.3.2.3 for information on conducting water level measurements in "methane" wells.

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

In general, performing this task requires the use of Level D PPE with nitrile or butyl gloves. Consult the radiation work permit (RWP) for PPE requirements when conducting in water level measurements in wells or piezometers in RCAs or any other areas with known radiological contamination, such as IHSSs.

7.5.2 SOP GW.2: Well Development

Task Description

Well development is undertaken on new wells to remove drilling fluids and mobile particulates, and on old wells to remove sediment, from the water column in the well. Water level measurement in accordance with SOP GW.1 is performed, and groundwater is evacuated from the well using a bailer or inertial pump. Recovered groundwater is retained in a graduated container to measure quantity, transferred to a tank in the field vehicle, and transported to the Main Decontamination Facility (MDF) for disposal.

Refer to Section 7.3.2.3 when conducting well development in "methane" wells.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 89 of 123
Effective Date: 3/15/95
Organization: Environmental Management

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

In general, Level D PPE with nitrile or butyl gloves will be worn when conducting well development activities. Consult the radiation work permit (RWP) for PPE requirements when conducting well development in RCAs or any other areas with known radiological contamination.

7.5.3 SOP GW.3: Pump-in Borehole Packer Testing

Task Description

Pump-in borehole packer testing is occasionally utilized at Rocky Flats to evaluate aquifer characteristics such as hydraulic conductivity. Associated tasks include SOP GW.1. Three types of packer tests are used: constant head, constant rate of flow, and pressure pulse tests. Each of these tests require placing the packer in an open borehole, inflating the packer, and monitoring measurements of water levels or pressure differentials as stress is induced on a portion of the borehole.

Refer to Section 7.3.2.3 when conducting packer testing in "methane" wells.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 90 of 123
Effective Date: 3/15/95
Organization: Environmental Management

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

In general, PPE appropriate for conducting pump-in borehole packer testing consists of Level D with nitrile or butyl gloves. Consult the radiation work permit (RWP) for PPE requirements when conducting pump-in borehole packer tests in RCAs or any other areas with known radiological contamination.

7.5.4 SOP GW.4: Slug Tests

Task Description

Slug tests are occasionally performed in site monitoring wells and piezometers to measure the rate of water level recovery in the well. Associated tasks include SOP GW.1. The procedure involves the introduction of a solid slug into the standing water column in the well while simultaneously measuring water levels during the period of recovery to static conditions.

Refer to Section 7.3.2.3 when conducting slug tests in "methane" wells.

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 91 of 123
Effective Date: 3/15/95
Organization: Environmental Management

In general, slug tests will be performed in Level D PPE with the addition of nitrile or butyl gloves. Consult the radiation work permit (RWP) for PPE requirements when conducting slug tests in RCAs or any other areas with known radiological contamination.

7.5.5 SOP GW.5: Field Measurement of Groundwater Field Parameters

Task Description

Field crews are required to measure certain chemical and physical characteristics of groundwater during well development and purge activities. Associated tasks include SOP GW.1 and SOP GW.2. These characteristics include temperature, pH, specific conductance, nitrate, and turbidity. Field crews measure these parameters at established volumetric intervals using field instruments such as the Hach DR2000 Spectrophotometer (or equivalent).

Refer to Section 7.3.2.3 when conducting field measurement of groundwater field parameters in "methane" wells.

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

In general, field measurement of groundwater field parameters shall be conducted in Level D PPE. Consult the radiation work permit (RWP) for PPE requirements when conducting field measurement of groundwater field parameters in RCAs or any other areas with known radiological contamination.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 92 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.5.6 SOP GW.6: Groundwater Sampling

Task Description

Groundwater sampling is the primary task of the Groundwater Monitoring Program subcontractor. Associated tasks include SOP GW.1, SOP GW.2, and SOP GW.5. The wells are purged and samples collected with bailers and a hand reel system.

Refer to Section 7.3.2.3 when conducting groundwater sampling in "methane" wells.

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

In general, groundwater sampling will be conducted in Level D PPE with the addition of nitrile or butyl gloves. Consult the radiation work permit (RWP) for PPE requirements when conducting groundwater sampling in RCAs or any other areas with known radiological contamination.

7.5.7 SOP GW.8: Aquifer Pumping Tests

Task Description

Step-drawdown and constant rate discharge pumping tests are performed in well points and completed wells. Aquifer pumping tests are performed by pumping wells at fractions of full capacity while varying pumping rates in a time step fashion, and/or pumping at a constant rate.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 93 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Water levels are simultaneously measured in the production well or nearby observation wells.

Water level measurements are conducted in accordance with SOP GW.1.

Refer to Section 7.3.2.3 when conducting aquifer pumping tests in "methane" wells.

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

In general, aquifer pumping tests will be conducted in Level D PPE with the addition of nitrile or butyl gloves. Consult the radiation work permit (RWP) for PPE requirements when conducting aquifer pumping tests in RCAs or any other areas with known radiological contamination.

7.5.8 SOP FO.01: Air Monitoring and Dust Control

Task Description

Air monitoring and dust control activities are generally not conducted by the Groundwater Monitoring Program subcontractor. However, intrusive activities conducted at "methane wells" in the vicinity of the site landfill are to be conducted only when wind velocity exceeds 14 miles per hour. A hand-held anemometer will be utilized by field crews to verify wind speed prior to conducting intrusive activities at these locations.

**FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM**

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 94 of 123
Effective Date: 3/15/95
Organization: Environmental Management

PPE Requirements

At a minimum, Level D PPE is required for this task.

7.5.9 SOP FO.02: Transmittal of Field QA Records

Task Description

Field QA records must be properly completed, authenticated, and provided with a unique identification number. A package of QA records is to be transmitted to the responsible EG&G project manager at least once every seven days. This task is conducted in the subcontractor Base Laboratory.

PPE Requirements

At a minimum, Level D PPE is required for this task.

7.5.10 SOP FO.03: General Equipment Decontamination

Task Description

General equipment decontaminated in the field and at the Main Decontamination Facility (MDF) consists of sampling and monitoring equipment utilized by the field crews. Decontamination activities will be conducted in accordance with the Decontamination Facility HASP. Procedures to conduct equipment decontamination depend upon the specific piece of equipment, the location in which the equipment was used, and the location where the decontamination activity is conducted.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 95 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Procedures to conduct general equipment decontamination include the following steps:

- Prior to arriving at the MDF, the user will conduct a pre-decontamination radiological survey for alpha, beta, and gamma contamination, including an equipment frisk and a smear sample for removable contamination. Additionally, the user will conduct an organic vapor monitoring survey with an Organic Vapor Detector;
- Survey results will be reviewed by the Decontamination Facility Subcontractor (DFSC) and user HSSs for elevated levels of contamination (above EMRG 3.1 guidelines for radiological parameters or above action levels provided in Table 7-2 for organic vapors). RE and/or IH will be notified if elevated levels are identified;
- If the equipment to be decontaminated originates in an RCA, an RWP will be developed and the MDF will be posted as an RCA during decontamination activities. If the equipment does not originate from an RCA, no special posting is required unless directed by RE;
- Following acceptance of survey results, the equipment will be decontaminated by the user, using the pressurized steam cleaner. General procedures for equipment decontamination require removal of residual contaminants, placement of the equipment on the wash rack with open end down (if applicable), and standing upwind or crosswind of the equipment while using the steam cleaner. The equipment is to be placed in a clean area to air dry, or the equipment is dried using disposable towels;
- The DFSC or user HSS will conduct a post-decontamination radiological survey of the equipment if radiological contamination was detected prior to decontamination; and,

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 96 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- The DFSC or user HSS will conduct a post-decontamination radiological survey of the MDF if the MDF was posted as an RCA or radiological contamination was detected on equipment prior to decontamination, and provide the results to the DFSC HSS.

PPE Requirements

In general, PPE required for field decontamination consists of Level D with the addition of nitrile or butyl gloves. Consult the radiation work permit (RWP) for PPE requirements when conducting field general equipment decontamination in RCAs or any other areas with known radiological contamination.

For decontamination activities at the MDF, PPE utilized to conduct the pre- and post-decontamination radiological surveys consists of Level D. If the radiological frisk identifies contamination above EMRG 3.1 or 3.2 limits, the survey will be temporarily discontinued and the MDF posted as an RCA. Level C PPE will be donned and the survey completed.

PPE utilized while performing decontamination activities at the MDF is comprised of Modified Level D, with coated disposable chemical-resistant coveralls such as Saranextm or equivalent. Additionally, a faceshield and nitrile or butyl gloves will be worn. PPE may be upgraded to Level C if the MDF is designated as an RCA.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 97 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.5.11 SOP FO.05: Handling of Purge and Development Water

Task Description

Purge and development water originating from groundwater monitoring wells is collected in buckets during purge and development activities at each well. Water is transferred to a holding tank in the field vehicle, and transported to the MDF for disposal in the MDF sedimentation tanks. The water is transferred into the sedimentation tanks by the field crew and the MDF subcontractor through a pump and purge hose.

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

In general, PPE requirements for collection of purge and development water at each well location consists of Level D PPE. Consult the radiation work permit (RWP) for PPE requirements when handling purge and development water in RCAs or any other areas with known radiological contamination.

PPE requirements for purge and development water transfer operations is comprised of Level D PPE with the addition of ear plugs (when using a gasoline-powered pump), nitrile or butyl gloves, and a splash apron.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 98 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.5.12 SOP FO.06: Handling Personal Protective Equipment

Task Description

PPE generated from Groundwater Monitoring Program operations is disposed of at the subcontractor Base Laboratory. PPE disposal requirements vary according to whether the PPE is radiologically contaminated or not. When the container is full, the subcontractor HSS will conduct a Bicron™ Frisk-tech survey of the PPE. If the PPE is identified as contaminated or potentially contaminated, RE will be notified and the subcontractor will dispose of the PPE according to RE guidelines. If the results of the FIDLER gamma survey indicate that the PPE is not radiologically contaminated, the PPE will be disposed of as uncontaminated material. Disposal for uncontaminated PPE consists of placing the PPE in double plastic bags, sealing the bags, labelling them as uncontaminated PPE, and transferring the PPE to Rocky Flats Environmental Operations Personnel.

PPE Requirements

PPE to be utilized for handling used PPE consists of Level D with nitrile or butyl gloves.

7.5.13 SOP FO.07: Handling of Decontamination Water and Wash Water

Task Description

Water generated from decontamination and wash activities is disposed of at the MDF. Water may be generated from field activities or from MDF pad activities. The water flows to or is placed in

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 99 of 123
Effective Date: 3/15/95
Organization: Environmental Management

the MDF sump, and is pumped through the separators to Sedimentation Tank 1. Subsequent handling of decontamination water and wash water is conducted by the MDF operator.

PPE Requirements

PPE required for handling decontamination and wash water consists of Level D with the addition of ear plugs (when using a gasoline-powered pump), nitrile or butyl gloves, and a splash apron. Consult the radiation work permit (RWP) for PPE requirements when handling decontamination water or wash water in RCAs or any other areas with known radiological contamination.

7.5.14 SOP FO.11: Field Communications

Task Description

Field crews will utilize the buddy system, and radio communication is required. Knowledge of audible alarms, as described in Section 8.4, is required. Hand signals may be appropriate in high noise situations. LS/DW (Life Safety/Disaster Warning) announcements will be relayed via radio to field crews by their supervisor.

PPE Requirements

At a minimum, Level D (standard work uniform) will be worn when conducting field communications.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 100 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.5.15 SOP FO.12: Decontamination Facility Operations

Task Description

General equipment and heavy equipment decontamination activities not conducted in the field are performed at the Main Decontamination Facility (MDF) or Protected Area Decontamination Facility (PADF). Decontamination operations at either facility require pre- and post-decontamination radiological surveys by an HSS. Decontamination operations will be performed in accordance with FO.3 and FO.4 requirements, and in accordance with the requirements of the Decontamination Facility HASP.

PPE Requirements

PPE requirements for Groundwater Monitoring Program personnel conducting FO.12 tasks includes Level D clothing with butyl or nitrile gloves, and ear plugs. If actual decontamination activities requiring the use of the steam cleaner will be performed, Modified Level D PPE is required. Respiratory protection will be upgraded according to RWP requirements if the Decontamination Facility is designated as an RCA.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 101 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.5.16 SOP FO.13: Containerization, Preserving, Handling and Shipping of Soil and Water Samples

Task Description

Groundwater samples are preserved by the placement of liquid preservatives in the bottles prior to sample collection. Placement of the preservative is performed in the subcontractor preservative room laboratory. The preservative room is ventilated with a positive-pressure blower. A pipette is used to place the preservative in the bottle.

Groundwater samples collected from monitoring wells are shipped to analytical laboratories for analysis. Samples are collected from the monitoring wells, placed in appropriate sample bottles, and the bottles are placed in a shipping cooler. The exteriors of the bottles and the shipping cooler are surveyed for radiological contamination and decontaminated as necessary. Sample bottle and cooler handling includes a direct frisk and swipe sample radiological survey for alpha, beta, and gamma contamination. The sample bottles and coolers are decontaminated as necessary; the bottles are placed in sealed plastic bags, and shipped in a sealed cooler. Water used for decontaminating bottle and cooler exteriors is disposed in the MDF sump. At no time will sample bottles or coolers be shipped prior to the HSS determination, through radiological survey, that EMRG 3.1 and 3.2 limits have not been exceeded. Shipped samples will have a PRE and Transfer tag.

Shipping requirements for soil and water samples includes preparation of appropriate paperwork and assurance that the shipment is in compliance with relevant DOT shipping regulations.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 102 of 123
Effective Date: 3/15/95
Organization: Environmental Management

PPE Requirements

In general, water sample containerizing and handling will be conducted in Level D PPE with nitrile or butyl gloves. Refer to Section 7.5.6, "SOP GW.6: Groundwater Sampling," for additional details on PPE requirements when containerizing and handling water samples.

Sample preservation PPE requirements consist of Level D with nitrile or butyl gloves, a splash apron, and a faceshield.

At a minimum, Level D PPE is required when shipping sample containers.

7.5.17 SOP FO.14: Field Data Management

Task Description

Field data management is comprised of data entry into the Rocky Flats Environmental Data System (RFEDS). This task is an office activity conducted by the subcontractor.

PPE Requirements

An office work uniform is appropriate for this task; no special PPE is required.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 103 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.5.18 SOP FO.15: Photoionization Detectors (PID) and Flame Ionization Detectors (FID)

Task Description

Photoionization Detectors (PIDs) are used by the Groundwater Monitoring Program subcontractor when conducting well casing headspace analysis prior to water level measurement, well development, or sample collection. Specific monitoring strategies for these instruments are described in Section 7.3.2.

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

PPE required to perform PID monitoring generally consists of Level D during monitoring prior to sampling. Refer to task-specific descriptions for PPE requirements during PID monitoring.

7.5.19 SOP FO.16: Field Radiological Measurements

Task Description

Field radiological measurements are performed by RPTs or the subcontractor HSS. Measurements include collection and survey of smear samples, as well as field frisks of personnel and equipment. The results of the surveys are typically compared to EMRG 3.1 and 3.02 release criteria.

**FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM**

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 104 of 123
Effective Date: 3/15/95
Organization: Environmental Management

PPE Requirements

In general, PPE requirements for conducting field radiological measurements consists of Level D with nitrile or butyl gloves. Consult the radiation work permit (RWP) for PPE requirements when conducting field radiological measurements in RCAs or any other areas with known radiological contamination.

7.5.20 SOP FO.18: Environmental Sample Radioactivity Content Screening

Task Description

Environmental sample radioactivity content screening is conducted on sample containers and sample coolers by the subcontractor HSS prior to shipment to analytical laboratories.

PPE Requirements

In general, PPE requirements for conducting environmental sample radioactivity content screening consists of Level D with nitrile or butyl gloves.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 105 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.5.21 SOP FO.19: Base Laboratory Work

Task Description

Base Laboratory work is conducted at the subcontractor trailer and consists of staging equipment for sampling activities, storing and preparing sample containers and sample sets, receiving, preparing, and shipping samples, and equipment storing and calibration.

PPE Requirements

Base Laboratory work will be conducted in Level D PPE.

7.5.22 SOP FO.25: Shipment of Radioactive Materials Samples

Task Description

Radioactive materials samples are shipped to analytical laboratories for analysis. Samples are shipped after appropriate survey and decontamination, if necessary, as described in Section 7.5.20.

PPE Requirements

At a minimum, Level D PPE will be worn by personnel conducting FO.25 tasks.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 106 of 123
Effective Date: 3/15/95
Organization: Environmental Management

7.5.23 Special Tasks Conducted by the Groundwater Monitoring Program Subcontractor

Task Description

The Groundwater Monitoring Program subcontractor may be required by Rocky Flats to perform tasks which are not specifically provided for in the GW SOPs and FOs listed above. In the event that the subcontractor is requested to perform "out of scope" tasks, the individual requesting performance of the task will complete a Health and Safety information form for the subcontractor. A Special Task Health and Safety Plan will be prepared by the subcontractor Health and Safety Officer. The information form and Special Task Health and Safety Plan are provided in Appendix E.

PPE Requirements

Refer to Section 7.3.2 for air monitoring PPE requirements.

The specific risks associated with each task must be assessed based on information provided by the requestor, and appropriate PPE selected by the HSO in consultation with the EG&G PM, if necessary.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 107 of 123
Effective Date: 3/15/95
Organization: Environmental Management

8.0 EMERGENCY RESPONSE PROCEDURES

8.1 Radio Communications

Field teams will have a method of communicating with both the field office trailer and other field teams. Radio communications are required. Each field crew will be issued a radio for communication with the subcontractor Base Laboratory trailer office. Field crews will be required to utilize assigned open channel radio frequencies, and "check in" with the subcontractor office at least every two hours. The Base Laboratory will utilize the radios to relay messages, such as LS/DW announcements, to field crews.

8.2 Emergency Telephone

Emergency help is accessed by any Rocky Flats phone or field radios. The closest accessible telephone during all work hours will be identified by the HSS before beginning field activities in case radio communication with the communication center is not possible. All Rocky Flats guard posts have telephones.

The subcontractor Base Laboratory trailer office will be equipped with telephone communications and shall be attended at all times during operations. Emergency telephone numbers, as listed below and in Table 8-1, are posted near the office telephones and at the office entrances.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 108 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Site Health and Safety Officer	(303) 966-6079
24-Hour Installation Health/Safety Coordinator	(303) 966-2911
Fire	(303) 966-2911
Ambulance	(303) 966-2911
Poison Center	(303) 629-1123
Security	(303) 966-2911
Police	(303) 966-2911
Medical Facility General Information	(303) 966-2594
NEAREST MEDICAL SERVICES ARE LOCATED AT:	Building 122

8.3 Medical Facilities

The Rocky Flats Medical Facility provides emergency care and ambulance service for on-site incidents. Telephone numbers for the Rocky Flats Medical Facility are provided below:

- General Information 966-2594
- Ambulance Service 966-2911
- Emergency Telephone 966-2911
- Fire/Explosion 966-2911

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 109 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Directions to the Medical Facility (Building 122, Central Avenue, Figure 8-1) are as follows:

From the Contractor's trailer compound, take a northbound street to Central Avenue and turn left onto Central Avenue: Building 122 will be on the left side and slightly west of a guard building on the right after approximately 1.25 miles.

From the Rocky Flats eastern boundary, upon entering Rocky Flats from Indiana Street, you will be on Central Avenue. Proceed approximately 3.5 miles: Building 122 will be on the left side.

From the Rocky Flats western boundary at Hwy. 93, proceed along the entrance road to just past the gate, at which time you will be eastbound on Cactus Avenue. Then turn left onto the first street past Second Street, (Third Street, which is not marked). Proceed up Third Street past Building 125, which is on the left: the next building on the left will be the medical facility (Building 122).

8.4 Emergency Response Procedures

The On-site Project Manager, with assistance from the SSO, has responsibility and authority for coordinating all emergency response activities until proper authorities arrive and assume control.

The subcontractor will develop an Emergency Response Exercise program, submitted to the EG&G Project Manager and Environmental Restoration Health and Safety Officer for approval, in order to practice Emergency Response procedures prior to an actual emergency. At a minimum, the Emergency Response Exercise should involve a reasonable emergency scenario that requires actions in the following areas:

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 110 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Emergency recognition;
- Safe distance and place of refuge (assembly area) designation;
- Site security and control;
- Evacuation routes;
- Emergency treatment and first aid;
- Personnel and equipment decontamination;
- Emergency communication;
- PPE and emergency equipment uses; and,
- A follow-up meeting to discuss effectiveness of the exercise and recommended actions.

The exercise will be conducted at a minimum frequency of every 6 months.

Audible emergency alarms are used at Rocky Flats to alert personnel of specific emergencies. A list of the specific warnings, associated sound, and instructions for response, is provided in Table 8-2.

8.4.1 Fire/Explosion

Fire emergencies will be handled by immediately notifying the fire department (2911). Only if a fire appears to be small and easily extinguishable will personnel attempt to control it with fire extinguishers available in the work area. Otherwise, immediate evacuation of the area is required.

0

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 111 of 123
Effective Date: 3/15/95
Organization: Environmental Management

In the event of an explosion, all personnel shall be evacuated and the fire department notified. No one shall re-enter the area until re-entry has been cleared by the fire department.

8.4.2 Physical Injury

In case of injuries to personnel, the SSO will be notified first, then first aid treatment will be initiated immediately by trained personnel. In case of serious injuries, the SSO/base lab shall call 2911. As groundwater sites are often in remote areas, the emergency personnel may respond faster by coming to the base lab and getting a knowledgeable escort. All serious injuries (e.g., snake bites) will be transported by Rocky Flats Emergency response personnel and vehicles. Minor injuries may be treated on site (first aid), but all injuries will be evaluated by Rocky Flats medical personnel.

In the event the injured person is contaminated with chemicals or radionuclides, decontamination will be performed to prevent further exposure only if it will not further aggravate the injury.

8.4.3 Injury Due to Heat

If a person is suffering from heat exhaustion (profuse perspiration, normal body temperature), the following procedures will be taken:

- Remove the person to a cooler, shaded area;
- Give 8 ounces of Gatorade (if available) every 15 minutes for three or four doses. Drinking water will be used if Gatorade™ is not readily available;
- Allow the person to rest; and,

0

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 112 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- If the person is suffering from cramps, press warm, wet towels over the cramped area.

A **life threatening** situation exists and **immediate action** is indicated if a person is suffering from **heat stroke** (skin hot and dry, very high body temperature); the following procedures will be taken:

- **Immediately** contact the HSS and request that medical facility personnel be contacted and respond to the accident location, and take instructions from the medical personnel for care of the victim until their arrival;
- Cool the victim quickly by soaking the person in cool (but not cold) water, sponging the body with rubbing alcohol or cool water, or pouring water on the body; and,
- Transport to hospital for medical attention as quickly as possible.

8.4.4 Injury Due to Cold

First aid for frostbite consists of the following procedures:

- Notify the On-site Project Manager or HSS, and Rocky Flats Occupational Medicine (OM);
- Bring the victim indoors and quickly rewarm the affected areas in water between 102° to 105°F;
- Give victim a warm drink--NOT coffee, tea, or alcohol;
- Do not permit the victim to smoke;

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 113 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Keep the frozen parts in warm water or covered with warm cloths for 30 minutes, even though the tissue will be painful as it thaws;
- Evaluate the injured areas and cover with sterile, soft, dry material;
- Keep the victim warm and get immediate medical care;
- Do not rub the frostbitten part;
- Do not allow blisters to be broken;
- Do not use ice, snow, or anything cold on frostbite;
- Do not use heat lamps or hot water bottles to rewarm the body part; and,
- Do not place the affected part near a hot stove.

First aid for excessive exposure to cold (hypothermia) consists of the following procedures:

- Contact SSO, who will call paramedics (2911) so victim can be moved safely and quickly;
- Bring victim into a warm area as quickly as possible;
- Remove wet or cold garments;
- Dry the person thoroughly;
- Provide warm, dry clothing or covering;
- Provide rapid but gentle rewarming;
- Give victim a warm drink--NOT coffee, tea, or alcohol;
- Keep the victim warm; and,

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 114 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- Decontaminate the victim only after the frostbite situation is rectified and initiation of decontamination is approved by a physician.

8.4.5 Reporting and Notification

Reporting and notification of emergency situations shall be carried out in accordance with Chain of Command requirements in Department of Energy (DOE) Order 5484.1. In the event of an emergency, a crew member of the field team involved will notify the Site Safety Officer who will notify the appropriate emergency assistance personnel (for example, fire, police, ambulance) at extension 2911 immediately, and then notify the Site Manager. The Site Manager will notify the Rocky Flats Environmental Restoration (ER) Program Field Supervisor, PM, and Health and Safety Administrator. The responsibility of the SSO is to implement notification and reporting requirements of DOE Order 5484.1.

8.4.6 Thunderstorms and Tornadoes

A severe thunderstorm watch or a tornado watch announcement on radio or television indicates that a severe thunderstorm or tornado is possible. Work will continue at the work site during severe thunderstorm watches or tornado watches. A severe thunderstorm warning or a tornado warning signifies that a severe thunderstorm or a tornado has been sighted or detected by radar and may be approaching. All work on site shall cease during a thunderstorm, severe thunderstorm warning, or tornado warning.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 115 of 123
Effective Date: 3/15/95
Organization: Environmental Management

Personnel on site during a tornado shall take the following steps:

- Evacuate office trailers or vehicles;
- If outdoors, lie flat in a nearby ditch;
- Stay away from power poles, electrical appliances, and metal objects; and,
- Do not try to outrun a tornado.

8.4.7 Other Adverse Weather

In the event of adverse weather, the SSO will determine if work can continue without sacrificing the health and safety of site personnel. Some of the items to be considered prior to determining if work should continue are:

- High winds;
- Heavy rainfall;
- Potential for heat stress;
- Potential for cold stress;
- Limited visibility;
- Potential for accidents; and,
- The malfunctioning of monitoring equipment.

8.4.8 Electric Shock

All electrical shocks shall be considered as a physical injury and will be handled as described in Subsection 8.4.2. In addition, the following requirements will be followed:

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 116 of 123
Effective Date: 3/15/95
Organization: Environmental Management

- All electric shocks are accidents and must be reported to the Field Supervisor;
- Employees who attempt to rescue shock victims must not endanger themselves or others; and,
- The electrical source should be de-energized immediately if the victim is still in contact with electrical energy.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 117 of 123
Effective Date: 3/15/95
Organization: Environmental Management

9.0 LOGS, REPORTS, AND RECORDKEEPING

9.1 General

Records shall be kept documenting the site safety program, health and safety audits, training meetings (weekly/tailgates), Radiation Work Permits, and radiological surveys. A bound logbook will be used by the HSS/HSST to record results of each environmental monitoring event within the exclusion zone. All records shall be maintained and handled in accordance with applicable Rocky Flats procedures. As a minimum, the requirements of Procedure 2-G18-ER-ADM-17.01 and the Rocky Flats Quality Assurance Manual shall be met.

9.2 Personnel Records

Records shall be kept on each on-site individual. Records include a medical clearance statement from a qualified physician, fit test, and training documentation. When site safety meetings are conducted, an attendance sheet that includes the subjects briefed must be kept.

9.3 Calibration Records

All radiological monitoring equipment will be calibrated as described in ANSI N323-1978 "Radiation Protection Instrument Test and Calibration" and Rocky Flats directives. All monitoring equipment used for health and safety purposes will be calibrated as suggested by the manufacturer. Records of all calibrations will be maintained.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 118 of 123
Effective Date: 3/15/95
Organization: Environmental Management

9.4 Occupational Safety and Health Administration Form 200

An OSHA Form 200 will be posted in an area frequented by all subcontractor personnel. The HSS will be responsible for maintaining this form.

9.5 Health and Safety Logbook

A separate health and safety logbook and sign in/sign out log shall be maintained by the SSO throughout the project and turned in to the EG&G Project Manager after the project is completed. Logged information shall include:

- Names of all personnel entering and leaving the site each day;
- Daily listing of site numbers to be visited by field teams;
- Description of unforeseen hazards and steps taken to mitigate hazards;
- VOC readings taken in the breathing zone if above background;
- Summary of telephone conversations regarding health and safety;
- Safety infractions, if any;
- Accidents and injuries; and,
- All other significant health and safety items.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 119 of 123
Effective Date: 3/15/95
Organization: Environmental Management

9.6 Accident/Incident Reporting

9.6.1 Subcontractor Procedures

In the event of an accident or incident, the HSS will immediately notify the On-site Project Manager and the Health and Safety Officer (HSO) after appropriate emergency personnel have been notified. Types of accidents or incidents that are considered reportable are listed in ADM 1601.

Work will be suspended until the cause of the accident/incident is canceled and to modify this HASP as necessary.

A accident/incident report form (DOE Form F 5484.X) must be submitted to the EG&G Project Manager (PM) and HSO within 24 hours of occurrence.

9.6.2 Rocky Flats Procedures

In accordance with the Site Health and Safety Plan (HSP) Section 3.03, the SSO or HSS will notify the appropriate emergency personnel at extension 2911. The Site Manager will notify the Rocky Flats Environmental Restoration (ER) Program Field Supervisor, the Rocky Flats ER Program Manager, Rocky Flats Site Health and Safety Coordinator of any accidents or incidents that occur during field activities that fall into the following classifications. The Site Safety Officer will also submit a completed DOE Form F 5484.X for any of the following incidents:

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 120 of 123
Effective Date: 3/15/95
Organization: Environmental Management

1. "Recordable" occupational injuries or illnesses as defined below:

OCCUPATIONAL INJURY is any injury such as a cut, fracture, sprain, or amputation that results from a work accident or from an exposure involving a single incident in the work environment. NOTE: Conditions resulting from animal or insect bites, or one-time exposure to chemicals, are considered to be injuries.

OCCUPATIONAL ILLNESS of an employee is any abnormal condition or disorder, other than one resulting from an occupational injury, caused by exposure to environmental factors associated with employment. It includes acute and chronic illnesses or diseases that may be caused by inhalation, absorption, ingestion, or direct contact with a toxic material.

2. PROPERTY DAMAGE LOSSES of \$1,000 or more are reported as follows: accidents that cause damage to Department of Energy (DOE) property, regardless of fault, or accident wherein DOE may be liable for damage to a second party, are reportable if damage is \$1,000 or more. Include damage to facilities, inventories, equipment, and properly parked motor vehicles. Exclude damage resulting from a DOE-reportable vehicle accident.
3. GOVERNMENT MOTOR VEHICLE ACCIDENTS resulting in damages of \$500 or more, or involving injury, are reported unless the government vehicle is not at fault, damage of less than \$500 is sustained by the government vehicle, or no injury is inflicted on the government vehicle occupants. Accidents are also reportable to DOE if:
- Damage to DOE property is greater than or equal to \$500 and the driver of a government vehicle is at fault
 - Damage to any private property or vehicle is greater than or equal to \$500 and the driver of a government vehicle is at fault
 - Any person is injured and the driver of a government vehicle is at fault

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 121 of 123
Effective Date: 3/15/95
Organization: Environmental Management

10.0 REFERENCES

- Interagency Agreement (IAG), 1990. Draft. The U.S. Department of Energy, U.S. Environmental Protection Agency, and the Colorado Department of Health.
- Interagency Agreement (IAG), 1991. Final. The U.S. Department of Energy, U.S. Environmental Protection Agency, and the Colorado Department of Health.
- Rockwell International Corporation, 1988. Draft Remedial Investigation and Feasibility Study Plans for Low Priority Sites. Volume I. Site Descriptions, Groupings and Prioritization.
- U.S. Department of Energy (DOE), 1980. Final Environmental Impact Statement. Rocky Flats Plant Site, Golden, Colorado (Final Statement to ERDA 1545-D), 3 volumes. DOE/EIS-0064, UC-2, 11. April.
- U.S. Department of Energy (DOE), 1986a. Comprehensive Environmental Assessment and Response Program (CEARP), Phase I Installation Assessment. Rocky Flats Plant, Albuquerque Operations Office.
- U.S. Department of Energy (DOE), 1986b. Resource Conservation and Recovery Act (RCRA), Part B Operating Permit Application for Rocky Flats Plant Hazardous and Radioactive Mixed Wastes. CO7890010526.
- U.S. Department of Energy (DOE), 1986c. Resource Conservation and Recovery Act (RCRA), Part B Operating Permit Application for Rocky Flats Plant Transuranic (TRU) Mixed Wastes. CO7890010526.
- U.S. Department of Energy (DOE), 1987. RCRA 3004(u) Waste Management Units. Appendix 1 of the Rocky Flats Plant RCRA Part B Operating Permit Application.
- U.S. Department of Energy (DOE), 1988. Closure Plan, Container Storage Facilities: Property Utilization and Disposal Container Storage Facilities, Swinerton and Walberg Building 980 Container Storage Facility, Swinerton and Walberg Contractor Storage Yard, Building 885 Drum Storage Area, Building 881 Drum Storage Area, Building 865 Drum Storage Area, Building 883 Drum Storage Area, Building 334 Cargo Container Area, Building 444/453 Drum Storage Area, Rocky Flats Plant.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 122 of 123
Effective Date: 3/15/95
Organization: Environmental Management

U.S. Department of Energy (DOE), 1990. Final Phase III RFI/RI Work Plan, Rocky Flats Plant 881 Hillside Area (Operable Unit No. 1). Rocky Flats Plant, Golden, Colorado. October.

U.S. Department of Energy (DOE), 1991a. Phase II RFI/RI/FS Work Plan (Alluvial), 903 Pad, Mound, and East Trenches Areas (Operable Unit 2). Rocky Flats Plant, Golden, Colorado.

U.S. Department of Energy (DOE), 1991b. Phase II RFI/RI Work Plan (Bedrock), 903 Pad, Mound, and East Trenches Areas (Operable Unit 2). Rocky Flats Plant, Golden, Colorado.

U.S. Department of Energy (DOE), 1991c. Draft Final RFI/RI Work Plan for Operable Unit 3. Rocky Flats Plant, Golden, Colorado.

U.S. Department of Energy (DOE), 1991d. Draft Final Phase I RFI/RI Work Plan, Solar Evaporation Ponds (Operable Unit No. 4). Rocky Flats Plant, Golden, Colorado.

U.S. Department of Energy (DOE), 1991e. Environmental Assessment, Dewatering and RCRA Partial Closure Action on Solar Evaporation Ponds. Rocky Flats Plant, Golden, Colorado, DOE/EA-0487. June.

U.S. Department of Energy (DOE), 1991f. Final Phase I RFI/RI Work Plan, Rocky Flats Plant Woman Creek Priority Drainage (Operable Unit No. 5). Rocky Flats Plant, Golden, Colorado. October.

U.S. Department of Energy (DOE), 1991g. Final Phase I RFI/RI Work Plan, Rocky Flats Plant Walnut Creek Priority Drainage (Operable Unit No. 6). Rocky Flats Plant, Golden, Colorado. Vol. 1. September.

U.S. Department of Energy (DOE), 1991h. Phase I RFI/RI Work Plan, Present Landfill, IHSS 1:14, and Inactive Waste Storage area, IHSS 203 (Operable Unit No. 7).

U.S. Department of Energy (DOE), 1991i. Final Phase I RFI/RI Work Plan, Rocky Flats Plant Original Process Waste Lines (Operable Unit No. 9). Rocky Flats Plant, Golden, Colorado. November.

U.S. Department of Energy (DOE), 1991j. Draft Final Phase I RFI/RI Work Plan, Rocky Flats Plant Other Outside Closures (Operable Unit No. 10). Rocky Flats Plant, Golden, Colorado. November.

FINAL
HEALTH AND SAFETY PLAN GROUNDWATER MONITORING PROGRAM

**ROCKY FLATS
ENVIRONMENTAL
TECHNOLOGY SITE**

Manual: RFP/ER-SAF-94-GMP
Revision No.: 0
Page: 123 of 123
Effective Date: 3/15/95
Organization: Environmental Management

U.S. Department of Energy (DOE), 1991k. Final Phase I RFI/RI Work Plan, West Spray Field (Operable Unit No. 11). Rocky Flats Plant, Golden, Colorado. December 18.

U.S. Department of Energy (DOE), 1992a. Draft Historical Release Report for the Rocky Flats Plant.

U.S. Department of Energy (DOE), 1992b. Draft Phase I RFI/RI Work Plan, Rocky Flats Plant Site 700 Area (Operable Unit 8). Rocky Flats Plant, Golden, Colorado.

U.S. Department of Health and Human Services, 1985. Occupational Safety and Health Guidance Manual for Hazardous Waste Site Activities.

Woodward-Clyde, 1993. Health & Safety Plan (Accident Prevention Safety Program Plan), Rocky Flats Plant, Groundwater Monitoring Program.

TABLE 6-1
SIGNS AND SYMPTOMS OF HEAT STRESS

Stress Type	Cause	Symptoms
Heat rash	Continuous exposure to heat or humid air	red, itchy rash on the body
Heat cramps	Heavy sweating with inadequate electrolyte replacement	muscle spasms, pain in the hands, feet, and abdomen
Heat exhaustion	Increased stress on various body organs including inadequate blood circulation due to cardiovascular insufficiency or dehydration	pale, cool, moist skin, heavy sweating, dizziness, nausea, fainting
Heat stroke	The most serious form of heat stress. Temperature regulation fails, and the body temperature rises to critical levels. Immediate action must be taken to cool the body before serious injury and death occur. Competent medical help must be obtained.	red, hot, and usually dry skin, lack of or reduced perspiration, nausea, dizziness or confusion, strong and rapid pulse, coma

TABLE 6-2
PERMISSIBLE HEAT EXPOSURE LIMITS
Adapted From the ACGIH 1993-1994 TLVs
(Values are given in °C and °F WBGT)*

Level of PPE	Work-Rest Regimen each hour	Work Load in WBGT					
		Light ^(a)		Moderate ^(b)		Heavy ^(c)	
		°C	°F	°C	°F	°C	°F
Summer work Uniform	Continuous Work	30.0	86	26.7	80	25.0	77
	75% Work / 25% Rest	30.6	87	28.0	82	25.9	78
	50% Work / 50% Rest	31.4	89	29.4	85	27.9	82
	25% Work / 75% Rest	32.2	90	31.1	88	30.0	86
Cotton Coveralls	Continuous Work	28.0	82	24.7	76	23.0	73
	75% Work / 25% Rest	28.6	83	26.0	78	23.9	74
	50% Work / 50% Rest	29.4	85	27.4	81	25.9	78
	25% Work / 75% Rest	30.2	86	29.1	84	28.0	82
Winter work Uniform	Continuous Work	26.0	79	22.7	73	21.0	70
	75% Work / 25% Rest	26.6	80	24.0	75	21.9	71
	50% Work / 50% Rest	27.4	82	25.4	78	23.9	75
	25% Work / 75% Rest	28.2	83	27.1	81	26.0	79
Water barrier, permeable	Continuous Work	24.0	75	20.7	69	19.0	66
	75% Work / 25% Rest	24.6	76	22.0	71	19.9	67
	50% Work / 50% Rest	25.4	78	23.4	74	21.9	71
	25% Work / 75% Rest	26.2	79	25.1	77	24	75

* As workload increase, the heat stress impact on an unacclimated worker is exacerbated. For unacclimatized workers performing a moderate level of work the permissible heat exposure TLV should be reduced by approximately 2.5°C.

- (a) Light = sitting or standing to control machinery, performing light hand or arm work.
- (b) Moderate = walking about with moderate lifting or pushing
- (c) Heavy = pick and shovel work, hand augering

Comments: For situations other than those listed above, personal heat stress monitoring is required.

TABLE 7-1**ENVIRONMENTAL MANAGEMENT RADIOLOGICAL GUIDELINES**

EMRG No.	Title
EMRG 1.0	Organization and Responsibilities
EMRG 1.1	Gama Radiation Surveys
EMRG 1.2	Beta Radiation Surveys
EMRG 1.3	Posting of Radiation Protection Requirements
EMRG 2.1	Personnel Contamination Monitoring
EMRG 2.2	Possible Inhalation Exposure
EMRG 2.3	Wounds and Skin Contamination
EMRG 3.1	Performance of Surface Contamination Surveys
EMRG 3.02	Survey Requirements for Conditional and Unrestricted Use
EMRG 3.5	Handling of Contaminated Dosimetry/Security Badges
EMRG 6.1	Performance Test and Operational Checks for Ludlum Model 12-A, Model 12, and Model 31 Survey Instruments
EMRG 6.3	Performance Checking and Operation of the Eberline SAC-4 Alpha-Scintillation Smear Counting Instrumentation
EMRG 6.4	Performance Testing and Operation of the Eberline BC-4 Beta Smear Counting Instrumentation
EMRG 6.5	Use of the Bicon Frisk-Tech with the A-100 and B-50 Detectors
EMRG 6.6	Use of the Bicon Fidler (Field Instrument for the Detection of Low-Energy Radiation)
EMRG 9.1	Respiratory Protection Requirements and Posting
EMRG 10.1	Radiological Deficiency Reporting Program

TABLE 7-2

ACTION LEVELS FOR NONRADIOACTIVE ISSUES

Indicator	Action Level in the Breathing Zone	Action
<i>Photoionization Detector</i>		
OVD with an 11.7 eV lamp	> Background	Stop work and notify the HSS; work may be conducted in Level B PPE at the discretion of the HSS
<i>Colormetric Detector Tubes</i>		
Benzene Detector Tubes	> 0.5 ppm	Stop work and notify the HSS; work may be conducted in Level B PPE at the discretion of the HSS
Carbon Tetrachloride Detector Tubes	> 1 ppm	Stop work and notify the HSS; work may be conducted in Level B PPE at the discretion of the HSS
Chloroform Detector Tubes	> 1 ppm	Stop work and notify the HSS; work may be conducted in Level B PPE at the discretion of the HSS
1,1-Dichloroethene Detector Tubes	> 0.5 ppm	Stop work and notify the HSS; work may be conducted in Level B PPE at the discretion of the HSS
Methylene Chloride Detector Tubes	> 12 ppm	Stop work and notify the HSS; work may be conducted in Level B PPE at the discretion of the HSS
Tetrachloroethene Detector Tubes	> 0.5 ppm	Stop work and notify the HSS; work may be conducted in Level B PPE at the discretion of the HSS
Vinyl Chloride Detector Tubes	> 0.5 ppm	Stop work and notify the HSS; work may be conducted in Level B PPE at the discretion of the HSS
<i>Combustible Gas Indicator</i>		
CGI	Greater than 10% of the LEL	Exit exclusion zone and review Subsection 7.3.2

TABLE 7-3

TASK-SPECIFIC PPE REQUIREMENTS

Task and Activity	PPE Requirements	Text Reference
SOP GW.1 Water Level Measurements in Wells and Piezometers	Air monitoring, then Level D with nitrile or butyl gloves, or according to RWP requirements.	7.3.2, 7.5.1
SOP GW.2 Well Development	Air monitoring, then Level D with nitrile or butyl gloves, or according to RWP requirements.	7.3.2, 7.5.2
SOP GW.3 Pump in Borehole Packer Testing	Air monitoring, then Level D with nitrile or butyl gloves, or according to RWP requirements.	7.3.2, 7.5.3
SOP GW.4 Slug Tests	Air monitoring, then Level D with nitrile or butyl gloves, or according to RWP requirements.	7.3.2, 7.5.4
SOP GW.5 Field Measurement of Groundwater Field Parameters	Air monitoring, then Level D with nitrile or butyl gloves, or according to RWP requirements.	7.3.2, 7.5.5
SOP GW.6 Groundwater Sampling	Air monitoring, then Level D with nitrile or butyl gloves, or according to RWP requirements.	7.3.2, 7.5.6
SOP GW.8 Aquifer Pumping Tests	Air monitoring, then Level D with nitrile or butyl gloves, or according to RWP requirements.	7.3.2, 7.5.7
SOP FO.01 Air Monitoring and Dust Control	Level D	7.5.8
SOP FO.02 Transmittal of Field QA Records	Level D	7.5.9
SOP FO.03 General Equipment Decontamination		7.3.2, 7.5.10
- Radiological Surveys	Level D unless results exceed EMRG 3.1, then Level C or B as appropriate, or according to RWP requirements.	

TABLE 7-3

TASK-SPECIFIC PPE REQUIREMENTS

Task and Activity	PPE Requirements	Text Reference
- VOC Surveys	Level D, upgrading to Level C or B as appropriate.	
- Decontamination	Modified Level D, with coated chemical - resistant disposable coveralls, face shield, and nitrile or butyl gloves, or according to RWP requirements.	
SOP FO.05 Handling of Purge and Development Water		7.3.2, 7.5.11
- Collection	Air monitoring, then Level D, or according to RWP requirements.	
- Transfer	Air monitoring, then Level D, with ear plugs, nitrile or butyl gloves, splash apron, or according to RWP requirements.	
SOP FO.06 Handling Personal Protective Equipment	Level D with nitrile or butyl gloves.	7.5.12
SOP FO.07 Handling and Decontamination of Water and Wash Water	Level D with ear plugs, nitrile or butyl gloves, splash apron, or according to RWP requirements.	7.5.13
SOP FO.11 Field Communications	Level D.	7.5.14
SOP FO.12 Decontamination Facility Operations		7.5.15
- Non-steam cleaner use	Level D with nitrile or butyl gloves and ear plugs, or according to RWP requirements.	
- Steam cleaner use	Modified Level D, or according to RWP requirements	
SOP FO.13 Containerization, Preserving, Handling and Shipping of Soil and Water Samples		7.5.16

TABLE 7-3

TASK-SPECIFIC PPE REQUIREMENTS

Task and Activity	PPE Requirements	Text Reference
- Containerization and handling	Level D with nitrile or butyl gloves.	
- Preservation	Level D with nitrile or butyl gloves, splash apron, and faceshield.	
- Shipping	Level D	
SOP FO.14 Field Data Management	Office work uniform.	7.5.17
SOP FO.15 Photoionization Detectors (PID) and Flame Ionization Detectors (FID)	Air monitoring, then Level D, or according to task-specific requirements.	7.3.2, 7.5.18
SOP FO.16 Field Radiological Measurements	Level D with nitrile or butyl gloves, or according to RWP requirements	7.5.19
SOP FO.18 Environmental Sample Radioactivity Content Screening	Level D with nitrile or butyl gloves	7.5.20
SOP FO.19 Base Laboratory Waste	Level D	7.5.21
SOP FO.25 Shipment of Radioactive Materials Samples	Level D	7.5.22
Special Tasks	Air monitoring (if required), then Level D, or as required by the Special Task Health and Safety Plan	7.3.2, 7.5.23

TABLE 8-1**EMERGENCY TELEPHONE NUMBERS**

Site Health and Safety Officer	(303) 966-6079
24-Hour Installation Health/Safety Coordinator	(303) 966-2911
Fire	(303) 966-2911
Ambulance	(303) 966-2911
Poison Center	(303) 629-1123
Security	(303) 966-2911
Police	(303) 966-2911
Medical Facility General Information	(303) 966-2594
NEAREST MEDICAL SERVICES ARE LOCATED AT:	Building 122

Directions to Medical Services:

From the Contractor's trailer compound, take a northbound street to Central Avenue and turn left onto Central Avenue: Building 122 will be on the left side and slightly west of a guard building on the right after approximately 1.25 miles.


From the RFP eastern boundary, upon entering RFP from Indiana Street, you will be on Central Avenue. Proceed approximately 3.5 miles: Building 122 will be on the left side.

From the RFP western boundary at Hwy. 93, proceed along the entrance road to just past the gate, at which time you will be eastbound on Cactus Avenue. Then turn left onto the first street past Second Street, (Third Street, which is not marked). Proceed up Third Street past Building 125, which is on the left: the next building on the left will be the medical facility (Building 122).


TABLE 8-2
EMERGENCY ALARMS

WARNING	SOUND	INSTRUCTIONS
Fire Alarm	Bell	Evacuate area
Civil Defense Warning Alarm	High Frequency Pitch Steady Tone	Follow public address instruction and building announcements
Civil Defense Attack Alarm	Wailing Siren	Follow public address instructions
Criticality Alarm	Wailing Tone	Evacuate building and assemble in evacuation area

An Emergency Alarm Overview training tape is available for audio review at 966-7541.



150



BUILDING NO. 122
MEDICAL FACILITY

INDIANA AVENUE

CONTRACTORS AREA

HIGHWAY 93

<p>CLIENT/PROJECT</p> <p>EG&G - ROCKY FLATS</p> <p>GROUNDWATER MONITORING PROGRAM</p> <p>HEALTH AND SAFETY PLAN</p>	<p>Golder Associates</p> <p>Denver, Colorado</p>	<p>TITLE</p> <p>MEDICAL FACILITY MAP</p>
<p>DRAWN BDL</p> <p>CHECKED CER</p> <p>REVIEWED LEC</p>	<p>DATE SEPT 1994</p> <p>SCALE NTS</p> <p>FILE NO.</p>	<p>JOB NO. 933-2715</p> <p>DWG NO./REV. NO.</p> <p>FIGURE 8-1</p>

APPENDIX A

**RESPONSIBILITIES AND AUTHORITY OF
HEALTH AND SAFETY PERSONNEL**

**EM HEALTH &
SAFETY OFFICER: Keith Anderson**
966-6979

-Ensures that radiological aspects of
project specific documents meet
criteria of SOPs

**EM RADIOLOGICAL
ENGINEER: Rick Gentry**
966-8349

-Responsible for HSS program
-Prepares EMRGs & ensures compliance
-Oversees RWP and RDR program

EM PROJECT MANAGER
Steve Singer 966-8635
-Implements HSO & RE directives

EG&G

Subcontractor

SUBCONTRACTOR PROJECT MANAGER
Larry Cope 980-0540
-Implements EM-PM directives

SITE MANAGER
Kerry Bayer 966-6079
-Assures compliance with HASP
-Supports SSO and HSS

SITE SAFETY OFFICER
Harold Sanchez 966-6079
-Implements HASP
-Supervises HSSs
-Generates, reviews, and/or
maintains database referencing
Health and Safety subjects
-Interfaces with EM-RE and CHSO

HEALTH AND SAFETY SPECIALIST
Harold Sanchez 966-6079
-Conducts surveys and documents
results
-Supervises HSSTs
-Directs implementation of HASP
to field crews

FIELD CREWS
-Conduct tasks in accordance
with HASP

**CORPORATE HEALTH
AND SAFETY OFFICER**
Bill Hager (206)883-0777
-Oversees HASP

**PROJECT HEALTH AND
SAFETY OFFICER**
Christopher Rife 980-0540
-Develops project Health
and Safety program

Note: Responsibilities presented herein are summarized from
Appendix A data. For full details, please refer to specific
titles and responsibilities presented in Appendix A.



**Golder
Associates**

Denver, Colorado

TITLE

HEALTH AND SAFETY RESPONSIBILITY FLOW CHART

CLIENT/PROJECT

**EG&G - ROCKY FLATS
GROUNDWATER MONITORING PROGRAM
HEALTH AND SAFETY PLAN**

DRAWN

PGQ

DATE

SEPT 1994

JOB NO.

933-2715

CHECKED

CER

SCALE

DWG NO./REV. NO.

2715A001

REVIEWED

LEC

FILE NO.

2715A001

FIGURE NO.

A-1

APPENDIX A

RESPONSIBILITIES AND AUTHORITY OF HEALTH AND SAFETY PERSONNEL

ENVIRONMENTAL MANAGEMENT (EM) HEALTH AND SAFETY OFFICER (HSO)

Responsibilities

The HSO will ensure that the radiological aspects of project-specific documents meet the criteria established in EG&G Rocky Flats Plant Site-Wide Standard Operating Procedures (SOPs).

EM RADIOLOGICAL ENGINEER (EMRE)

Responsibilities

- Establish qualifications for the Health and Safety Specialist (HSS) position.
- Review the credentials of prospective HSSs and, when appropriate, approve individuals to complete tasks reserved for HSSs.
- Review and approve subcontractor-prepared training programs that are designed to qualify a subcontractor employee to serve as an HSS.
- Prepare Environmental Management Radiological Guidelines (EMRGs) that address subjects such as, but not limited to, survey methods, documentation, frequencies, and locations.
- Establish survey and sampling strategies for property that cannot be surveyed in accordance with the standard techniques outlined in existing EMRGs, and ensure that property to be released for unrestricted use does not exceed the limits specified in DOE Order 5400.5 (Reference 5.2).
- Provide guidance on the performance of the procedures and techniques utilized in field operations for surface contamination surveys.
- Specify work controls for radiologically controlled areas, or review and approve work controls prepared by Subcontractors.
- Review and approve selected radiation survey reports.
- Investigate unanticipated survey results such as a lack of radioactivity when radioactivity is known to be present, or radiation levels exceeding anticipated levels.

APPENDIX A
(Continued)

- Oversee Radiation Work Permit (RWP) program administration.
- Oversee Radiological Deficiency Report (RDR) program administration.
- Sign, or designate a representative to sign, forms such as property releases.
- Perform dose reconstruction for personnel whose dosimeters have been contaminated or are deemed "unreadable."
- Determine the appropriate posting and control of radiologically contaminated sites and approve the deposing of signs.
- Evaluate Possible Inhalation Exposures and decide on appropriate actions.
- Evaluate possible wound and skin contamination incidents.
- Provide support for the evaluation and control of work requiring respiratory protection.
- Perform all additional specific procedural duties relating to EM field activities detailed in the Radiological Engineering Procedures Manual, applicable Radiological Engineering documents, and the applicable HSP manual.
- Anticipate, recognize, and evaluate radiological health hazards, and recommend control measures as necessary. Engineering controls shall be emphasized.
- Perform quarterly inspections of OUs and Hazardous Waste Areas (HWAs) to determine compliance with the Health and Safety Plans.
- Ensure, in conjunction with Industrial Hygiene and Environmental Management, that site characterization and analysis, in accordance with 29 CFR 1910.120, is performed to identify specific site radiological hazards at OUs and to determine the necessary safety and health control procedures to protect personnel from the identified hazards.
- Ensure, in conjunction with Industrial Hygiene and Environmental Management, that appropriate site control procedures are implemented before cleanup work begins to control personnel exposure to radiological hazards.

APPENDIX A (Continued)

- Provide technical review of all Health and Safety Plans, Job Safety Analyses (JSAs), Integrated Work Control Programs (IWCPs), and procedures as necessary.
- Implement Radiological Protection Program.

INDUSTRIAL HYGIENE (IH)

Responsibilities

- Anticipate, recognize, and evaluate non-radiological health hazards, and recommend control measures as necessary. Engineering controls shall be emphasized, rather than administrative or personal protective equipment (PPE) controls.
- Perform quarterly inspections of OUs and HWAs to determine compliance with the Health and Safety Plan.
- Ensure, in conjunction with Environmental Management and Radiological Engineering, that site characterization and analysis, in accordance with 29 CFR 1910.120, is performed to identify specific site health hazards at OUs and to determine the necessary safety and health control procedures to protect personnel from identified hazards.
- Ensure, in conjunction with Environmental Management and Radiological Engineering, that appropriate site control procedures for OUs are implemented before cleanup work begins, to control personnel exposure to hazardous substances.
- Ensure, in conjunction with Waste Operations, Radiological Engineering, Waste Programs, Environmental Management, and Occupational Safety personnel, that specific site health hazards at HWAs and OUs are identified, and to determine necessary safety and health control procedures to protect personnel from the identified hazards.
- Provide a Subject Matter Expert (SME) for technical input to all plant training applicable to 29 CFR 1910.120.
- Provide technical review of all Health and Safety Plans, JSAs, IWCP documents, and procedures, as necessary.

APPENDIX A (Continued)

- Provide the H&S Liaison Officer

- The Liaison Officer's responsibilities include the following:

- ▶ Coordinate health and safety activities with the Environmental Management H&S Officer and the Environmental Management Site Project Managers.
 - ▶ Supervise the EG&G Site H&S Coordinators at each OU.
 - ▶ Coordinate health and safety guidance for hazardous waste operations in HWAs.
 - ▶ Coordinate preparation and approval of OU and HWA Health and Safety Plans.
 - ▶ Coordinate quarterly health and safety audits and inspections of health and safety programs and program documentation for subcontractors for hazardous waste operations.
 - ▶ Coordinate review of OU workplans with the Environmental Management H&S Officer.
 - ▶ Perform formal audits of EG&G Hazardous Waste Operations Training Courses on an annual basis. The purpose of these audits is to ensure compliance with OSHA requirements for hazardous waste operations training.
 - ▶ Coordinate review and approval of Health and Safety Plan field changes.

- Provide Site Health and Safety Coordinators (SHSCs) for OUs.

- The SHSCs' duties include the following:

- ▶ Oversee EG&G and subcontractor work to verify compliance with the requirements of Health and Safety Plans.
 - ▶ Perform audits for proper and appropriate use of PPE, monitoring and decontamination procedures, site control, and all required documentation.

APPENDIX A (Continued)

NOTE

Radiological decontamination procedures shall be reviewed by Radiological Engineering personnel.

- ▶ Alert the OU Site Project Manager, H&S Liaison Officer, and the Environmental Operations Manager of health and safety violations at OUs.
- ▶ Provide health and safety support for EG&G employees.

OCCUPATIONAL SAFETY (OS)

Responsibilities

- Anticipate, recognize, and evaluate safety hazards, and recommend control measures as necessary. Engineering controls shall be emphasized.
- Perform quarterly inspections of OUs and HWAs to determine compliance with Health and Safety Plans.
- Ensure, in conjunction with Waste Operations, Radiological Engineering, Waste Programs, Environmental Management, and Industrial Hygiene personnel, that specific site health hazards at HWAs and OUs are identified, and determine necessary safety and health control procedures to protect personnel from the identified hazards.
- Provide technical review of all Health and Safety Plans, JSAs, IWCPs, and procedures as necessary.

GROUNDWATER MONITORING PROGRAM (GMP)- PROJECT MANAGER

Responsibilities

- Direct the development of a formal training program designed to qualify subcontractor employees to be designated as HSSs by the EMRE. The training program will include classroom sessions and supervised field work, and will be submitted to the EMRE for approval.
- Direct and monitor the implementation of the health and safety program.

APPENDIX A (Continued)

- Advise personnel on health and safety matters.
- Issue directives, advisories, and information to the Corporate Health and Safety Manager (CHSM).
- Advise the CHSM on the policy, liability, and professional issues.
- Assure that adequate funds are allocated to fully implement project health and safety plans.
- Nominate Site Safety Officer (SSOs) and Health and Safety Specialists (HSSs) for EMRE approval.

Authority

- Direct changes in the health and safety program.
- Determine and implement personnel disciplinary actions, as required.
- Approve and audit project health and safety expenditures.

CORPORATE HEALTH AND SAFETY MANAGER (CHSM)

Responsibilities

- Track health and safety regulations and implement improvements to the health and safety program.
- Ensure records are maintained pertaining to medical surveillance, training, fit testing, chemical exposure, and incidents.
- Update health and safety manual.
- Manage medical surveillance program.
- Ensure health and safety training is obtained.
- Provide industrial hygiene/chemical safety guidance to SSOs.
- Audit key aspects of health and safety program and report effectiveness to project manager.

APPENDIX A

(Continued)

- Investigate reports of incidents or accidents.
- Provide guidance on radiological issues.

Authority

- Approve the qualifications of employees to work at the decontamination pads.
- Establish employee training and medical surveillance procedures.
- Suspend work on any project that jeopardizes the health and safety of personnel.
- Access project files to perform health and safety audits or investigate accidents/incidents.
- Remove individuals from projects if their conduct jeopardizes their health and safety or that of co-workers.

SITE SAFETY OFFICER (SSO)

Responsibilities

- Implement the applicable Site-Specific HSP (SSHSP) and verify compliance with all applicable health and safety requirements.
- Ensure that updated copies of the Health and Safety Plan (HSP), applicable SSHSP, EMRGs, and all documents referenced by the EMRGs, are available to subcontractor employees.
- Supervise HSSs in the performance of their responsibilities.
- Ensure HSSs and subcontractor employees are advised of the radiological hazards, both expected and suspected, by posting and controlling radiological areas according to EMRG instructions.
- Ensure that HSP 18.19, "Criteria and Actions for Potential Intakes," is adhered to for the duration of the project.
- Verify that performance of EG&G and subcontractor-owned instruments has been conducted in accordance with the manufacturer's recommendations. The SSO

APPENDIX A

(Continued)

will also ensure that the test results are recorded daily in a calibration log specific to each instrument.

- Review and approve completed survey reports/forms. If an unsatisfactory report/form is received, it will be returned to the appropriate individual(s) for correction. When conducting that review the SSO will ensure that:
 - the correct report/form is complete
 - the entries are reasonable
 - the required signatures are affixed to the report
- Forward approved survey reports/forms to the EMRE and maintain a file of all completed Radiological Survey Forms. This file will be organized by survey areas, with an index placed in the front of the file.
- Immediately contact the EMR by phone when survey results indicate radiation levels exceeding 5 millirems/hour (mrem/h). For contaminant radiation levels requiring access controls not already established, or levels exceeding an established action level, the EMRE will also be notified.
- Maintain an Instrumentation Field Log Book which documents the specific equipment used at the work site.
- Interface with project manager in matters of health and safety.
- Report to CHSM and project manager on health and safety matters.
- Develop or review project health and safety plans prior to submittal to EG&G for review.
- Conduct staff training and orientation on health and safety related activities.
- Monitor compliance with health and safety plans and conduct site audits.
- Assist project managers with obtaining required health and safety equipment.
- Ensure compliance to relevant and appropriate OSHA requirements.

APPENDIX A (Continued)

Authority

- Suspend work or otherwise limit exposures to personnel if health and safety plans appear to be unsuitable or inadequate or if health or safety of personnel is endangered.
- Direct personnel to change work practices if existing practices are deemed to be hazardous to health and safety of personnel.
- Remove personnel from projects if their actions or condition endanger their health and safety or the health and safety of co-workers.

SITE MANAGER

Responsibilities

- Assure that the project is performed in a manner consistent with the health and safety program.
- Assure that the project health and safety plan is prepared, approved, and properly implemented.
- Provide the SSO with the information needed to develop health and safety plans.
- Coordinate with the SSO and project manager on health and safety matters.
- Assure compliance with health and safety plans.
- Assure that Environmental Management Division Operating Procedures are maintained and that the Health and Safety Specialist (HSS) reviews Document Change Notices for any health and safety implications.

Authority (Safety Related)

- Assign SSO-approved HSS to project and, if necessary, assign a suitably qualified replacement.
- Temporarily suspend field activities if health and safety of personnel are endangered, pending an evaluation by the SSO or CHSM.
- Temporarily suspend an individual from field activities for infractions of the Health and Safety Plan, pending an evaluation by the SSO or CHSM.

APPENDIX A (Continued)

HEALTH AND SAFETY SPECIALIST (HSS)

Responsibilities

- Conduct surveys and document the results, as required by the EMRGs, the applicable SSHSP, and the EG&G Rocky Flats Plant Site-Wide SOPs.
- Supervise Health and Safety Specialist-in-Training (HSST) during field activities.
- Countersign all reports/forms completed by the HSST.
- Forward completed survey reports/forms to the SSO.
- Notify the SSO of survey results that indicate radiation levels exceeding 5 mrem/h, levels requiring access controls not already established, or levels exceeding an established action level.
- Control access and advise all personnel when radiological precautions are required.
- Complete performance and operational checks required for radiation instruments and make entries in the Instrumentation Field Log Book.
- Direct health and safety activities on site.
- Provide a copy of the Health And Safety Plan to all field crews.
- Report immediately all safety-related incidents or accidents to the SSO and project manager.
- Assist project managers in all aspects of implementing health and safety plans.
- Maintain health and safety equipment on site.
- Implement emergency procedures as required.
- Be approved by EG&G Radiological Engineering and Industrial Hygiene to conduct radiological monitoring procedures as outlined by EMRGs and complete all other related tasks assigned to Health and Safety Specialist-in-Training (HSST).
- Maintain a file of Environmental Management Radiological Guidelines (EMRGs) and complete all responsibilities assigned to the Health and Safety Specialist.

APPENDIX A (Continued)

- Review Document Change Notices (DCNs) to Environmental Management Division Operating Procedures and, when necessary, implement appropriate health and safety procedures.
- Conduct monitoring for chemical and physical hazards.

Authority

- Temporarily suspend field activities if health and safety of personnel are endangered, pending further consideration by the HSO and/or CHMS.
- Temporarily suspend an individual from field activities for infractions of the Health and Safety Plan, pending further consideration by the HSO and/or CHMS.

HEALTH AND SAFETY SPECIALIST-IN-TRAINING (HSST):

The HSST shall assist the HSS in implementing this plan. An HSST will be present in the immediate vicinity during all field activities.

Responsibilities

- Participate in a formal training program designed to qualify subcontractor employees to be designated as Health and Safety Specialists by the EMRE.
- Conduct surveys and document the results as required by the EMRGs, the applicable SSHSP, and the EG&G Rocky Flats Plant Site-Wide SOPs.
- Notify the HSS of unanticipated radiation and contamination levels such as a lack of radioactivity where radioactivity is known to be present, or radiation or contamination levels exceeding anticipated levels.
- Request HSS countersignatures on all survey reports.
- Post required signs according to EMRG instructions.
- Ensure that each individual within his/her jurisdiction complies with the provisions of this plan.
- Audit safety practices used by on-site teams.
- Provide on-site air monitoring during field activities, if necessary.

APPENDIX A (Continued)

- Communicate with command post for on-site activities.
- Supervise decontamination, monitor workers for heat or cold stress, and distribute health and safety equipment if certified by RE and IH to perform these tasks.
- Document safety practices.
- Initiate appropriate emergency procedures.
- Be in an approved program by EG&G Radiological Engineering to conduct radiological monitoring procedures as outlined by EMRGs and complete all other related tasks assigned to Health and Safety Specialist-in-Training (HSST).

Authority

- The HSST shall have the authority to stop work in case of an imminent safety hazard or potentially dangerous situation; after stopping work, the HSST shall immediately consult the HSS and EG&G project manager.

APPENDIX B

**HISTORICAL CHARACTERISTICS OF RADIOISOTOPES
FOUND AT THE ROCKY FLATS ENVIRONMENTAL
TECHNOLOGY SITE**

The DOE Rocky Flats Plant produces "triggers" for nuclear weapons, which involves the processing and machining of plutonium, as well as the use of beryllium and other materials. Uranium and other radionuclides are known to be present on the site, either from process operations or from the disposal of wastes from other facilities.

Normal process releases from this facility are reported to be minimal, although there are several historical incidents that have released significant quantities of contaminants.

Plutonium can spontaneously combust in air, a characteristic which contributed to serious fires that released plutonium to the environment in 1957 and 1969. In 1969 a glovebox fire resulted in the release of several kilograms of plutonium to the environment. Analysis of soil samples, taken mostly east of DOE property, found up to 6 pCi/g on the top centimeter of soil (background is 0.04 pCi/g) shortly after this fire. In 1974 there was another accidental release of plutonium to the air.

Starting in 1958, barrels containing used machining fluids were stored outdoors at a location now called the 903 Pad. Leakage from the barrels was discovered in 1964. By 1968, the last barrels had been removed and the area was monitored for alpha activity. Levels of up to 13.5 μ Ci/g of soil were found, with activity penetrating to 8 inches deep. Rocks were removed from the area and fill was applied to the storage area, which was then paved. Additional fill was added to the area surrounding the 903 Pad in 1970 after soil sample analysis revealed greater than 50 pCi/g of alpha activity.

Other sites on the facility that may be significant contaminant sources include the West Spray Fields, an area east of the plant used for burial called the East Mounds, the 881 Hillside area, and the solar evaporation ponds. With the exception of the West Spray Fields, all of these locations are to the east of the new sanitary landfill sites.

The distribution of radioactive dusts in the environment is driven by prevailing wind patterns and drainage patterns at the Plant site. Both the prevailing winds and drainage patterns are west-to-east, with a significant north/south component for prevailing winds. This can be verified

by the distribution of radionuclides in the soil as reported by Rocky Flats Plant annual environmental reports.

Expected concentrations of plutonium near the areas of this work is thought to be approximately 0.05 pCi/gm (0.02 pCi/g [0.04 dis/min/g] is considered background). This level is well below levels considered hazardous. Reasonable dust control measures in areas containing 0.05 pCi/gm will provide adequate protection against exposure to plutonium by inhalation.

Elevated levels of plutonium have been measured in various areas in the buffer zone around the Rocky Flats Plant, primarily to the east of the facility. The highest levels of plutonium measured are to the east and south of the Plant, with the principal source being the 903 Pad. Soils at Indiana Avenue have been found to have an activity of 7.34 pCi/g.

Radionuclides of Concern

Pu^{239}

The predominant isotope present as an environmental contaminant is Pu^{239} . Major radiations from this material include the following:

alpha (He^{2+})	5.16 MeV (88%)
	5.11 MeV (11%)

Pu^{239} emits very little gamma (photons) of low energy, the most important being:

0.052 MeV (0.020%)

Pu^{239} is beta (e^-) stable.

The radiation of concern (alpha) is not sufficiently penetrating to penetrate the dead layers of the skin, which means Pu^{239} is not an external hazard. However, it is very important to avoid

inhalation or ingestion of this material, as alpha radiation may be very damaging from within the body.

Am^{241}

Am^{241} is a contaminant of weapons-grade plutonium, present at less than 20% of the concentration of Pu^{239} . Major radiations from this material include the following:

alpha (He^{2+})	5.49 MeV (85%)
	5.44 MeV (13%)

Am^{241} emits some gamma (photons) of low energy, the most important being:

0.060 MeV (36%)

Am^{241} is beta stable.

The radiation of concern (alpha) is not sufficiently penetrating to penetrate the dead layers of the skin, which means Am^{241} is not an external hazard. However, it is very important to avoid inhalation or ingestion of this material, as alpha radiation may be very damaging from within the body.

U^{235}

U^{235} is also known to be present in some soils at this site. U^{235} is normally present as 0.7 percent of the total uranium present. Major radiations from this material include the following:

alpha (He^{2+})	4.58 MeV (8%)
	4.40 MeV (57%)
	4.37 MeV (18%)

Gamma emissions are principally due to the presence of thorium daughter radiations, the most important being:

0.143 MeV (11%)

0.185 MeV (54%)

0.204 MeV (5%)

U^{235} is beta stable.

The radiation of concern (alpha) is not sufficiently penetrating to penetrate the dead layers of the skin, which means U^{235} is not an external hazard. However, it is very important to avoid inhalation or ingestion of this material, as alpha radiation may be very damaging from within the body. At concentrations much higher than are expected to be present at this site, U^{235} can be an external hazard from daughter gamma emissions.

U^{238}

U^{238} is also known to be present in some soils at this site. U^{238} is normally present as 99.276 percent of the total uranium present. Major radiations from this material include the following:

alpha (He^{2+})	4.20 MeV (75%)
	4.15 MeV (25%)
	4.37 MeV (18%)

Gamma emissions are principally due to the presence of daughter radiations, principally from Th^{234} and Pa^{234m} .

Beta emissions include:

(e^-)	0.030 MeV
	0.043 MeV

The radiation of concern (alpha) is not sufficiently penetrating to penetrate the dead layers of the skin, which means U^{238} is not an external hazard. However, it is very important to avoid inhalation or ingestion of this material, as alpha radiation may be very damaging from within

the body. At concentrations much higher than are expected to be present at this site, U^{238} can be an external hazard from daughter gamma emissions. The beta emissions are not sufficiently energetic to penetrate the outer (dead) layers of skin.

APPENDIX C

LIST OF CHEMICAL SUBSTANCES FOUND AT ROCKY FLATS PLANT

Note:

The reader should keep in mind that a material safety data sheet (MSDS) for a given substance provides information concerning the substance in a relatively pure form and that the substances that may be encountered during this project will be at very low concentrations from the view point of significant occupational exposures. MSDSs for chemicals of concern are kept on EG&G Environmental Restoration Office (T891E). Analyte concentrations for combined operable units 1-6 and Upper and Lower Interceptor ditches are provided in Table B-1.

APPENDIX D

**EXAMPLE ON-THE-JOB
TRAINING (OJT) FORM**

Name: _____ Extension _____
Job Title: _____ Department or Company: _____
Job Code: _____ Organization Code: _____
Employee #/SSN _____
Supervisor: _____ Extension _____ Mail Stop _____

PART ONE

Required for Admittance to RFP Courses 018-691-02 and 018-691-03

TSD WORKERS

At RFP, hazardous waste generators place RCRA hazardous waste in drums at satellite or 90 day storage areas. Waste generators are not generally considered "hazardous waste workers" under OSHA. (Hazardous waste generators receive Hazard Communication training to learn about the hazards of the chemicals with which they work)

1. Will you repackage drums of RCRA regulated waste *after* they have been initially packaged by the generator? ☐ No ☐ Yes
2. Will you be directly involved in RCRA hazardous waste treatment? ☐ No ☐ Yes
If 'Yes', at what location? _____
3. Are you potentially exposed to hazardous waste at a permitted or interim status TSD storage area during routine (non-emergency) operations? ☐ No ☐ Yes

ENVIRONMENTAL RESTORATION SITE WORKERS

At RFP, environmental restoration sites are referred to as "operable units" or OU's. When an OU exists in a building, *only* the portion of the building scheduled for environmental investigation or remediation is considered the OU.

4. Will you perform or field supervise environmental investigation or remediation activities at an OU? ☐ No ☐ Yes
5. Will you perform maintenance or other non-environmental activities at an OU? ☐ No ☐ Yes
If 'Yes', what activities? _____
6. Will you tour or audit an OU? ☐ No ☐ Yes

If You Checked "Yes" to Any of Items 4-6. Complete the Following:

7. Will you be required to wear Level A or B PPE at an OU? ☐ No ☐ Yes
8. Will you be required to wear Level C PPE at an OU? ☐ No ☐ Yes

IF YOU CHECKED "YES" TO ANY OF ITEMS 1-6, COMPLETE THE FOLLOWING:

8. Are you likely to perform any of tasks 1-5 for 30 or more days per year? ☐ No ☐ Yes
9. Are you likely to wear a respirator for 30 or more days per year? ☐ No ☐ Yes

Supervisor _____
Print Name _____ Signature _____ Date _____
Employee _____
Print Name _____ Signature _____ Date _____

FOR INDUSTRIAL HYGIENE REPRESENTATIVE ONLY

Date Form Received _____ Date Form Completed _____

Employee Requires: (check one) ☐ 24-Hour, #018-691-02 ☐ 40-Hour, #018-691-03 ☐ No HAZWOPER Training
(check one) ☐ 1 Day Field Experience ☐ 3 Day Field Experience ☐ No Field Experience
(check one) ☐ Hazardous Waste Medical Surveillance ☐ No Hazardous Waste Medical

Industrial Hygiene Rep. _____
Print Name _____ Signature _____ Date _____

* Part Two is only required for work in an OU, it is not required for work in a TSD.

Employee has Completed: (check one) ☐ 24-Hour, #018-691-02 ☐ 40-Hour, #018-691-03
and per Part One requires: (check one) ☐ 1 Day Field Experience ☐ 3 Day Field Experience

Representative

Print Name

Signature _____

Date _____

Employee has Completed:	(check one)	<input type="checkbox"/> 24-Hour	<input type="checkbox"/> 40-Hour
Course Source			Course Date
and requires:	(check one)	<input type="checkbox"/> 1 Day Field Experience	<input type="checkbox"/> 3 Day Field Experience
or has attached proof of:	(check one)	<input type="checkbox"/> 1 Day Field Experience	<input type="checkbox"/> 3 Day Field Experience

Supervisor

Print Name _____

Signature

Date _____

Environmental Restoration Tasks

- a. Site reconnaissance, inspection or audit
- b. Drilling or similar activity
soil boring, well installation, cone penetrometer
- c. Environmental media sampling
soil, soil gas, surface water, groundwater
- d. Excavation
- e. Contaminant treatment system installation,
operation or maintenance
- f. Other, specify _____

- g. Utilities system maintenance
water, electricity, sewer
- h. Soil disturbance
excavations, grading, hand digging
- i. Equipment maintenance
- j. Other, specify _____

Student has completed at least: ☐ 1 Day (8 hours) ☐ 3 Days (24 hours) of supervised work in an OU
(check one) Course #009-691-01 Course #018-691-07

Supervisor

Print Name _____

Signature

Date _____

Employee

APPENDIX E

AIR MONITORING SURVEY RESULTS

Historical Air Monitoring Results

Results of air monitoring surveys conducted at wells in the Groundwater Monitoring Program have been compiled for utilization in determining future air monitoring and PPE requirements at these wells. Table E-1 lists all wells currently included in the program. Table E-2 provides results of air monitoring at all wells, upon opening and after venting. Background, breathing zone, and well head readings are also provided in Table E-2. Table E-3 provides similar data, but only for wells with positive readings. Additionally, variances between background and breathing zone or well head readings are provided in Table E-3.

Following is an explanation of codes utilized in Tables E-1, E-2, and E-3.

Well ID: Identification number for well.

Status: Sample = well is included in the sampling program.
WLM = well is included only in the Water Level Measurement program.
ND = well has not been developed.

Year: Year in which air monitoring was conducted.

Qtr: Quarter in which air monitoring was conducted.

Survey Results: Results of air monitoring survey, as provided by air HNu PA-101 photoionization detector. All results provided in parts per million (ppm)

At opening = air monitoring results from survey conducted immediately after opening the well casing cap.

BG = Background. Reading from survey conducted in airspace upwind and away from well.

BZ = Breathing Zone. Reading from survey conducted in the field crew breathing zone.

WH = Wellhead. Reading from survey conducted at the top of the well casing.

BZ Diff = Breathing Zone Difference. Variance between background and breathing zone readings. Negative value indicates that the breathing zone reading was below the background reading.

WH Diff = Wellhead Difference. Variance between background and wellhead readings. Negative value indicates that the wellhead reading was below the background reading.

TABLE E-1
ROCKY FLATS GROUNDWATER WELLS
RESEARCHED FOR
AIR MONITORING DATA

Well ID	Status	Well ID	Status	Well ID	Status	Well ID	Status	Well ID	Status	Well ID	Status	Well ID	Status
5070	WLM	1487BR	SAMPLE	B203789	WLM	P114989	SAMPLE	04591	SAMPLE	38291	SAMPLE	43993	WLM
5074	WLM	1587	SAMPLE	B203889	WLM	P115089	SAMPLE	04691	SAMPLE	38591	SAMPLE	44893	WLM
5174	WLM	1687BR	SAMPLE	B203989	WLM	B315289	WLM	04891	WLM	38891	SAMPLE	44993	WLM
5274	WLM	1887BR	SAMPLE	B204089	WLM	P115489	SAMPLE	04991	SAMPLE	38991	SAMPLE	45093	WLM
5374	WLM	1987	SAMPLE	B204189	WLM	P115589	SAMPLE	05091	SAMPLE	39191	SAMPLE	45293	WLM
5474	WLM	2087BR	WLM	B304789	WLM	P115689	SAMPLE	05191	SAMPLE	39291	SAMPLE	45393	WLM
5774	WLM	2187	SAMPLE	B304889	WLM	P215789	SAMPLE	05291	ND	39691	SAMPLE	45593	WLM
5874	WLM	2287BR	SAMPLE	B304989	WLM	P415889	SAMPLE	05391	SAMPLE	40491	WLM	45693	WLM
5974	WLM	2387BR	WLM	B405189	WLM	P415989	SAMPLE	05691	SAMPLE	40791	WLM	45793	WLM
6074	WLM	2487	SAMPLE	B405289	WLM	P416089	SAMPLE	05991	WLM	40991	WLM	45893	WLM
6174	WLM	2587BR	SAMPLE	B305389	WLM	P416189	SAMPLE	06091	SAMPLE	41091	SAMPLE	45993	WLM
6274	WLM	2687	WLM	B405489	WLM	P416289	SAMPLE	06191	SAMPLE	41491	SAMPLE	46093	WLM
6374	WLM	2787	WLM	B205589	WLM	P416389	SAMPLE	06291	SAMPLE	41591	SAMPLE	46193	WLM
0186	SAMPLE	2887BR	SAMPLE	B405689	WLM	P416489	SAMPLE	06391	WLM	41691	SAMPLE	46293	WLM
0386	SAMPLE	2987	SAMPLE	B405789	WLM	P416589	SAMPLE	06491	SAMPLE	45391	SAMPLE	46393	WLM
0586	SAMPLE	3087BR	SAMPLE	B405889	WLM	P416689	SAMPLE	06591	SAMPLE	03092	ND	46493	WLM
0686	WLM	3187BR	SAMPLE	B405989	WLM	P416789	SAMPLE	06691	SAMPLE	03192	ND	51193	SAMPLE
0786	SAMPLE	3287	WLM	B106089	SAMPLE	P416889	SAMPLE	06791	SAMPLE	10092	SAMPLE	58793	SAMPLE
0886	SAMPLE	3387	SAMPLE	B206289	SAMPLE	P416989	SAMPLE	06891	SAMPLE	10192	SAMPLE	59093	ND
0986	SAMPLE	3487BR	SAMPLE	B206489	SAMPLE	B317189	WLM	06991	SAMPLE	10292	SAMPLE	59393	SAMPLE
1086	SAMPLE	3587	WLM	B206589	SAMPLE	B217289	SAMPLE	07191	SAMPLE	10392	SAMPLE	59493	SAMPLE
1386	SAMPLE	3687BR	SAMPLE	B206689	SAMPLE	B217489	WLM	07291	SAMPLE	10492	SAMPLE	59593	SAMPLE
1486	SAMPLE	3887	SAMPLE	B206789	SAMPLE	B217789	WLM	07391	SAMPLE	10592	SAMPLE	59793	ND
1586	SAMPLE	3987	SAMPLE	B206889	SAMPLE	P317989	WLM	07891	SAMPLE	10692	SAMPLE	61293	ND
1686	SAMPLE	4087	WLM	B206989	SAMPLE	P218089	WLM	07991	SAMPLE	10792	SAMPLE	63093	SAMPLE
1786	SAMPLE	4187BR	SAMPLE	B207089	SAMPLE	P218289	SAMPLE	08091	SAMPLE	10892	SAMPLE	70093	SAMPLE
1886	WLM	4287	SAMPLE	B207289	WLM	P218389	SAMPLE	08291	WLM	10992	SAMPLE	70193	SAMPLE
1986	SAMPLE	4387	WLM	P207389	SAMPLE	B218789	WLM	08391	WLM	11092	SAMPLE	70293	SAMPLE
2186	SAMPLE	4487	WLM	P207589	SAMPLE	P219189	SAMPLE	08491	WLM	43392	SAMPLE	70393	SAMPLE
2286	SAMPLE	4587BR	SAMPLE	P207689	SAMPLE	P119389	SAMPLE	08591	WLM	43492	SAMPLE	70493	SAMPLE
2386	SAMPLE	4787	WLM	P207789	SAMPLE	P219489	SAMPLE	08891	SAMPLE	46192	SAMPLE	70593	SAMPLE
2486	SAMPLE	4887	WLM	P207889	SAMPLE	P219589	SAMPLE	09091	SAMPLE	46292	SAMPLE	70693	SAMPLE
2586	SAMPLE	4987	WLM	P207989	SAMPLE	P419689	SAMPLE	09691	SAMPLE	46392	SAMPLE	70893	SAMPLE
2686	SAMPLE	5087	WLM	B208089	SAMPLE	P320089	SAMPLE	10991	SAMPLE	46492	SAMPLE	71193	SAMPLE
2786	SAMPLE	5187	SAMPLE	B208189	SAMPLE	B220189	WLM	11291	WLM	46692	SAMPLE	71493	SAMPLE
2986	WLM	5287	SAMPLE	B208289	SAMPLE	B220489	WLM	11491	WLM	46792	SAMPLE	71693	SAMPLE
3086	SAMPLE	5387	WLM	B208389	WLM	0190	SAMPLE	11691	SAMPLE	46892	SAMPLE	71893	SAMPLE
3186	WLM	5487	SAMPLE	B208489	WLM	0290	SAMPLE	11791	SAMPLE	49192	SAMPLE	72093	SAMPLE
3286	SAMPLE	5587	SAMPLE	B208589	WLM	0390	SAMPLE	11891	SAMPLE	49292	SAMPLE	72293	SAMPLE
3386	SAMPLE	5687	SAMPLE	B208689	SAMPLE	0590	WLM	12091	SAMPLE	50092	SAMPLE	72393	SAMPLE
3486	SAMPLE	5887	SAMPLE	B208789	WLM	0690	WLM	12191	SAMPLE	50192	ND	72493	ND
3586	SAMPLE	6087	SAMPLE	P208889	SAMPLE	0790	WLM	12291	SAMPLE	50292	ND		
3686	SAMPLE	6187	SAMPLE	P208989	SAMPLE	0990	WLM	12391	SAMPLE	75092	SAMPLE		
3786	SAMPLE	6287	WLM	P209089	SAMPLE	1490	SAMPLE	12491	SAMPLE	75292	SAMPLE		
3886	SAMPLE	6487	SAMPLE	P209189	WLM	00191	SAMPLE	12691	SAMPLE	75892	ND		
3986	SAMPLE	6587	SAMPLE	P209289	SAMPLE	00291	SAMPLE	12891	WLM	75992	SAMPLE		
4086	SAMPLE	6687	SAMPLE	P209389	SAMPLE	00391	SAMPLE	12991	SAMPLE	76192	ND		
4186	WLM	6887	SAMPLE	P209489	SAMPLE	00491	SAMPLE	13091	SAMPLE	76292	SAMPLE		
4286	SAMPLE	7087	SAMPLE	P209589	SAMPLE	00691	SAMPLE	13191	SAMPLE	76792	ND		
4386	SAMPLE	7187	SAMPLE	P209689	SAMPLE	00791	WLM	13291	SAMPLE	76992	ND		
4486	WLM	7287	SAMPLE	P209789	SAMPLE	00891	WLM	13391	SAMPLE	77192	ND		
4686	SAMPLE	B400089	WLM	P209889	SAMPLE	00991	WLM	13491	SAMPLE	77392	ND		
4786	SAMPLE	B400189	WLM	P209989	WLM	01291	SAMPLE	13591	WLM	77492	SAMPLE		
4886	SAMPLE	B400289	WLM	P210089	SAMPLE	01391	SAMPLE	20591	WLM	00193	ND		
4986	SAMPLE	B400389	WLM	P210189	SAMPLE	01491	SAMPLE	20691	WLM	00293	SAMPLE		
5086	SAMPLE	B400489	WLM	B210389	WLM	01791	SAMPLE	20791	WLM	00393	SAMPLE		
5186	SAMPLE	B200589	WLM	B210489	SAMPLE	01891	SAMPLE	30991	SAMPLE	00493	ND		
5286	WLM	B200689	WLM	B410589	SAMPLE	01991	SAMPLE	31491	WLM	05093	SAMPLE		
5386	SAMPLE	B200789	WLM	B410689	SAMPLE	02091	SAMPLE	31791	SAMPLE	05193	SAMPLE		
5486	WLM	B200889	WLM	B410789	SAMPLE	02191	WLM	31891	SAMPLE	05293	SAMPLE		
B405586	WLM	B201089	WLM	B110889	SAMPLE	02291	SAMPLE	32591	SAMPLE	05393	ND		
5686	SAMPLE	B201189	WLM	B110989	SAMPLE	02391	WLM	33491	SAMPLE	22093	SAMPLE		
5786	SAMPLE	B201289	WLM	B111189	SAMPLE	02491	SAMPLE	33691	WLM	22193	SAMPLE		
5886	WLM	B201589	WLM	B411289	SAMPLE	02591	SAMPLE	33891	SAMPLE	22293	SAMPLE		
6186	SAMPLE	B401989	WLM	B411389	SAMPLE	02691	SAMPLE	34591	WLM	22393	SAMPLE		
6286	SAMPLE	B302089	WLM	P313489	SAMPLE	02791	WLM	34791	SAMPLE	22593	SAMPLE		
6386	SAMPLE	B402189	WLM	P313589	SAMPLE	02891	WLM	35391	SAMPLE	23193	SAMPLE		
6486	SAMPLE	B102289	WLM	P213689	SAMPLE	02991	SAMPLE	35691	SAMPLE	23293	ND		
6586	SAMPLE	B102389	WLM	B213789	SAMPLE	03091	SAMPLE	35991	WLM	40193	WLM		
6686	SAMPLE	B202489	WLM	P213889	WLM	03191	WLM	36191	SAMPLE	40293	WLM		
6786	WLM	B202589	WLM	P213989	WLM	03391	SAMPLE	36391	SAMPLE	40393	WLM		
6886	SAMPLE	B402689	WLM	P314089	SAMPLE	03591	SAMPLE	36691	SAMPLE	40593	WLM		
7086	SAMPLE	B302789	WLM	P414189	SAMPLE	03691	SAMPLE	36991	WLM	41193	WLM		
0187	SAMPLE	B302889	WLM	P314289	SAMPLE	03791	SAMPLE	37191	SAMPLE	41693	WLM		
0487	SAMPLE	B302989	WLM	P114389	SAMPLE	03891	WLM	37591	SAMPLE	41993	WLM		
0587BR	SAMPLE	B303089	WLM	P114489	SAMPLE	03991	SAMPLE	37691	SAMPLE	42393	WLM		
0987	SAMPLE	B203189	WLM	P114589	SAMPLE	04091	SAMPLE	37791	SAMPLE	42993	WLM		
1087	SAMPLE	B203289	WLM	P114689	SAMPLE	04191	SAMPLE	37891	SAMPLE	43293	WLM		
1187	SAMPLE	B203489	WLM	P114789	SAMPLE	04291	SAMPLE	37991	SAMPLE	43593	WLM		
1287	SAMPLE	B203589	WLM	P114889	SAMPLE	04491	SAMPLE	38191	SAMPLE	43893	WLM		

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HN₂ READINGS

ROCKY FLATS GROUNDWATER SAMPLING RING READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
5070	WLM	1994	2	0	0	0				
		1994	1	0	0	0				
5074	WLM	1994	2	0	0	0				
5174	WLM	1994	2	0	0	0				
5274	WLM	1994	2	0	0	0				
5374	WLM	1994	2	0	0	0				
5474	WLM	1993	4	5	5	5				
		1994	2	0	0	0				
		1996	4	5	5	5				
5774	WLM	1994	2	0	0	0				
5874	WLM	1994	2	0	0	0				
5974	WLM	1993	4	5	5	5				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	5	5	5				
6074	WLM	1994	2	0	0	0				
6174	WLM	1994	2	0	0	0				
6274	WLM	1994	2	0	0	0				
6374	WLM	1993	4	5	5	5				
		1994	2	0	0	0				
		1993	4	4.2	4.2	4.2				
0186	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.1	0.1	0.1				
		1992	2	0.1	0.1	0.1				
0386	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0	0	0				
		1994	2	0	0	0				
		1994	1	0.6	0.6	0.6				
0586	SAMPLE	1993	4	1.2	1.2	3	0.2	0.2	0.2	
		1993	3	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1993	2	0.4	0.4	0.4				
		1992	3	0.4	0.4	0.4				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0.2	0.2	0.2				
0686	WLM	1991	4	0.2	0.2	0.2				
		1991	3	0.3	0.3	0.3				
		1991	2	2	1.8	0.4				
		1994	2	0	0	0				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0.2	0.2	0.2				
0786	SAMPLE	1991	4	0.2	0.2	0.2				
		1991	3	0.3	0.3	0.3				
		1991	2	2	1.8	0.4				
		1994	2	0	0	0				
		1994	1	10.8	10.8	10.8				
		1993	4	0.2	0.2	0.2				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING H₂O READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
0886	SAMPLE	1993	3	0.2	0.2	0.2				
		1993	1	0.8	0.8	0.8				
		1992	3	0.2	0.2	0.2				
		1992	2	1.4	1.4	3.2	0.5	0.5	0.5	
		1992	1	0.3	0.2	0.2				
		1994	2	0	0	0				
		1994	1	2	2	2				
		1993	4	0.3	0.3	0.3				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
0986	SAMPLE	1993	1	0.8	0.8	0.8				
		1992	3	0.2	0.2	0.2				
		1992	2	1.6	1.6	1.6				
		1994	2	0	0	0				
		1994	1	0.4	0.4	0.4				
		1993	3	0.1	0.1	0.1				
		1993	2	0.4	0.4	0.4				
		1993	1	0.6	0.6	0.6				
		1992	3	0.2	0.2	0.2				
		1992	2	1.6	1.6	1.6				
1086	SAMPLE	1992	1	0.3	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.3	0.3	0.3				
		1993	1	0.3	0.3	0.3				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
1386	SAMPLE	1993	4	0.2	0.2	0.2				
		1994	1	6.7	6.7	6.7				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1992	3	0.2	0.2	0.4	0.4	0.4	0.4	
		1992	2	0.4	0.4	0.3	0.8	0.8	0.8	
		1992	1	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	2.4	2.4	2.4				
		1993	4	0.2	0.2	0.2				
1486	SAMPLE	1993	3	0.4	0.4	0.4				
		1993	2	0.4	0.4	0.4				
		1992	3	0.2	0.2	0.4	0.1	0.1	0.1	
		1992	2	0.4	0.4	0.3				
		1992	1	0.3	0.2	0.2				
		1994	2	0	0	0				
		1994	1	4.6	4.6	4.6				
		1993	4	0.2	0.2	0.2				
		1993	3	0.4	0.4	0.4				
		1993	2	0.5	0.5	0.5				
1586	SAMPLE	1993	1	0.4	0.4	0.4				
		1992	2	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.2				
		1994	2	0	0	0				
		1994	1	4.6	4.6	4.6				
		1993	4	0.2	0.2	0.2				
		1993	3	0.4	0.4	0.4				
		1993	2	0.5	0.5	0.5				
		1993	1	0.4	0.4	0.4				
		1992	2	0.2	0.2	0.2				
1686	SAMPLE	1992	2	0.4	0.4	0.2				
		1994	2	0	0	0				
		1994	1	2.6	2.6	2.6				

TABLE E-2
ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
1786	SAMPLE	1993	4	0.3	0.3	0.3				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1993	1	0.3	0.3	0.3				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.3				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
1886	WLM	1993	2	0	0	0				
		1993	1	0.6	0.6	0.6				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	5.8	5.9	5.9				No venting data
		1993	2	0.1	0.1	0.1				
		1992	3	0.3	0.3	0.4	0.6	0.6	0.4	
		1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.2	0.2				
1986	SAMPLE	1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.4	0.4	0.4				
		1993	2	0.1	0.1	0.1				
		1992	3	0.4	0.4	0.4				
		1992	2	0.3	0.3	0.3				
		1992	1	0.4	0.4	0.4				
		1991	4	0.4	0.4	0.9	0.2	0.2	0.2	
2186	SAMPLE	1994	2	0	0	0				
		1994	1	4.4	4.4	4.4				
		1993	4	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.4	0.4	0.4				
		1991	4	0.4	0.4	0.4				
		1991	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	3.6	3.6	3.6				
2286	SAMPLE	1993	4	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
		1993	1	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.4	0.2	0.2				
		1994	2	0	0	0				
		1994	1	3.6	3.6	3.6				
		1993	4	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
2386	SAMPLE	1993	1	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.4	0.2	0.2				
		1994	2	0	0	0				
		1994	1	3.2	3.2	3.2				
		1993	4	0.5	0.5	0.5				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1993	1	0.4	0.4	0.4				
2486	SAMPLE	1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING H₂O READINGS

ROCKY PLATS GROUNDWATER SAMPLING TIME READINGS											
Well ID	Status	Year	Qtr	Survey Results						COMMENTS	
				At Opening			After Venting				
				BG	BZ	WH	BG	BZ	WH		
2586	SAMPLE	1994	1	0.5	0.5	0.5					
		1993	3	0.3	0.3	0.3					
		1993	2	0.4	0.4	0.4					
		1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.3					
		1992	1	0.2	0.2	0.2					
		1991	4	0.4	0.4	0.8	0	0	0		
		1994	2	0	0	0					
		1994	1	0	0	0					
		1993	4	0.4	0.4	0.4					
		1993	3	0.3	0.3	0.3					
		1993	2	0.4	0.4	0.4					
		1993	1	0.2	0.2	0.2					
		1992	3	0.3	0.3	0.3					
2686	SAMPLE	1992	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1994	1	10.8	10.8	10.8					
		1993	4	0.4	0.4	0.4					
		1993	3	0.3	0.3	0.3					
		1993	2	0.4	0.4	0.4					
		1993	1	0.2	0.2	0.2					
		1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1994	1	3.2	3.2	3.2					
		1993	3	0.3	0.3	0.3					
		1993	2	0.2	0.2	0.2					
		1993	1	1	1	1					
2786	SAMPLE	1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1994	1	3.2	3.2	3.2					
		1993	3	0.3	0.3	0.3					
		1993	2	0.2	0.2	0.2					
		1993	1	1	1	1					
		1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.2					
		1992	1	0.2	0.2	0.2					
		1994	2	0	0	0					
		1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.3					
		1992	1	0.3	0.3	0.3					
2986	WLM	1991	4	0.2	0.2	0.2					
		1991	3	0.4	0.4	0.4					
		1991	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1994	1	3	3	3					
		1993	4	0.5	0.5	0.5					
		1993	3	0.3	0.3	0.3					
		1993	2	0.2	0.2	0.2					
		1993	1	0.5	0.5	0.5					
		1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.3					
		1992	1	0.2	0.2	0.2					
		1991	4	0.2	0.2	0.2					
		1991	3	0.4	0.4	0.4					
3086	SAMPLE	1991	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1994	1	3	3	3					
		1993	4	0.5	0.5	0.5					
		1993	3	0.3	0.3	0.3					
		1993	2	0.2	0.2	0.2					
		1993	1	0.5	0.5	0.5					
		1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1994	1	0.6	0.6	0.6					
		1993	2	0.1	0.1	0.1					
		1992	3	0.3	0.3	0.3					
		1992	3	0.3	0.3	0.3					
3186	WLM	1991	4	0.4	0.4	0.4					
		1991	3	0.2	0.2	0.2					
		1991	2	0.4	0.4	0.4					
		1994	2	0	0	0					
		1994	1	0.6	0.6	0.6					
		1993	2	0.1	0.1	0.1					
		1992	3	0.3	0.3	0.3					
		1992	3	0.3	0.3	0.3					
		1991	4	0.4	0.4	0.4					
		1991	3	0.2	0.2	0.2					
		1991	2	0.4	0.4	0.4					
		1994	2	0	0	0					
		3286	SAMPLE	1994	2	0	0	0			

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
3386	SAMPLE	1994	1	2.3	2.3	2.3				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.6	0.6	0.6				
		1993	3	0.3	0.3	0.3				
		1993	2	0.1	0.1	0.1				
		1992	3	0.3	0.3	0.3				
3486	SAMPLE	1992	2	0.3	0.3	0.3				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
		1992	3	0.4	0.4	0.3				
		1992	2	0.8	0.8	0.8				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		3586	SAMPLE	1994	2	0	0	0		
1994	1			0.3	0.3	0.3				
1993	3			0.2	0.2	0.2				
1993	2			0.2	0.2	0.2				
1992	3			0.3	0.3	0.2				
1992	2			0.8	0.8	0.8				
1992	1			0.2	0.2	0.2				
1991	4			0.3	0.3	0.3				
1994	2			0	0	0				
1994	1			5.5	5.6	5.7			No venting data	
1993	3			0.1	0.1	0.1				
1993	2			0.4	0.4	0.4				
3686	SAMPLE	1993	1	0.6	0.6	0.6				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	1.8	1.8	1.8				
		1993	3	0.3	0.3	0.3				
		1993	2	0.6	0.6	0.6				
		1993	1	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.2				
		1992	2	0.4	0.4	0.3				
		1992	1	0.2	0.2	0.2				
3786	SAMPLE	1994	2	0	0	0				
		1994	1	5.9	6	6.2			No venting data	
		1993	4	0.2	0.2	0.2				
		1993	3	0.1	0.1	0.1				
		1993	2	0.4	0.4	0.4				
		1993	1	0.4	0.4	0.4				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	5.9	6	6.2				
		3886	SAMPLE	1993	4	0.2	0.2	0.2		
1993	3			0.1	0.1	0.1				
1993	2			0.4	0.4	0.4				
1993	1			0.4	0.4	0.4				
1992	3			0.2	0.2	0.2				
1992	2			0.4	0.4	0.4				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
3986	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	1	1	1				
		1992	2	0.4	0.4	0.3				
		1992	1	0.2	0.2	0.2				
4086	SAMPLE	1994	2	0	0	0				
		1993	4	1.1	1.1	1.1				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	0.1	0.1	0.1				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
4186	WLM	1992	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	2	0.4	0.4	0.4				
		1992	3	0.2	0.2	0.2				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
		1991	4	0.3	0.3	0.3				
		1991	3	0.1	0.1	0.1				
4286	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1993	4	0.5	0.5	0.5				
		1992	3	0.2	0.2	0.2				
		1992	2	0.2	0.2	0.2				
4386	SAMPLE	1994	2	0	0	0				
		1994	1	9	9	9				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
		1992	3	0.5	0.5	0.5				
		1992	2	0.9	0.9	0.9				
		1992	1	0.3	0.3	0.3				
		1991	4	0.3	0.3	0.3				
4486	WLM	1994	2	0	0	0				
		1994	1	0.9	0.9	0.9				
		1992	3	0.4	0.4	0.4				
		1992	2	0.3	0.3	0.3				
		1992	1	0.1	0.1	0.1				
		1991	4	0	0	0				
		1991	3	0.4	0.4	0.4				
		1991	2	0.3	0.3	0.3				
4686	SAMPLE	1994	2	0	0	0				
		1994	1	0.3	0.3	0.3				
		1993	4	0.6	0.6	0.6				
		1993	3	0.3	0.3	0.3				
		1993	2	0.6	0.6	0.6				
		1993	1	0.2	0.2	0.2				
		1992	3	1.1	1.1	1.1				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
4786	SAMPLE	1992	2	0.7	0.7	0.7				
		1994	2	0	0	0				
		1994	1	2	2	2				
		1993	4	2.2	2.2	2.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1992	3	0.9	0.9	0.9				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
4886	SAMPLE	1994	2	0	0	0				
		1994	1	1.9	1.9	1.9				
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1993	1	0.5	0.5	0.5				
		1992	3	2.8	2.8	2.8				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
4986	SAMPLE	1994	2	0	0	0				
		1994	1	5	5	5				
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	0.5	0.5	0.5				
		1992	2	0.6	0.6	0.5				
		1992	1	0.2	0.2	0.2				
5086	SAMPLE	1994	2	0	0	0				
		1994	1	3	3	3				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.3	0.3	0.3				
		1992	3	0.7	0.7	0.7				
		1992	2	0.8	0.8	0.8				
		1992	1	0.2	0.2	0.2				
		1992	1	0.2	0.2	0.2				
5186	SAMPLE	1994	2	0	0	0				
		1994	1	5.7	5.7	5.7				
		1993	4	2.1	2.1	2.1				
		1993	3	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.6	0.6	0.6				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
5286	WLM	1994	2	0	0	0				
		1994	1	1	1	1				
		1993	1	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.6	0.6	0.6				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1991	2	0.2	0.2	0.2				
5386	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	2	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
		1993	1	0.6	0.6	0.6				
		1992	3	3.2	3.2	3.2				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
5486	WLM	1992	2	0.1	0.1	0.1				
		1992	1	0.1	0.1	0.1				
		1994	2	0	0	0				
		1993	2	0.4	0.4	0.4				
		1992	3	1.6	1.6	1.8	0.4	0.4	0.4	
		1992	2	0.8	0.8	0.8				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.4	0	0	0	
		1991	3	0.2	0.2	0.2				
		1991	2	0.4	0.4	0.4				
B405586 =5586	WLM	1994	2	0	0	0				
		1993	2	0.1	0.1	0.1				
		1993	1	0.4	0.4	0.4				
		1992	3	1.8	2.8	3.2	0.4	0.4	0.4	
		1992	2	0.8	0.8	0.8				
		1992	1	0	0	0				
		1991	4	0.2	0.2	0.2				
		1991	2	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	2.8	2.8	2.8				
5686	SAMPLE	1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	0.5	0.5	0.5				
		1992	2	0.8	0.8	0.8				
		1991	3	0.2	0	0				
		1991	4	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	2	0.8	0.8	0.8				
		1993	1	0.2	0.2	0.2				
5786	SAMPLE	1992	3	0.6	0.6	0.5				
		1992	2	0.7	0.7	0.6				
		1992	1	0.2	0.2	0.2				
		1991	4	0	0.1	0.1	0.3	0.3	0.3	
		1994	2	0	0	0				
		1993	2	0.4	0.4	0.4				
		1992	3	0.6	0.6	0.5				
		1992	2	0.7	0.7	0.7				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
5886	WLM	1991	3	0.3	0.3	0.3				
		1991	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1993	2	0.4	0.4	0.4				
		1992	3	0.6	0.6	0.5				
		1992	2	0.7	0.7	0.7				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1991	3	0.3	0.3	0.3				
		1991	2	0.3	0.3	0.3				
6186	SAMPLE	1994	2	0	0	0				
		1994	1	6.2	6.2	6.2				
		1993	4	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.3	0.3	0.2				
		1992	1	0.1	0.1	0.1				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1991	2	0.3	0.3	0.3				
		1994	2	0	0	0				
6286	SAMPLE	1994	1	0.3	0.3	0.3				
		1993	3	0.1	0.1	0.1				
		1993	2	0.6	0.6	0.6				
		1993	1	0.2	0.2	0.2				
		1993	3	0.1	0.1	0.1				
		1993	2	0.6	0.6	0.6				

TABLE E-2
ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HING READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
6386	SAMPLE	1992	3	0.4	0.4	0.4				
		1992	2	4	4	4				
		1992	1	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1992	3	2.4	2.4	2.4				
		1992	2	4	4	4				
6486	SAMPLE	1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.1				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	3	0.2	0.2	0.2				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.8	0.8	0.8				
6586	SAMPLE	1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	3	0	0	0				
		1993	1	0.7	0.7	0.7				
		1992	3	0.2	0.2	0.2				
		1992	2	0.6	0.6	0.6				
		1992	1	0.2	0.2	0.2				
		1991	4	0.1	0.1	0.1				
6686	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.2	0.2	0.2				
		1992	2	0.7	0.7	0.7				
		1994	2	0	0	0				
6786	WLM	1993	2	0.1	0.1	0.1				
		1992	3	0.3	0.3	0.3				
		1992	2	0.7	0.7	0.4				
		1991	4	0.2	0.2	0.1				
		1991	3	0.2	0.2	0.2				
		1991	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
6886	SAMPLE	1993	1	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.1	0.1	0.1				
		1991	4	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
7086	SAMPLE	1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.1	0.1	0.1				
		1991	4	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	3	0.5	0.5	0.5				
		1993	2	0.3	0.3	0.3				
		1993	1	0.9	0.9	0.9				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
0187	SAMPLE	1992	3	0.6	0.6	0.6				
		1992	2	0.2	0.2	0.2				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	6	6	6				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.5	0.5	0.5				
		1992	3	0.2	0.2	0.2				
0487	SAMPLE	1992	2	0.2	0.2	0.2				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	12	1.2	1.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1993	4	0	0	0				
		1992	3	0.2	0.2	0.2				
		1992	2	0.2	0.2	0.2				
0587BR	SAMPLE	1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	2.2	2.2	2.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	0.5				
		1992	1	0.3	0.3	0.3				
0987	SAMPLE	1994	2	0	0	0				
		1994	1	1	1	1				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
		1993	1	0.8	0.8	0.8				
		1992	3	2	2	2				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
1087	SAMPLE	1994	1	1	1	1				
		1993	2	0.3	0.3	0.3				
		1993	1	0.8	0.8	0.8				
		1992	3	1.9	1.9	1.9				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.8	0.8	0.8				
1187	SAMPLE	1992	3	1.9	1.9	1.9				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
1287	SAMPLE	1992	3	0.4	0.4	0.4				
		1992	2	4	4	5	0.4	0.4	0.4	
		1992	1	0.3	0.3	0.3	0.3	0.3	0.3	
		1994	2	0	0	0				
		1994	1	9	9	9				
		1993	3	0	0.4	0.8				No venting data
		1993	2	0.3	0.3	0.3				

TABLE E-2
ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
1487BR	SAMPLE	1992	3	0.2	0.2	0.3	0.4	0.4	1.2	Day 2
		1992	2	0.4	0.4	1.2	0.3	0.3	0.3	Day 2
		1992	1	0.1	0.1	0.4	0.3	0.3	0.3	
		1991	4	0.1	0.1	0.2	0.3	0.3	0.3	
		1994	2	0	0	0				
		1994	1	5.4	5.4	5.4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				
1587	SAMPLE	1992	2	0.4	0.4	0.4				
		1992	1	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	1.4	1.4	3	2.5	2.5	2.5	
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1993	1	0.5	0.5	0.5				
		1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.4	0.4	4	4	4	
1687BR	SAMPLE	1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0.3	0.3	0.3				
		1993	3	0.1	0.1	0.1				
		1993	2	0.2	0.2	0.2				
		1993	1	0.3	0.3	0.3				
		1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.4	0.4	3.8	3.8	3.8	
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
1887BR	SAMPLE	1993	4	0	0	0				
		1993	2	0.4	0.4	0.4				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.3	0.3				
		1991	4	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	8.5	8.5	8.5				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
1987	SAMPLE	1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.4	0.1	0.1	0.2	Day 2
		1992	1	0.4	0.4	1.4				No venting data
		1991	3	0.2	0.3	0.3	0.3	0.3	0.3	
		1994	2	0	0	0				
		1994	1	7.7	7.7	7.7				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
		1992	1	0.4	0.4	0.4				
		1991	4	0	0	0				
2087BR	WLM	1991	3	0.2	0.2	0.2				
		1991	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.3	0.3	0.3				
		1994	1	0.3	0.3	0.3				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
		1992	1	0.4	0.4	0.4				
2187	SAMPLE	1991	4	0	0	0				
		1991	3	0.2	0.2	0.2				
		1991	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.3	0.3	0.3				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
2287BR	SAMPLE	1993	2	0.4	0.4	0.4				
		1993	1	0.5	0.5	0.5				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	2	0.5	0.5	0.5				
		1994	4	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
2387BR	WLM	1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1992	3	0.5	0.5	0.5				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
		1991	4	0.4	0.4	0.2				
		1991	3	0.2	0.1	0.1				
		1991	2	0.1	0.1	0.1				
2487	SAMPLE	1991	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	2	0.4	0.4	0.4				
		1992	3	0	0	0				
		1992	2	0.2	0.2	0.2				
		1992	1	0.4	0.4	0.4				
		1991	4	0.4	0.4	0.2				
		1991	3	0.1	0.1	0.1				
		1994	2	0	0	0				
2587BR	SAMPLE	1994	1	0.6	0.6	0.6				
		1993	4	0	0	0				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1993	1	0.2	0.2	0.2				
		1992	3	0.1	0.1	0.1				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	2	0.3	0.3	0.3				
2687	WLM	1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
		1992	1	0.2	0.2	0.2				
		1991	4	0.1	0.1	0.1				
		1991	3	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	2	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
2787	WLM	1992	1	0.2	0.2	0.2				
		1991	4	0.1	0.1	0.1				
		1991	3	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	2	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.2				
		1992	2	0.6	0.6	0.9	0.4	0.4	0.4	
		1992	1	0.1	0.1	0.2	0.9	0.5	0.5	
		1991	4	0.2	0.2	0.2				
2887BR	SAMPLE	1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HN₂ READINGS

ROCKY FLATS GROUNDWATER SAMPLING RING READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
2987	SAMPLE	1993	4	4	4	4				No venting data
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1993	1	0.3	0.3	0.3				
		1992	3	0.2	0.2	0.2				
		1992	2	0.6	0.6	0.6				
		1994	2	0	0	0				
		1994	1	5	5	6				
		1993	3	0.3	0.3	0.3				
		1993	2	0.1	0.1	0.1				
3087BR	SAMPLE	1993	1	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.5	0.5	0.5				
		1992	1	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	2.5	2.5	2.5				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.1	0.1	0.1				
		1993	1	0.4	0.4	0.4				
3187BR	SAMPLE	1992	3	0.3	0.3	0.3				
		1992	2	0.5	0.5	0.5				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.2				
		1992	2	0.4	0.4	0.4				
3287	WLM	1994	2	0	0	0				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.3	0.3				
		1991	4	0.3	0.3	0.3				
		1991	3	0.1	0.1	0.1				
		1991	2	0.8	0.6	0.4				
		1991	1	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
3387	SAMPLE	1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0.2	0.2	0.2				
		1991	4	0.1	0.1	0.1				
		1991	3	0	0	0				
		1991	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
3487BR	SAMPLE	1992	1	0.2	0.2	0.2				
		1991	4	0.1	0.1	0.1				
		1991	3	0	0	0				
		1991	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
		1993	2	0.6	0.6	0.6				
		1993	1	0.2	0.2	0.2				
3587	WLM	1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY PLATS GROUNDWATER SAMPLING HING READINGS											
Well ID	Status	Year	Qtr	Survey Results						COMMENTS	
				At Opening			After Venting				
				BG	BZ	WH	BG	BZ	WH		
3687BR	SAMPLE	1994	1	11.2	11.2	11.2				No venting data	
		1992	3	0.2	0.2	0.1					
		1992	2	0.2	0.2	19.5					
		1992	1	0.2	0.2	0.2					
		1991	4	0.3	0.3	0.3					
		1991	3	0.1	0.1	0.1					
		1991	2	0.3	0.3	5.3				No venting data	
		1994	2	0	0	0					
		1994	1	2.5	2.5	2.5					
		1993	4	0.2	0.2	0.2					
		1993	3	0.4	0.4	0.4					
		1993	2	0.1	0.1	0.1					
3887	SAMPLE	1993	1	0.5	0.5	0.5				No venting data	
		1992	3	0.3	0.3	0.3					
		1992	2	0.2	0.2	2.4					
		1994	2	0	0	0					
		1994	1	0.6	0.6	0.6					
		1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.3					
		1992	1	0.9	0.9	0.6					
		1991	3	0.2	0.2	0.2					
		1991	2	0.4	0.4	0.4					
		1994	2	0	0	0					
		1994	1	0	0	0					
3987	SAMPLE	1993	4	0.2	0.2	0.2				No venting data	
		1993	3	0.3	0.3	0.3					
		1993	2	0.2	0.2	0.2					
		1993	1	0.6	0.6	0.6					
		1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.3					
		1992	1	0.3	0.2	0.1					
		1991	4	0.2	0.2	0.2					
		1994	2	0	0	0					
		1994	1	4.4	4.4	4.4					
		1993	3	0.1	0.1	0.1					
		1993	2	0.2	0.2	0.2					
4087	WLM	1993	1	0.6	0.6	0.6				No venting data	
		1992	3	0.3	0.3	0.3					
		1992	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1993	4	0.3	0.3	0.3					
		1993	3	0.2	0.2	0.2					
		1993	2	0.2	0.2	0.2					
		1992	3	0.2	0.2	0.2					
		1992	2	0.4	0.4	0.4					
		1992	1	0.3	0.2	0.1					
		1991	4	0.2	0.2	0.2					
		1994	2	0	0	0					
4187BR	SAMPLE	1994	1	4.4	4.4	4.4				No venting data	
		1993	3	0.1	0.1	0.1					
		1993	2	0.2	0.2	0.2					
		1992	3	0.2	0.2	0.2					
		1992	2	0.4	0.4	0.3					
		1992	1	0.3	0.2	0.1					
		1991	4	0.2	0.2	0.2					
		1994	2	0	0	0					
		1994	1	0.3	0.3	0.3					
		1993	3	0.2	0.2	0.2					
		1993	2	0.6	0.6	0.6					
		1993	1	0.6	0.6	0.6					
4287	SAMPLE	1992	3	0.2	0.2	0.2				No venting data	
		1992	2	0.4	0.4	0.4					
		1992	1	0.3	0.2	0.1					
		1991	4	0.2	0.2	0.2					
		1994	2	0	0	0					
		1994	1	0.3	0.3	0.3					
		1993	3	0.2	0.2	0.2					
		1993	2	0.6	0.6	0.6					
		1993	1	0.6	0.6	0.6					
		1992	3	0.2	0.2	0.2					
		1992	2	0.4	0.4	0.4					
		1992	1	0.3	0.2	0.2					
4387	WLM	1994	2	0	0	0					

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
4487	WLM	1993	2	0.2	0.2	0.2				No venting data
		1992	1	0.1	0.1	0.1				
		1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	250				
		1991	4	0.2	0.2	0.2				
		1991	3	0.3	0.3	0.3				
		1991	2	0.4	0.4	0.8	0.2	0.2	0.2	
		1994	2	0	0	0				
		1994	1	5.5	5.5	5.5				
		1992	3	0.2	0.2	0.2				
4587BR	SAMPLE	1992	2	4	4	17	0.6	0.6	0.6	
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1991	3	0.1	0.1	0.1				
		1991	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	2.8	2.8	2.8				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
4787	WLM	1992	3	0.3	0.3	0.3				
		1992	2	4	4	4.5	0.2	0.2	0.2	
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.5	0.5	0.5				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1992	1	0.2	0.2	0.2				
		1991	4	0	0	0				
		1991	3	0.1	0.1	0.1				
4887	WLM	1991	2	2.2	2.2	2.2				
		1994	2	0	0	0				
		1994	1	5.8	5.8	5.8				
		1993	1	0.9	0.9	0.9				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.3	0.3				
		1991	4	0.2	0.2	0.2				
		1991	3	0.1	0.1	0.1				
		1994	2	0	0	0				
4987	WLM	1994	1	5.2	5.2	5.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1991	3	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	5.2	5.2	5.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
5087	WLM	1992	1	0.2	0.2	0.2				No venting data
		1991	4	0.2	0.2	0.2				
		1991	3	0.1	0.2	0.2				
		1991	2	2.5	2.5	2.5				
		1994	2	0	0	0				
		1994	1	5.2	5.2	5.2				
		1992	3	0.3	0.3	0.3				
		1992	2	4	4	4.5				
		1992	1	0.1	0.1	0.1				
		1991	4	0.2	0.2	0.2				
		1991	3	0.1	0.2	0.2				No venting data
		1991	2	2.4	2.4	2.4				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
5187	SAMPLE	1994	2	0	0	0				
		1994	1	3.6	3.6	3.6				
		1993	1	0.7	0.7	1	0	0	0	
		1992	3	0.4	0.4	0.4				
		1992	2	0.3	0.3	0.3				
		1992	1	0.1	0.1	0.1				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
5287	SAMPLE	1994	2	0	0	0				
		1994	1	6.3	6.3	6.3				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1992	3	0.1	0.1	0.1				
		1992	2	0.2	0.2	0.2				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
5387	WLM	1994	2	0	0	0				
		1994	1	0.5	0.5	0.5				
		1992	3	0.4	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1992	1	0.2	0.2	0.2				
		1991	4	0.1	0.1	0.1				
		1991	3	0.1	0.1	0.1				
		1991	2	2	1.8	1.8				
5487	SAMPLE	1994	2	0	0	0				
		1994	1	1.2	1.2	1.2				
		1993	3	0.1	0.1	0.1				
		1993	2	0.6	0.6	17	0.4	0.4	10	2nd Day
		1991	2	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.2				
		1992	2	0.4	0.4	0.3				
		1992	1	0.1	0.1	0.1				
5587	SAMPLE	1994	2	0	0	0				
		1994	1	5.6	5.6	5.6				
		1993	3	0.02	0.02	1	0	0	0	
		1993	2	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.2				
		1992	2	0.3	0.3	0.3				
		1992	1	0.1	0.1	0.1				
		1991	4	0.1	0.1	0.1				
5687	SAMPLE	1994	2	0	0	0				
		1994	1	3.6	3.6	3.6				
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.4	0.2	0.2				
5887	SAMPLE	1994	2	0	0	0				
		1994	1	0.3	0.3	0.3				
		1993	4	0.3	0.3	0.4	0.5	0.5	0.5	1%LEL
		1993	3	0.2	0.2	0.2				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	0.2	0.2	0.2				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY PLATEAU GROUNDWATER SAMPLING HNT READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
6087	SAMPLE	1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0.5	0.5	0.5				
		1993	3	0.2	0.2	0.2				
		1993	1	0.5	0.5	0.5				
		1992	3	0.1	0.1	0.1				
		1992	2	1.4	1.4	3.8	0.2	0.2	0.2	
6187	SAMPLE	1992	1	0.3	0.2	0.1				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0	0.2	0.2				1% EXP
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	1	0.2	0.6	0.6				
		1992	3	0.1	0.1	0.1				
6287	WLM	1992	2	1.2	1.2	1.2				
		1994	2	0	0	0				
		1993	1	0.2	0.2	0.2				
		1992	3	0.1	0.1	0.3	0.3	0.3	0	
		1992	2	1.2	1.2	3.8	0.2	0.2	0.2	
		1992	1	0.2	0.2	0.1				
		1991	4	0.3	0.3	0.3				
		1991	3	0.4	0.4	0.4				
6487	SAMPLE	1991	2	1.5	1.5	1.4				
		1994	2	0	0	0				
		1994	1	2.6	2.6	2.6				
		1993	4	0.3	0.3	0.3				
		1993	3	0.3	0.3	0.3				
		1993	1	0.8	0.8	0.8				
		1992	3	0.1	0.1	0.1				
		1992	2	0.4	0.4	0				
6587	SAMPLE	1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	2.9	2.9	2.9				
		1993	4	0.1	0.1	0.1				
		1993	1	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
		1992	3	0.2	0.2	0.2				
		1992	2	0.6	0.6	0.6				
6687	SAMPLE	1992	1	0.3	0.2	0.2				
		1994	2	0	0	0				
		1994	1	2.6	2.6	2.6				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
6887	SAMPLE	1992	1	0.3	0.2	0.2				
		1994	2	0	0	0				
		1994	1	7.2	7.2	7.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.1	0.1	0.1				
		1992	3	0.1	0.1	0.1				
		1992	2	1.6	1.6	1.6				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS

ROCKY FLATS GROUNDWATER SAMPLING RING READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
7087	SAMPLE	1992	1	0.2	0.2	0.1				
		1991	4	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	4.5	4.5	4.5				
		1993	4	0.3	0.3	0.3				
		1993	3	0.2	0.2	0.2				
		1993	1	0.8	0.8	0.8				
		1992	3	0.2	0.2	0.2				
7187	SAMPLE	1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.2	0.2				
		1994	2	0	0	0				
		1994	1	6	6	6				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
7287	SAMPLE	1992	2	1.6	1.6	1.6				
		1992	1	0.3	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.3	0.3	0.3				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
		1993	1	0.2	0.2	0.2				
B400089 B400189	WLM	1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	2	0	0	0				
		1992	3	2.8	2.8	2.8				
		1992	3	1.3	1.3	1.3				
		1992	1	0	0	0				
		1991	4	0.2	0.2	0.2				
B400289	WLM	1991	3	0.3	0.3	0.3				
		1991	2	0.4	0.3	0.3				
		1991	1	0	0	0				
		1993	2	0.2	0.2	0.2				
		1993	3	0.4	0.4	0.4				
		1992	3	2.2	2.2	2.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0	0	0				
B400389	WLM	1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1991	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1993	2	0.4	0.4	0.4				
		1993	1	0.4	0.4	0.4				
		1992	3	3	3	3				
		1992	2	0.3	0.3	0.3				
B400489	WLM	1992	1	0	0	0				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0	0	0				
		1993	1	0.4	0.4	0.4				
		1992	3	3	3	3.6	0.2	0.2	0.2	

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
B200589	WLM	1992	2	0.5	0.5	0.5				
		1992	1	0	0	0				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.6	0.6	0.6				
		1993	1	0.4	0.4	0.4				
		1992	3	0.6	0.6	0.6				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
B200689	WLM	1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.4	0.4	0.4				
		1992	3	1.5	1.5	1.5				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1991	2	3	2	2				
B200789	WLM	1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	1.7	1.7	1.7				
		1992	2	0.4	0.4	0.4				
		1992	1	0.4	0.4	0.4				
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1991	2	2	2	2				
		1994	2	0	0	0				
B200889	WLM	1993	2	0.6	0.6	0.6				
		1992	3	1.7	1.7	1.7				
		1992	2	0.3	0.3	0.3				
		1992	1	0.2	0.2	0.2				
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.6	0.6	0.6				
		1992	3	1.7	1.7	1.7				
		1992	2	0.3	0.3	0.3				
B201089	WLM	1992	1	0.2	0.2	0.2				
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1991	2	2	2	2				
		1994	2	0	0	0				
		1993	1	0.4	0.4	0.4				
		1992	3	0.9	0.9	0.9				
		1992	2	0.5	0.5	0.5				
		1992	1	4.2	4.2	4.2				
		1991	4	0.2	0.2	0.2				
B201189	WLM	1991	3	0.2	0.2	0.2				
		1991	2	2	2	2				
		1994	2	0	0	0				
		1993	1	0.8	0.8	2.5	0.5	0.5	0.5	
		1992	3	2	2	2				
		1992	2	0.8	0.8	100	0.8	0.8	0.8	
		1992	1	0	0	0				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1991	2	2	2	2				
B201289	WLM	1994	2	0	0	0				
		1993	1	0.4	0.4	0.4				
		1992	3	2.8	2.8	2.8				

TABLE E-2
ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
B201589	WLM	1992	2	4.6	4.6	3.8				
		1992	1	0	0	0				
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1991	2	2	2	2				
		1994	2	0	0	0				
		1993	1	0.2	0.2	0.2				
		1992	3	2.4	2.4	2.4				
		1992	2	2	2	150	0.2	0.2	0.2	
		1992	1	0	0	0				
		1991	4	0	0	0				
		1991	3	0.2	0.2	0.2				
B401989	WLM	1991	2	2	2	2				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	3.2	3.2	3.2				
		1992	2	0.7	0.7	0.7				
		1992	1	1.2	1.2	1.2				
		1991	4	0.1	0.1	0.1				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.4	0.4	0.4				
B302089	WLM	1992	3	1.4	1.4	1.4				
		1992	2	0.7	0.7	0.5				
		1992	1	0	0	0				
		1991	4	0.1	0.1	0.1				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.4	0.4	0.4				
		1992	3	1.4	1.4	1.4				
		1992	2	0.7	0.7	0.5				
		1992	1	0	0	0				
		1991	4	0.1	0.1	0.1				
B402189	WLM	1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	1.8	1.8	1.8				
		1992	2	0.7	0.7	0.5				
		1992	1	0.4	0.4	0.4				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1992	1	0.3	0.3	0.3				
		1992	3	0.9	0.9	0.9				
B102289	WLM	1992	2	0.5	0.5	0.5				
		1991	4	0.4	0.4	0.3				
		1991	3	0.2	0.2	0.2				
		1991	2	2	2	2				
		1994	2	0	0	0				
		1993	1	0.4	0.4	0.4				
		1992	3	1	1	1				
		1992	2	0.5	0.5	0.5				
		1992	1	0.3	0.3	0.3				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1991	2	2	2	2				
B202489	WLM	1994	2	0	0	0				
		1993	1	0.3	0.3	0.3				
		1992	3	2.6	2.6	2.6				

TABLE E-2
ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS											
Well ID	Status	Year	Qtr	Survey Results						COMMENTS	
				At Opening			After Venting				
				BG	BZ	WH	BG	BZ	WH		
B202589	WLM	1992	2	6.5	6.2	5.8				No venting data	
		1992	1	0	0	0					
		1991	4	0.4	0.4	0.4					
		1991	3	0.2	0.2	0.2					
		1991	2	2	2	2					
		1994	2	0	0	0					
		1993	1	0.3	0.3	0.5	0.4	0.4	0.4		
		1992	3	2.4	2.4	2.4					
		1992	2	1.2	1.2	4	0.5	0.5	0.5		
		1992	1	0	0	0					
		1991	4	0.2	0.2	0.2					
		1991	3	0.2	0.2	0.3					
B402689	WLM	1991	2	0.2	0.2	0.2					
		1994	2	0	0	0					
		1993	2	0.2	0.2	0.2					
		1992	3	3.6	3.6	3.6					
		1992	2	0.2	0.2	0.2					
		1992	1	0.4	0.4	0.4					
		1991	4	0.2	0.2	0.2					
		1991	3	0.2	0.2	0.2					
		1991	2	0.2	0.2	0.2					
		1994	2	0	0	0					
		1993	1	0.2	0.2	0.2					
		1992	3	0.2	0.2	2.8	0.2	0.3	0.3		
B302789	WLM	1992	2	0.4	0.4	0.4				Day 2	
		1992	1	0	0	0					
		1991	4	0.15	0.15	0.15					
		1991	3	0.2	0.2	0.2					
		1991	2	0.2	0.2	0					
		1994	2	0	0	0					
		1993	1	0.4	0.4	0.4					
		1992	3	2.8	2.8	2.8					
		1992	2	0.3	0.3	0.3					
		1992	1	0	0	0					
		1991	4	0.1	0.1	0.1					
		1991	3	0.3	0.3	0.3					
B302889	WLM	1991	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1993	1	0.4	0.4	0.4					
		1992	3	2.8	2.8	2.8					
		1992	2	0.3	0.3	0.3					
		1992	1	0	0	0					
		1991	4	0.1	0.1	0.1					
		1991	3	0.3	0.3	0.3					
		1991	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1992	3	2.8	2.8	2.8					
		1992	2	0.7	0.7	0.6					
B302989	WLM	1992	1	0	0	0					
		1991	4	0.2	0.2	0.2					
		1991	3	0.3	0.3	0.3					
		1991	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1992	3	2.8	2.8	2.8					
		1992	2	0.7	0.7	0.6					
		1992	1	0	0	0					
		1991	4	0.2	0.2	0.2					
		1991	3	0.3	0.3	0.3					
		1991	2	0.3	0.3	0.3					
		1991	1	0.2	0.3	0.3					
B303089	WLM	1994	2	0	0	0				No venting data	
		1994	1	0.7	0.7	0.7					
		1993	4	0.4	0.4	0.3					
		1993	1	0.3	0.3	0.3					
		1992	3	0.1	0.1	0.1					
		1992	2	4.8	4.8	4.8					
		1992	1	0	0	0					
		1991	4	0.1	0.1	0.1					
		1994	2	0	0	0					
		1993	2	0.4	0.4	0.4					
		1993	1	0.3	0.3	0.3					
		1992	3	0.1	0.1	0.1					
B203189	WLM	1992	2	4.8	4.8	4.8					
		1992	1	0	0	0					
		1991	4	0.1	0.1	0.1					
		1994	2	0	0	0					
				1993	2	0.4	0.4	0.4			

TABLE E-2
ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
B203289	WLM	1993	1	0.3	0.3	0.3				
		1992	3	0.4	0.4	0.4				
		1992	2	0.7	0.7	0.7				
		1992	1	0.6	0.6	0.7	0.2	0.2	0.2	
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.4	0.4	0.4				
		1993	1	0.2	0.2	0.2				
		1992	3	1.6	1.6	1.6				
		1992	2	0.5	0.5	0.5				
		1992	1	0.2	0.2	0.2				
B203489	WLM	1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.7	0.2	0.2	0.2	
		1992	3	2	2	2				
		1992	2	0.4	0.4	0.4				
		1992	1	0.4	0.4	0.4				
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.6	0.6	0.6				
B203589	WLM	1993	1	0.2	0.2	0.2				
		1992	3	1.8	1.8	1.8				
		1992	2	1.7	1.7	150.2	0.2	0.2	0.2	
		1992	1	0.4	0.4	0.4				
		1991	4	0.3	0.3	0.3				
		1991	3	0.4	0.4	0.4				
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	1.6	1.6	1.6				
		1992	2	1.3	1.3	1.3				
		1992	1	0	0	0				
B203789	WLM	1991	4	0.3	0.3	0.3				
		1991	3	0.3	0.3	0.3				
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	1.6	1.6	1.6				
		1992	2	1.3	1.3	1.3				
		1992	1	0	0	0				
		1991	4	0.3	0.3	0.3				
		1991	3	0.3	0.3	0.3				
		1994	2	0	0	0				
		1993	2	0.6	0.6	0.6				
B203889	WLM	1993	1	0.2	0.2	0.2				
		1992	3	1.8	1.8	1.8				
		1992	2	1.7	1.7	2.1	0.3	0.3	0.3	
		1992	1	0.2	0.2	0.2				
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.6	0.6	0.6				
		1993	1	0.2	0.2	0.2				
		1992	3	1.8	1.8	1.8				
		1992	2	1.7	1.7	2.1	0.3	0.3	0.3	
		1992	1	0.2	0.2	0.2				
B203989	WLM	1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	1	0.4	0.4	0.4				
		1992	3	1.9	1.9	1.9				
		1992	2	0.15	1.5	2	0.3	0.3	0.3	
		1992	1	0	0	0				
		1991	4	0.2	0.4	0.4				No venting data
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	2	0	0	0				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
B204189	WLM	1994	1	6.8	6.8	6.8				
		1993	1	0.3	0.3	0.3				
		1992	3	0.5	0.5	0.5				
		1992	2	1	1	1.2	0.4	0.4	0.4	
		1992	1	4	4	4.8	0.3	0.3	0.3	
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.4				
		1994	2	0	0	0				
		1994	1	8	8	8				
		1993	1	0.5	0.5	0.5				
		1992	3	0.5	0.5	0.5				
		1992	2	1	1.2	0.8	0.4	0.4	0.4	
		1992	1	4	4	5	0.3	0.3	0.3	
		1991	4	0.3	0.3	0.3				
B304789	WLM	1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	2	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				
		1992	2	0.7	0.7	0.5				
		1992	1	0	0	0				
		1991	4	0.1	0.1	0.1				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.4	0.4	0.4				
		1992	3	2.8	2.8	2.8				
		1993	2	3.4	3.4	3.4				
B304889	WLM	1993	1	0	0	0				
		1991	4	0.1	0.1	0.1				
		1991	3	0.3	0.3	0.3				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.4	0.4	0.4				
		1992	3	2.8	2.8	2.8				
		1993	2	3.4	3.4	3.4				
		1993	1	0	0	0				
		1991	4	0.1	0.1	0.1				
		1991	3	0.3	0.3	0.3				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.3	0.3	0.3				
B304989	WLM	1992	3	2.8	2.8	2.8				
		1992	2	3.3	3.3	3.3				
		1992	1	0	0	0				
		1991	4	0.1	0.1	0.1				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.3	0.3	0.3				
		1992	3	2.8	2.8	2.8				
		1992	2	3.3	3.3	3.3				
		1992	1	0	0	0				
		1991	4	0.1	0.1	0.1				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
B405189	WLM	1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
		1992	3	3.4	3.4	3.4				
		1992	2	0.8	0.8	0.5				
		1992	1	0	0	0				
		1991	4	0.1	0.1	0.1				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
		1992	3	3.4	3.4	3.4				
		1992	2	0.8	0.8	0.5				
		1992	1	0	0	0				
		1991	4	0.1	0.1	0.1				
B405289	WLM	1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
		1992	3	3.4	3.4	3.6	0.2	0.2	0.2	
		1992	2	0.7	0.7	0.6				
		1992	1	0.4	0.4	0.4				
		1991	4	0.1	0.1	0.1				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
		1992	3	3.4	3.4	3.6	0.2	0.2	0.2	
		1992	2	0.7	0.7	0.6				
1992	1	0.4	0.4	0.4						
1991	4	0.1	0.1	0.1						
1991	3	0.2	0.2	0.2						

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS											
Well ID	Status	Year	Qtr	Survey Results						COMMENTS	
				At Opening			After Venting				
				BG	BZ	WH	BG	BZ	WH		
B305389	WLM	1994	2	0	0	0					
		1993	2	0.3	0.3	0.3					
		1993	1	0	0	0					
		1992	3	2.4	2.4	2.4					
		1992	2	0.5	0.5	0.5					
		1992	1	0	0	0					
		1991	4	0.1	0.1	0.1					
		1991	3	0.2	0.2	0.2					
B405489	WLM	1994	2	0	0	0					
		1993	2	0.3	0.3	0.3					
		1993	1	0.2	0.2	0.2					
		1992	3	2.6	3	4.2	0.2	0.2	0.2		
		1992	2	0.3	0.3	0.3					
		1992	1	0	0	0					
		1991	4	0.2	0.2	0.2					
		1991	3	0.1	0.1	0.1					
B205589	WLM	1994	2	0	0	0					
		1994	1	0.6	0.6	0.6					
		1992	3	2.1	2.1	2.1					
		1992	2	0.3	0.3	0.3					
		1992	1	0	0	0					
		1991	4	0	0	0					
		1991	1	0.2	0.2	0.2					
		1991	2	2	2	2					
B405689	WLM	1994	2	0	0	0					
		1993	2	0.3	0.3	0.3					
		1993	1	0.8	0.8	0.8					
		1992	3	2.2	2.2	2.8	0.2	0.1	0.1		
		1992	2	1.2	1.2	0.8					
		1992	1	0	0	0					
		1991	4	0.2	0.1	0.1					
		1991	3	0.2	0.2	0.2					
B405789	WLM	1994	2	0	0	0					
		1993	2	0.3	0.3	0.3					
		1992	3	3	3	3					
		1992	2	0.5	0.5	0.5					
		1992	1	0	0	0					
		1991	4	0.2	0.2	0.2					
		1991	3	0.2	0.2	0.2					
		1991	2	0.3	0.2	0.2					
B405889	WLM	1994	2	0	0	0					
		1993	2	0.2	0.2	0.2					
		1993	1	0.2	0.2	0.2					
		1992	3	1.8	1.8	1.8					
		1992	2	0.7	0.7	0.4					
		1992	1	0.4	0.4	0.4					
		1991	4	0.15	0.15	0.15					
		1991	3	0.2	0.2	0.2					
B405989	WLM	1994	2	0	0	0					
		1993	1	0.2	0.2	0.2					
		1992	3	1.8	1.8	1.8					
		1992	2	0.7	0.7	0.5					
		1992	1	0.4	0.4	0.4					
		1991	4	0.1	0.2	0.1	0.3	0.2	0.2		
		1991	3	0.2	0.2	0.2					
		1991	3	0.2	0.2	0.2					

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS											
Well ID	Status	Year	Qtr	Survey Results						COMMENTS	
				At Opening			After Venting				
				BG	BZ	WH	BG	BZ	WH		
B106089	SAMPLE	1991	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1994	1	2.1	2.1	2.1					
		1993	4	0.3	0.3	0.3					
		1993	3	0	0	0					
		1993	2	0.3	0.3	0.3					
		1993	1	0.2	0.2	0.3					No venting data
		1992	3	0.1	0.1	0.1					
B206289	SAMPLE	1992	2	0.4	0.4	0.3					
		1994	2	0	0	0					
		1994	1	4.5	4.5	5					no venting info
		1993	4	0.2	0.2	0.2					
		1993	3	0.3	0.3	0.3					
		1993	2	0.3	0.3	0.3					
		1993	1	0.2	0.4	0					
		1992	3	0.1	0.1	0.1					
B206489	SAMPLE	1992	2	0.4	0.4	0.4					
		1994	2	0	0	0					
		1994	1	2.3	2.3	2.3					
		1993	4	0.2	0.2	0.2					
		1993	3	0.3	0.3	0.3					
		1993	2	0.4	0.4	0.4					
		1993	1	0.3	0.2	0.2					
		1992	3	0.2	0.2	0.2					
B206589	SAMPLE	1992	2	0.4	0.4	0.4					
		1994	2	0	0	0					
		1994	1	5.5	5.5	5.3					
		1993	3	0	0	0					
		1993	2	0.2	0.2	0.2					
		1993	1	0.3	0.3	0.4					
		1992	3	0.1	0.1	0.1					
		1992	2	0.4	0.4	0.4					
B206689	SAMPLE	1992	1	0.3	0.2	0.2					
		1994	2	0	0	0					
		1994	1	1.1	1.1	1.1					
		1993	4	0.2	0.2	0.2					
		1993	3	0.2	0.2	0.2					
		1993	2	0.2	0.2	0.2					
		1992	3	0.2	0.2	0.2					
		1992	2	0.5	0.5	0.5					
B206789	SAMPLE	1992	1	0.3	0.2	0.1					
		1994	2	0	0	0					
		1994	1	0.02	0.02	0.02					
		1993	4	0.2	0.2	0.2					
		1993	3	0.1	0.1	0.1					
		1993	2	0.2	0.2	0.2					
		1993	1	0.8	0.8	12					no venting info
		1992	3	0.2	0.2	0.2					
B206889	SAMPLE	1992	2	1.6	1.6	1.6					
		1994	2	0	0	0					
		1994	1	0.2	0.2	0.2					
		1993	4	0.3	0.3	0.3					
		1993	3	0.2	0.2	0.2					
		1993	1	0.5	0.5	0.5					
		1992	3	0.2	0.2	0.2					
		1992	2	0.2	0.2	0.2					

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
B206989	SAMPLE	1992	2	1.6	1.6	100.4	0.3	0.3	0.3	No venting data
		1992	1	0.3	0.3	0.2				
		1994	2	0	0	0				
		1994	1	0.5	0.5	0.5				
		1993	4	0.2	0.2	0.2				
		1993	3	0.1	0.1	0.1				
		1993	1	0.7	0.7	0.7				
B207089	SAMPLE	1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.1	0.1				
		1994	2	0	0	0				
		1994	1	7	7	7				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
B207289	WLM	1993	2	0.3	0.3	0.3				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.3				
		1992	1	0.3	0.3	0.2				
		1994	2	0	0	0				
		1994	1	0.09	0.09	0.09				
		1993	1	0.4	0.4	0.4				
P207389	SAMPLE	1992	3	0.4	0.4	0.4				
		1992	2	1.6	1.6	6.3				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.3	0.3	0.3				
P207589	SAMPLE	1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1991	4	0.2	0.2	0.3	0.2	0.2	0.2	
		1994	2	0	0	0				
P207689	SAMPLE	1994	1	0	0	0				
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.1	0.1	0.1				
		1993	1	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
P207789	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.5	0.5	0.5				
		1993	3	0.3	0.3	0.3				
		1993	2	0.5	0.5	0.5				
		1993	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
P207789	SAMPLE	1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	6.5	6.5	6.5				
		1993	4	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
1993	2	0.3	0.3	0.3						

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
P207889	SAMPLE	1993	1	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	7.5	7.5	7.5				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.3				
P207989	SAMPLE	1992	2	0.3	0.3	0.3				
		1992	1	0.7	0.7	0.7				
		1994	2	0	0	0				
		1994	1	7.2	7.2	7.2				
		1993	4	0.6	0.6	0.6				
		1993	3	0.3	0.3	0.3				
		1993	2	0.1	0.1	0.1				
		1993	1	1	1	1				
		1992	3	0.3	0.3	0.3				
B208089	SAMPLE	1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0.7	0.7	0.7				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
		1992	1	0.2	0.2	0.2				
B208189	SAMPLE	1994	2	0	0	0				
		1994	1	6.4	6.4	6.4				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.3				
		1992	1	0.2	0.1	0.1				
		1994	2	0	0	0				
B208289	SAMPLE	1994	1	4	4	4				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.2	0.2				
		1994	2	0	0	0				
		1994	1	4	4	4				
B208389	WLM	1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.1	0.1	0.1				
		1992	3	0.4	0.4	0.4				
B208489	WLM	1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.2	0.2				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING H₂O READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
B208589	WLM	1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	0.2	0.2	0.1				
		1991	4	0.2	0.2	0.2				
		1991	3	0.4	0.4	0.3				
B208689	SAMPLE	1991	2	0.2	0.2	0.2				
		1991	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.3	0.3	0.3				
		1993	3	0.2	0.2	0.2				
		1993	2	0.3	0.3	0.3				
		1993	1	0.5	0.5	0.5				
B208789	WLM	1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.2				
		1992	1	0.3	0.1	0.1				
P208889	SAMPLE	1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
P208989	SAMPLE	1992	2	0.3	0.3	0.3				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	2.3	2.3	2.3				
		1993	4	0.5	0.5	0.5				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
P209089	SAMPLE	1992	2	0.3	0.3	0.3				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.1	0.1	0.1				
		1993	1	0.4	0.4	0.4				
P209189	WLM	1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
P209289	SAMPLE	1992	1	0.4	0.3	0.2				
		1991	4	0.4	0.4	0.4				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0		0				
		1993	4	0.3	0.3	0.3				
		1993	3	0.1	0.1	0.1				
		1993	2	0.6	1	200	0.4	0.4	0.4	
		1993	1	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.3				
P209389	SAMPLE	1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.5	0.5	0.5				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
P209489	SAMPLE	1994	1	0	0	0				
		1993	4	0.6	0.6	0.6				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1993	1	0.5	0.5	0.5				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
P209589	SAMPLE	1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.3	0.3	0.3				
		1991	4	0.4	0.4	0.8	0.2	0.2	0.2	
		1994	2	0	0	0				
		1994	1	6.5	6.5	6.5				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
P209689	SAMPLE	1993	1	1	1	1				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.6	0.6	0.6				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.6	0.6	0.6				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	2				
		1992	3	0.3	0.3	0.3				
P209789	SAMPLE	1992	2	0.3	0.3	0.3				
		1992	1	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.6	0.6	0.6				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.6	0.6	0.6				
P209889	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.5	0.5	0.5				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	2				No venting data
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				

No venting data

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY PLATS GROUNDWATER SAMPLING HIND READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
P209989	WLM	1993	2	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
		1992	1	0	0	0				
		1994	2	0	0	0				
		1993	2	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.3				
P210089	SAMPLE	1992	1	0.2	0.2	0.2				
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	6.4	6.4	6.4				
		1993	4	0.2	0.2	0				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
P210189	SAMPLE	1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.3				
		1992	1	0.2	0.2	0.1				
		1994	2	0	0	0				
		1994	1	0.04	0.04	0.04				
		1993	4	0.5	0.5	0.04				
		1993	3	0.3	0.3	0.3				
		1993	2	0.6	0.6	4	0.5	0.5	1	
B210389	WLM	1993	1	0.4	0.4	1				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.5				No venting data
		1994	2	0	0	0				
		1993	2	0.6	0.6	0.6				
		1992	3	0.1	0.1	0.1				
		1992	2	0.4	0.4	0.4				
		1992	1	0.3	0.2	0				
B210489	SAMPLE	1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1991	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	4.5	4.5	4.5				
		1993	4	0.1	0.1	0.1				
		1993	3	0.2	0.2	0.2				
		1993	2	1	1	1				
B410589	SAMPLE	1993	1	0.5	0.5	0.5				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.3				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1992	3	0.4	0.4	0.4				
		1992	2	0.7	0.7	1	0.3	0.3	0.3	
		1992	1	0.3	0.3	0.3				
B410689	SAMPLE	1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1991	2	0.4	0.4	0.4				
		1991	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1992	3	0.4	0.4	0.4				
		1992	2	0.8	0.8	0.7				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
B410789	SAMPLE	1992	1	0.3	0.3	0.3				
		1991	4	0.3	0.3	0.3				
		1991	3	0.2	0.2	0.3	0.2	0.2	0.2	
		1991	2	0.3	0.4	0.4	0.4	0.4	0.4	
		1991	1	0	0	0				
		1994	2	0	0	0				
		1992	3	0.3	0.3	0.3				
		1992	2	0.8	0.8	0.5				
		1992	1	0.2	0.2	0.2				
		1991	4	0.3	0.3	0.3				
B110889	SAMPLE	1991	3	0.2	0.2	0.2				
		1991	2	0.4	0.3	0.3				
		1991	1	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	5	5	5				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.5	0.5	0.5				
		1992	3	0.4	0.4	0.4				
		1992	2	0.8	0.8	0.5				
B110989	SAMPLE	1992	1	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	3.8	3.8	3.8				
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.5	0.5	0.5				
		1992	3	0.8	0.8	0.8				
		1992	2	0.7	0.7	0.4				
		1994	2	0	0	0				
B111189	SAMPLE	1994	1	4.8	4.8	4.8				
		1993	3	0.1	0.1	0.1				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	0.4	0.4	0.4				
		1992	2	0.6	0.6	0.4				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1992	3	0.5	0.5	0.5				
		1992	2	0.8	0.8	0.8				
B411289	SAMPLE	1992	1	0.3	0.3	0.3				
		1994	2	0	0	0				
		1992	3	0.5	0.5	0.5				
		1992	2	0.8	0.8	0.8				
		1992	1	0.3	0.3	0.3				
		1991	4	0.2	0.2	0.2				
		1991	3	0.1	0.1	0.1				
		1991	2	0.3	0.3	0.3				
		1992	1	0.3	0.3	0.2				
		1994	2	0	0	0				
B411389	SAMPLE	1994	1	1.9	1.9	1.9				
		1993	4	0	0	0				
		1993	3	0.2	0.2	0.2				
		1993	4	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.8	0.8	0.4				
		1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	1.6	1.6	1.6				
		1994	1	1.6	1.6	1.6				
P313489	SAMPLE	1992	1	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	1.6	1.6	1.6				
		1994	1	1.6	1.6	1.6				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING H₂O READINGS

ROCKY FLATS GROUNDWATER SAMPLING H ₂ O READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
P313589	SAMPLE	1993	4	11.5	11.5	11.5				
		1994	2	0	0	0				
		1994	1	1.6	1.6	1.6				
		1993	4	14	14	14				
P213689	SAMPLE	1994	2	0	0	0				
		1994	1	2.5	2.5	2.5				
		1993	4	0	0	0				
		1992	3	0.4	0.4	0.4				
B213789	SAMPLE	1992	2	0.3	0.3	0.3				no venting info
		1994	2	0	0	0				
		1994	1	5.5	5.6	5.8				
		1993	4	0.4	0.4	0.4				
P213889	WLM	1992	3	0	0	0				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
P213989	WLM	1992	3	0.4	0.4	0.4				
		1992	2	5	5	5				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
P314089	SAMPLE	1994	2	0	0	0				
		1994	1	1.6	1.6	1.6				
		1993	4	0.9	0.9	0.9				
		1992	3	0.4	0.4	0.4				
P414189	SAMPLE	1994	2	0	0	0				
		1994	1	3.2	3.2	3.2				
		1993	4	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
P314289	SAMPLE	1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	3.2	3.2	3.2				
		1993	4	0.6	0.6	0.6				
P114389	SAMPLE	1992	3	0.2	0.2	0.2				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1993	4	0.2	0.2	0.2				
P114489	SAMPLE	1994	1	1.5	1.5	1.5				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
P114589	SAMPLE	1994	1	1	1	1				
		1993	4	0.2	0.2	0.2				
		1992	3	0.5	0.5	0.5				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
P114689	SAMPLE	1994	1	0.8	0.8	0.8				
		1993	4	0.2	0.2	0.2				
		1992	3	0.2	0.2	0.2				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	2	2	2				
		1993	4	0.9	0.9	0.9				
		1993	2	0.6	0.6	0.6				
P114789	SAMPLE	1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	0.5				
		1994	2	0	0	0				
		1994	1	0.35	0.35	0.35				
		1993	4	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
P114889	SAMPLE	1994	1	1.6	1.6	1.6				
		1993	4	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	1.8	1.8	1.8				
		1993	4	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
P114989	SAMPLE	1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	1.8	1.8	1.8				
		1993	4	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	1.9	1.9	1.9				
P115089	SAMPLE	1993	4	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	1.9	1.9	1.9				
		1993	4	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.3	0.3	0.3				
B315289	WLM	1994	2	0	0	0.1				No venting data
P115489	SAMPLE	1994	2	0	0	0				
		1994	1	2.5	2.5	2.5				
		1993	4	2.3	2.3	2.3				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	2.1	0	0	0	
		1994	1	3	3	3				
		1993	4	0.8	0.8	0.8				
P115589	SAMPLE	1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	2.1	0	0	0	
		1994	1	3	3	3				
		1993	4	0.8	0.8	0.8				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.5				No venting data
		1994	2	0	0	0				
P115689	SAMPLE	1994	1	2	2	4.9	0.7	0.7	0.7	
		1993	4	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	0.5				
		1994	2	0	0	0				
		1994	1	1.4	1.4	1.4				
		1993	4	0.9	0.9	0.9				
		1992	3	0.4	0.4	0.4				
P215789	SAMPLE	1992	2	0.5	0.5	0.5				
		1994	2	0	0	0				
		1994	1	1.4	1.4	1.4				
		1993	4	0.9	0.9	0.9				
		1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	0.5				
		1994	2	0	0	0				
		1994	1	1	1	1				
P415889	SAMPLE	1993	4	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				

TABLE E-2
ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING H ₂ O READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
P415989	SAMPLE	1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	1.7	1.7	1.7				
		1993	4	0.2	0.2	0.2				
		1992	3	0.2	0.2	0.2				
P416089	SAMPLE	1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	2.5	2.5	2.5				
		1993	4	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
P416189	SAMPLE	1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	3.2	3.2	3.2				
		1993	4	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
P416289	SAMPLE	1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	4	0.2	0.2	0.2				
		1992	3	0.2	0.2	0.2				
P416389	SAMPLE	1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
P416489	SAMPLE	1992	3	0.2	0.2	0.2				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	4	0.2	0.2	0.2				
P416589	SAMPLE	1993	3	0.3	0.3	0.3				
		1992	3	0.2	0.2	0.2				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0.26	0.26	0.26				
P416689	SAMPLE	1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1992	3	0.2	0.2	0.2				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
P416789	SAMPLE	1994	1	0.32	0.32	0.32				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
P416889	SAMPLE	1994	2	0	0	0				
		1994	1	0.32	0.32	0.32				
		1993	4	0.6	0.6	0.6				
		1993	3	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0.33	0.33	0.35	2.8	2.8	2.8	
		1993	4	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
P416989	SAMPLE	1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
B317189	WLM	1993	4	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	6.1	6.1	6.1				
		1992	3	0.1	0.1	0.1				
		1992	2	0.4	0.4	0.4				
B217289	SAMPLE	1992	1	0	0	0				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	3	3	3				
		1993	3	0.4	0.4	0.4				
		1992	3	0.2	0.2	0.2				
		1992	2	0.8	0.8	0.8				
		1992	1	0.4	0.4	0.4				
B217489	WLM	1994	2	0	0	0				
		1994	1	8.2	8.2	8.2				
		1993	2	0.1	0.1	0.1				
		1993	1	0.5	0.5	0.5				
B217589	WLM	1994	2	0	0	0				
		1993	3	0.1	0.1	0.1				
B217689	WLM	1994	2	0	0	0				
		1993	2	0.1	0.1	0.1				
		1993	1	0.4	0.4	0.4				
B217789	WLM	1994	2	0	0	0				
		1994	1	2	2	2				
		1993	1	0.4	0.4	0.4				
		1994	2	0	0	0				
P317989	WLM	1994	2	0	0	0				
		1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.2	0.2				
		1992	1	0.2	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1991	3	0.2	0.2	0.2				
		1991	2	0.6	0.6	0.6				
		1991	1	0.4	0.3	0.3				
P218089	WLM	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	3	0.6	0.6	0.6				
		1993	1	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.3	0.2	0.2				
		1991	4	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	3.5	3.5	3.5				
P218289	SAMPLE	1993	4	0.2	0.2	0.2				
		1994	2	0	0	0				
P218389	SAMPLE	1994	1	0	0	0				
		1993	4	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1992	1	0.3	0.2	0.2				
B218789	WLM	1994	2	0	0	0				
		1992	3	0.1	0.1	0.1				
		1992	2	0.3	0.3	0.3				
		1992	1	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HING READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
P219189	SAMPLE	1992	1	0.3	0.3	0.3				
		1991	4	0.2	0.2	0.2				
		1991	3	0.1	0.1	0.1				
		1991	2	0.4	0.4	2.2	0.4	0.4	0.6	
		1994	2	0	0	0				
		1994	1	4.3	4.3	4.3				
		1993	4	0.2	0.2	0.2				
		1993	2	0.6	0.6	0.6				
P119389	SAMPLE	1992	3	0.4	0.4	0.4				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1992	3	0.4	0.4	0.4				
P219489	SAMPLE	1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
P219589	SAMPLE	1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
P419689	SAMPLE	1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	4.4	4.4	4.4				
		1993	4	0.1	0.1	0.1				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
P320089	SAMPLE	1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0.4	0.4	0.4				
		1993	3	0.1	0.1	0.1				
		1993	2	0.2	0.2	0.2				
		1994	2	0	0	0				
B220189	WLM	1994	2	0	0	0				
B220489	WLM	1994	2	0	0	0				
0190	SAMPLE	1994	2	0	0	0				
		1994	1	6	6	6				
		1993	4	0.2	0.2	0.2				
		1993	3	0.1	0.1	0.1				
		1993	1	0.3	0.3	0.3				
0290	SAMPLE	1994	2	0	0	0				
		1994	1	6	6	6				
		1993	4	1	1	1				
		1993	1	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
		1992	3	0.4	0.4	0.4				
0390	SAMPLE	1992	2	5	3.8	3.8				
		1994	2	0	0	0				
		1994	1	2	2	2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1993	1	0.3	0.3	0.3				
		1992	3	0.2	0.2	0.2				
		1992	2	4.8	4.8	4.8				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
0590	WLM	1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.3				
		1992	2	5.2	5.2	5.8				
0690	WLM	1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
0790	WLM	1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
0990	WLM	1994	2	0	0	0				
		1993	2	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
1490	SAMPLE	1994	2	0	0	0				
		1994	1	0.02	0.02	0.02				
		1993	4	1	1	1				
		1993	3	0.2	0.2	0.2				
		1993	2	0.1	0.1	0.1				
		1993	1	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	1.2	1.2	1.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0	0.02	0.02			No venting data	
00191	SAMPLE	1993	2	0.4	0.4	0.4				
		1993	1	0.5	0.5	1				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
00291	SAMPLE	1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
00391	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	3	0.1	0.1	0.1				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	1			No venting data	
		1993	4	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.4			No venting data	
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
00491	SAMPLE	1993	4	4	4	4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.8	0.8	0.8				
		1992	3	0.6	0.6	0.6				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1992	3	0.6	0.6	0.6				
00691	SAMPLE	1992	2	4.8	4.8	5.4				No venting data
		1992	3	0.6	0.6	0.6				
		1993	4	0.2	0.2	0.2				
		1994	1	6	6	6				
		1994	2	0	0	0				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
00791	WLM	1994	2	0	0	0				
		1992	3	0.4	0.4	0.4				
		1992	2	5.2	5.2	6	0.2	0.2	0.2	
00891	WLM	1994	2	0	0	0				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
00991	WLM	1994	2	0	0	0				
		1992	3	0.4	0.4	0.4				
		1992	2	4	4	9				No venting data
01291	SAMPLE	1992	1	8	8	20				No venting data
		1994	2	0	0	0				
		1994	1	5.8	5.8	5.8				
		1993	2	0.2	0.2	0.2				
		1993	4	0.4	0.4	0.4				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.6				No venting data
01391	SAMPLE	1992	1	7.2	7.2	9				No venting data
		1994	2	0	0	0				
		1994	1	2.8	2.8	2.8				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.6	0.6	0.6				
		1993	1	0.4	0.4	0.4				
01491	SAMPLE	1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.2	0.3				No venting data
		1994	2	0	0	0				
		1994	1	3.5	3.5	3.5				
		1993	4	3	3	3				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
01791	SAMPLE	1993	1	0.5	0.5	0.5				
		1992	3	0.4	0.4	0.4				
		1992	2	0.9	0.9	0.3				
		1994	2	0	0	0				
		1994	1	2.5	2.5	2.5				
		1993	4	0	0	0				
		1993	3	0.1	0.1	0.1				
01891	SAMPLE	1993	2	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.9	0.9	0.8				
		1992	1	1.8	1.8	1.8				
		1994	2	0	0	0				
		1994	1	3	3	3				
		1993	4	0	0	0				
01991	SAMPLE	1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.9	0.9	0.9				
		1994	2	0	0	0				
		1994	1	1	1	1				
01991	SAMPLE	1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1993	1	0.6	0.6	0.6				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
02091	SAMPLE	1992	2	4.8	4.8	5				No venting data
		1992	3	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	4.2	4.2	8.4				No venting data
		1993	4	2.6	2.6	9.2				No venting data
		1993	3	0.2	0.2	25				Rapid dissipation
		1993	1	0.4	0.4	0.4				
		1992	3	0.2	0.2	0.2				
02191	WLM	1992	3	0.2	0.2	0.2				
		1992	3	0.2	0.2	0.2				
		1992	1	1.6	1.6	2.4				No venting data
		1994	2	0	0	0				
		1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.2	6.5				No venting data
		1992	1	1.5	1.8	5				No venting data
		1991	4	4.1	4.1	4.1				
02291	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.4				No venting data
		1993	4	0.2	0.2	22	0.2	0.2	20	
		1993	3	0.2	0.2	0.2				
		1993	1	0.5	0.5	2	0.5	0.5	0.5	1 min. venting
		1992	3	0.3	0.3	0.3				
		1992	2	0.5	0.5	2	1	1	1	
		1992	1	2	2	2				
02391	WLM	1994	2	0	0	0				
		1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.2	0.2				
		1992	1	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	2.2	2.2	2.2				
		1993	3	0.2	0.2	0.2				
02491	SAMPLE	1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	0.5				
		1992	1	1.5	1.5	14	8.2	8.2	8.2	
		1991	4	4.2	4.4	5.2				
		1994	2	0	0	0				
		1994	1	3.5	3.5	3.5				
		1993	4	2	2	2				
		1993	3	0.1	0.1	0.1				
02591	SAMPLE	1993	2	0.4	0.4	0.4				
		1993	1	0.7	0.7	0.7				
		1992	3	0.1	0.1	0.1				
		1992	2	4.8	4.8	6.6	0.4	0.4	0.4	
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.9	0.9	0.9				
		1993	3	0.3	0.3	0.3				
02691	SAMPLE	1993	2	0.2	0.2	0.2				
		1993	1	0.8	0.8	0.8				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.5	1.5	0.5	0.5	0.5	
		1994	2	0	0	0				
		1992	3	0.1	0.1	0.1				
		1992	2	0.2	0.2	0.2				
		1992	1	2.8	2.8	6				No venting data

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
02891	WLM	1994	2	0	0	0				
		1994	1	11	11	11.5				No venting data
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1992	3	0.2	0.2	0.2				
		1992	2	0.2	0.2	0.2				
02991	SAMPLE	1992	1	8.8	8.8	11.8				No venting data
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.6	0.6	0.6				
		1992	3	0.2	0.2	0.2				
03091	SAMPLE	1992	2	0.2	0.2	0.2				
		1992	1	3.8	4.8	4.8	1.6	1.6	1.6	
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	2.2	2.2	3				No venting data
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
03191	WLM	1993	1	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	11.5	11.5	11.5				
		1993	4	0.3	0.3	0.3				
		1992	3	1.5	1.5	1.5				
03391	SAMPLE	1992	2	0.2	0.2	0.2				
		1992	1	8.6	8.6	10.2	0	0	0.2	
		1991	4	1.2	1.2	1.2				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.3	0.3	0.3				
		1993	3	0	0	0				
03591	SAMPLE	1993	2	0.4	0.4	0.4				
		1993	1	0.7	0.7	0.7				
		1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.6	0.6	0.6				
03691	SAMPLE	1993	3	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1992	3	0.1	0.1	0.1				
		1992	2	0.2	0.2	0.2				
		1992	1	7.2	7.2	8.4	0.2	0.2	0.2	Day 4
		1994	2	0	0	0				
		1994	1	0.8	0.8	3.5				No venting data
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1993	1	0.7	0.7	6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.2	0.2				
		1992	1	0.2	0.2	0.2				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING H ₂ O READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
03791	SAMPLE	1994	2	0	0	0				
		1994	1	3.3	3.3	3.3				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
		1993	1	0.7	0.7	0.7				
		1992	3	0.2	0.2	0.2				
		1992	2	0.2	0.2	0.2				
03891	WLM	1992	1	6	6	6				
		1994	2	0	0	0				
		1992	3	0.1	0.1	0.1				
		1992	2	0.2	0.2	0.2				
		1992	1	2	2	2				
		1991	4	1.2	1.2	1.2				
		1994	2	0	0	0				
03991	SAMPLE	1994	1	2.9	2.9	2.9				
		1993	3	0.2	0.2	0.2				
		1993	4	0.6	0.6	0.6				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.1	0.1	0.1				
		1992	2	3.3	3.3	3.3				
04091	SAMPLE	1994	2	0	0	0				
		1994	1	2.8	2.8	2.8				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1993	1	0.6	0.6	0.6				
		1992	3	0.6	0.6	0.6				
04191	SAMPLE	1992	2	4	4	5	4.8	5	5.4	Day 2
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	4	1.1	1.1	1.1				
		1993	2	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	0.2	0.2	0.2				
04291	SAMPLE	1992	2	0.4	0.4	0.4				
		1992	1	2	2	2				
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	4	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.4	0.4	0.4	0.4	
04491	SAMPLE	1992	2	0.4	0.4	0.4				
		1992	1	4.8	4.8	6.2				No venting data
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	4	0.2	0.2	0.2				
		1993	2	0.03	0.03	0.03				
		1992	3	0.9	0.9	0.4				
04591	SAMPLE	1992	2	0.4	0.4	0.6	0.2	0.2	0.2	
		1992	1	7.8	7.8	8				No venting data
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING H ₂ O READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
04691	SAMPLE	1993	2	0.4	0.4	0.4				
		1993	1	0.3	0.3	0.3				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	1.1	1.1	1.1				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
04891	WLM	1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.3	0.3	0.3				
		1992	1	2	2	2.2	1	1	1	
04991	SAMPLE	1991	4	0	0	0				
		1994	2	0	0	0				
		1994	1	0.1	0.1	0.1				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
05091	SAMPLE	1992	2	0.4	0.4	0.4				
		1992	1	4.6	4.6	5	2	2	2	
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	0.5				
		1992	1	0.3	0.9	0.5	0.5	0.5	0.5	
05191	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	0.5				
		1992	1	0.3	0.9	0.5	0.5	0.5	0.5	
		1994	2	0	0	0				
05291	ND	1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
05391	SAMPLE	1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	0.5				
		1994	2	0	0	0.1	0	0	0	
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	2.8				No venting data
05691	SAMPLE	1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.5	0.5	0.5				
		1992	3	0.1	0.1	0.1				
		1992	2	0.2	0.2	0.2				
		1992	1	6.4	6.4	6.8	0.4	0.4	0.4	Day 2
		1994	2	0	0	0				
		1994	1	2.8	2.8	2.8				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
05991 06091	WLM SAMPLE	1993	4	0.3	0.3	0.3				
		1993	3	0.3	0.3	0.4				No venting data
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.8				
		1992	3	0.2	0.2	0.2				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	2	0	0	0				
		1994	1	2.8	2.8	2.8				
		1993	4	0.2	0.2	0.2				
		1993	3	0.1	0.1	0.1				
		1993	2	0.4	0.4	0.4				
		1993	1	0.6	0.6	0.6				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1992	1	1.8	1.8	1.8				
06191	SAMPLE	1994	2	0	0	0.6				No venting data
		1994	1	0.3	0.3	0.3				
		1993	4	2	2	2				
		1993	3	0.1	0.1	0.1				
		1993	2	0.8	0.8	0.8				
		1993	1	0.7	0.7	0.7				
		1992	3	0.1	0.1	0.1				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.6	0.6	0.6				
		1993	3	0.1	0.1	0.1				
		1993	2	0.4	0.4	0.4				
		1992	3	1.1	1.1	1.1				
		1992	2	0.5	0.5	0.5				
		1992	1	1.6	1.6	1.6				
06391	WLM	1994	2	0	0	0				
		1994	1	0.5	0.5	0.5				
		1993	4	0.4	0.4	0.4				
		1993	1	0.6	0.6	0.6				
		1992	3	1	1	1				
		1992	2	0.4	0.4	0.4				
		1992	1	1.6	1.6	1.6				
		1991	4	0.6	0.6	0.6				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.6	0.3	0.3	0.3	
		1992	3	0.2	0.2	0.2				
		1992	2	11.4	11.4	17.2	0.4	0.4	0.4	
06491	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.6	0.3	0.3	0.3	
		1992	3	0.2	0.2	0.2				
		1992	2	11.4	11.4	17.2	0.4	0.4	0.4	
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0.4	0.4	0.4				
		1993	3	0.4	0.4	0.4				
		1993	2	0.2	0.2	0.2				
		1993	1	0.3	0.3	0.3				
		1992	3	0.4	0.4	0.3				

TABLE E-2
ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING H ₂ O READINGS												
Well ID	Status	Year	Qtr	Survey Results						COMMENTS		
				At Opening			After Venting					
				BG	BZ	WH	BG	BZ	WH			
06691	SAMPLE	1992	2	0.2	0.4	0.4						
		1994	2	0	0	0						
		1994	1	1	1	1						
		1993	4	0.2	0.2	0.2						
		1993	3	0.3	0.3	0.3						
		1993	2	0.1	0.1	0.1						
		1993	1	0.3	0.3	0.3						
06791	SAMPLE	1992	3	0.4	0.4	0.9	0.3	0.3	0.3			
		1992	2	4.8	4.8	15	0.6	0.6	0.6	2 weeks later		
		1994	2	0	0	0						
		1994	1	1.8	1.8	1.8						
		1993	4	0.3	0.3	0.3						
		1993	3	0.3	0.3	0.3						
		1993	2	0.4	0.4	0.4						
		1993	1	0.5	0.5	0.8	0.3	0.3	0.3			
		1992	3	0.3	0.3	0.5	0.3	0.3	0.3			
		1992	2	5	5	10	3.6	3.6	4.4			
06891	SAMPLE	1994	2	0	0	0						
		1994	1	2.8	2.8	2.8						
		1993	4	0.2	0.2	0.2						
		1993	3	0.2	0.2	0.2						
		1993	2	0.2	0.2	0.2						
		1993	1	0.3	0.3	0.3						
		1992	3	0.4	0.4	0.2						
		1992	2	0.4	0.4	0.4						
		1994	2	0	0	0						
		1994	1	4.5	4.5	4.5						
06991	SAMPLE	1993	4	0.2	0.2	0.2						
		1993	3	0.2	0.2	0.2						
		1993	2	0.2	0.2	0.2						
		1993	1	0.5	0.5	0.5						
		1992	3	0.3	0.3	0.3						
		1992	2	0.2	0.2	1	1	1	1	Next month		
		1994	2	0	0	0						
		1994	1	1.5	1.5	1.8	2.2	2.2	2.8			
		1993	4	0.6	0.6	0.6						
		1993	3	0.3	0.3	0.3						
07191	SAMPLE	1993	2	0.1	0.1	0.1						
		1993	1	0.6	0.6	0.6						
		1992	3	0.4	0.4	1.2						
		1992	2	0.8	0.4	1				No venting data		
		1994	2	1.5	1.5	5.3				No venting data		
		1993	4	0.4	0.4	0.4				No venting data		
		1993	3	0.2	0.2	4	0.1	0.1	0.1			
		1993	2	0.1	0.1	0.1						
		1993	1	0.5	0.5	0.5						
		1992	3	0.3	0.3	0.4						
07291	SAMPLE	1992	2	0.2	0.4	0.4						
		1994	2	0	0	0						
		1994	1	2.5	2.5	11	1	1	5	Day 2		
		1993	4	0.6	0.6	1.6	0.4	0.4	1	Day 2		
		1993	3	0.2	0.2	0.9	0.2	0.2	50	Day 2		
		1993	2	4	4	4.9	0.4	0.4	3.5	Day 2		
		1993	1	0.6	0.6	10	0.6	0.6	10	Day 2		
		1992	3	0.3	0.3	0.8	0.5	0.5	0.5			
		07391	SAMPLE	1992	3	0.3	0.3	0.8	0.5	0.5	0.5	
				1992	3	0.3	0.3	0.8	0.5	0.5	0.5	

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS	
				At Opening			After Venting				
				BG	BZ	WH	BG	BZ	WH		
07891	SAMPLE	1992	2	4	4	35	0.3	0.3	0.4	Next month	
		1994	2	0	0	0					
		1994	1	0.2	0.2	0.2					
		1993	4	0.2	0.2	0.2					
		1993	3	0.3	0.3	0.3					
		1993	1	0.5	0.5	0.5					
		1992	3	0.1	0.1	0.1					
07991	SAMPLE	1992	2	0.2	0.2	1.6	0.5	0.5	0.5		
		1994	2	0	0	0					
		1994	1	0.2	0.2	0.2					
		1993	4	0.4	0.4	0.4					
		1993	3	0.3	0.3	0.3					
		1993	2	0.2	0.2	0.2					
		1993	1	0.2	0.2	0.2					
08091	SAMPLE	1992	3	0.4	0.4	0.4					
		1992	2	0.4	0.4	1.8					No venting data
		1994	2	0	0	0					
		1994	1	0.8	0.8	0.8					
		1993	4	0.3	0.3	0.3					
		1993	3	1.4	1.4	1.4					
		1993	1	1.4	1.4	1.4					
08291	WLM	1992	3	0.3	0.3	0.3					
		1992	2	0.4	0.4	0.6	0.6	0.6	0.6		Next month
		1992	1	5.5	5.5	6.4					No venting data
		1994	2	0	0	0					
		1992	3	0.4	0.5	0.4	0.3	0.3	0.3		
		1992	2	0.4	0.4	0.6	0.2	0.2	0.2		Next month
		1992	1	2.2	2.2	2.2					
08391	WLM	1994	2	0	0	0					
		1993	2	0.03	0.03	0.003					
		1993	1	0.8	0.8	0.8					
		1993	3	0.3	0.3	0.3					
		1992	3	0.7	0.7	0.6					
		1992	2	0.4	0.4	0.4					
		1992	1	2	2	2					
08491	WLM	1994	2	0	0	0					
		1992	3	0.3	0.3	0.3					
		1992	2	0.4	0.4	1	0.2	0.2	0.2		Next month
		1992	1	3.8	4.2	5.2					
08591	WLM	1994	2	0	0	0					
		1993	2	0.2	0.2	0.2					
		1993	1	1.4	1.4	1.4					
		1992	3	0.2	0.2	0.2					
		1992	2	0.2	0.4	0.6	0.4	0.4	0.4		
		1992	1	2	2	3					
		1994	2	0	0	0					
08891	SAMPLE	1994	1	1	3	4				Vented quickly No venting data	
		1993	4	0.4	0.4	30					
		1993	3	0.3	0.3	50	0.2	0.2	50		Day 2
		1993	2	0.2	0.2	0.2					
		1993	1	0.5	0.5	12	0.4	0.4	12		Day 2
		1992	3	0.4	0.4	43					No venting data
		1992	2	0.6	0.6	0.8					No venting data
09091	SAMPLE	1994	2	0	0	0					
		1994	1	1	1	1					

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
09691	SAMPLE	1993	4	0.2	0.2	0.2				
		1993	3	0.4	0.4	0.4				
		1993	2	0.1	0.1	0.1				
		1993	1	0.5	0.5	0.5				
		1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	1.2	1.2	1.2				
		1993	4	0.4	0.4	0.4				
		1993	3	0.4	0.4	0.4				
		1993	2	0.3	0.3	0.3				
		1993	1	0.6	0.6	1.4				No venting data
10991	SAMPLE	1992	3	0.2	0.2	0.2				
		1992	2	3.8	3.8	5.2	0.7	0.7	0.7	
		1994	2	0	0	0				
		1994	1	2	2	2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	0.5				
		1994	2	0	0	0				
		1992	3	0.2	0.2	0.2				
11291	WLM	1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1992	3	0.2	0.2	0.2				
		1992	2	0.5	0.5	0.5				
		1994	2	0	0	0				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	11.6	11.6	11.6				
		1993	1	0.3	0.3	0.3				
		1992	3	0.4	0.4	0.4				
		1992	2	0.6	0.6	0.6				
11691	SAMPLE	1994	2	0	0	0				
		1994	1	2.8	2.8	2.8				
		1993	4	0.2	0.2	0.2				
		1993	3	0.1	0.1	0.1				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1992	3	0.5	0.5	0.5				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	9	9	9				
		1993	4	0.6	0.6	0.6				
		1993	3	0.1	0.1	0.1				
11791	SAMPLE	1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	1				No venting data
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.4	0.2	0.2	0.2	Next month
		1994	2	0	0	0.9				No venting data
		1994	1	2.8	2.8	2.8				
		1993	4	3.2	3.2	3.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1993	1	0.7	0.7	0.7				
		1992	3	0.4	0.4	0.4				
		1992	2	0.2	0.2	0.2				
12091	SAMPLE	1994	2	0	0	0				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
12191	SAMPLE	1994	1	0.2	0.2	0.2				
		1993	4	0.6	0.6	0.6				
		1993	3	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.5	0.5	1.5	0.3	0.3	0.3	Next month
		1994	2	0	0	0				
		1994	1	1.2	1.2	1.2				
		1993	4	2.1	5.2	2.1				No venting data
		1993	3	0.2	0.2	0.2				
12291	SAMPLE	1993	2	0.3	7	0.3	0.8	0.8	2	
		1993	1	0.2	0.2	0.2				
		1992	3	0.1	0.1	0.1				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0.7	0.7	0.7				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
12391	SAMPLE	1992	3	0.5	0.5	0.5				
		1992	2	0.8	0.8	0.6				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.1	0.1	0.1				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.9	0.9	0.9				
		1992	2	0.3	0.3	0.3				
12491	SAMPLE	1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	4	3	3	3				
		1993	3	0	0	0				
		1993	2	0.2	0.2	0.2				
		1993	1	0.5	0.5	0.5				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	2.5	2.5	2.5				
12691	SAMPLE	1993	4	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1992	3	0.1	0.1	0.1				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	2.5	2.5	2.5				
		1993	4	0.4	0.4	0.4				
		1993	3	0.3	0.3	0.3				
12891	WLM	1993	2	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1992	3	0.1	0.1	0.1				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1992	3	0.3	0.3	0.4	0.2	0.2	0.2	
		1992	2	0.4	0.4	1	0.4	0.4	0.4	
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
12991	SAMPLE	1993	3	0.3	0.3	0.3				
		1993	2	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1993	1	0.6	0.6	0.6				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS		
				At Opening			After Venting					
				BG	BZ	WH	BG	BZ	WH			
13091	SAMPLE	1992	3	0.3	0.3	0.3						
		1992	2	0.4	0.4	1.2	0.3	0.3	0.4	Next month		
		1994	2	0	0	0						
		1994	1	1.4	1.4	1.4						
		1993	4	0.2	0.2	0.2						
		1993	3	0.3	0.3	0.3						
		1993	2	0.3	0.3	0.3						
13191	SAMPLE	1993	1	0.3	0.3	0.3						
		1992	3	0.5	0.4	0.3						
		1992	2	4.2	4.2	9	4.2	4.2	5			
		1994	2	0	0	0						
		1994	1	2.5	2.5	3	1.2	1.2	2			
		1993	4	0.4	0.4	0.4						
		1993	3	0.3	0.3	0.3						
13291	SAMPLE	1993	2	0.4	0.4	0.4						
		1994	4	0.3	0.3	0.3						
		1992	3	0.3	0.3	0.7	0.6	0.6	0.6			
		1992	2	0.2	0.4	0.4	0.4	0.4	0.4	Next month		
		1994	2	0	0	0						
		1994	1	0.8	0.8	0.8						
		1993	4	0.4	0.4	0.4						
13391	SAMPLE	1993	3	0.4	0.4	0.4						
		1992	3	0.3	0.3	1	0.4	0.4	0.4			
		1992	2	0.4	0.6	2				No venting data		
		1994	2	0	0	0						
		1994	1	2.9	2.9	2.9						
		1993	3	0.1	0.1	0.1						
		1993	4	3	3	3						
13491	SAMPLE	1993	2	0.4	0.4	0.4						
		1993	1	0.6	0.6	0.6						
		1992	3	0.1	0.1	0.1						
		1992	2	4.8	4.8	4.8						
		1994	2	0	0	0						
		1994	1	0.2	0.2	0.2						
		1993	4	3.1	3.1	3.1						
13591	WLM	1993	3	0.3	0.3	0.3						
		1993	2	0.4	0.4	0.4						
		1993	1	0.4	0.4	0.4						
		1992	3	0.1	0.1	0.1						
		1992	2	0.6	0.6	1.2	4.4	4.4	4.4	Next month		
		1994	2	0	0	0						
		1992	3	0.2	0.2	0.5				No venting data		
20591	WLM	1992	2	3.4	2.4	3.8	0.4	0.4	0.4	Next month		
		1994	2	0	0	0						
		20691	WLM	1994	2	0	0	0				
		20791	WLM	1994	2	0	0	0				
		30991	SAMPLE	1994	2	0	0	0				
				1994	1	1	1	1				
				1993	4	0.3	0.3	0.3				
1993	3			0.2	0.2	0.2						
1993	2			0.3	0.3	0.3						
31491	WLM	1993	1	0.8	0.8	0.8						
		1992	3	0.4	0.4	0.4						
		1992	2	4.5	4.5	5	0.4	0.4	0.4	Next month		
		1994	2	0	0	0						
		1994	2	0	0	0						

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS

ROCKY FLATS GROUNDWATER SAMPLING HINI READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
31791	SAMPLE	1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	1	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	1.8	1.8	1.8				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
31891	SAMPLE	1993	1	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	1.7	1.7	1.7				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	1	0.7	0.7	0.7				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
32591	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.3	0.3	0.3				
		1993	3	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0	0	0				
33491	SAMPLE	1993	3	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0	0	0				
		1993	3	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.4				
33691	WLM	1992	2	4.5	4.5	6	0.4	0.4	0.4	
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.4	0.4	0.4				
		1993	2	0.6	0.6	0.6				
33891	SAMPLE	1993	1	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				
		1992	2	0.9	0.9	0.9				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.4	0.4	0.4				
		1993	2	0.6	0.6	0.6				
		1993	1	0.6	0.6	0.6				
		1992	3	0.3	0.3	0.3				
34591	WLM	1992	2	0.9	0.9	0.9				
		1994	2	0	0	0				
		1992	3	0.5	0.5	0.5				
		1992	2	4	4	4				
		1994	2	0	0	0				
		1994	1	3.2	3.2	3.2				
		1993	4	0	0	0				
		1993	3	0.4	0.4	0.4				
		1993	2	0.3	0.3	0.3				
		1993	1	0.3	0.3	0.3				
34791	SAMPLE	1993	4	0	0	0				
		1993	3	0.4	0.4	0.4				
		1993	2	0.3	0.3	0.3				
		1993	1	0.3	0.3	0.3				
		1993	4	0	0	0				
		1993	3	0.4	0.4	0.4				
		1993	2	0.3	0.3	0.3				
		1993	1	0.3	0.3	0.3				
		1993	4	0	0	0				
		1993	3	0.4	0.4	0.4				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING RINQ READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
35391	SAMPLE	1992	3	0.3	0.3	0.3				
		1992	2	4.6	4.6	4.6				
		1994	2	0	0	0				
		1994	1	0.5	0.5	0.5				
		1993	4	0.4	0.4	0.4				
		1993	2	0.6	0.6	0.6				
35691	SAMPLE	1992	3	0.4	0.4	0.2				
		1992	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0.3	0.3	0.3				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
35991	WLM	1993	2	0.3	0.3	0.3				
		1993	1	0.6	0.6	0.6				
		1992	3	0.4	0.4	0.3				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1992	3	0.2	0.2	0.2				
36191	SAMPLE	1992	2	0.9	0.9	0.9				
		1994	2	0	0	0				
		1994	1	4.6	4.6	6	1.2	1.2	1.2	
		1993	4	0.1	0.1	0.1				
		1993	3	0.3	0.3	0.3				
		1993	1	0.4	0.4	0.4				
36391	SAMPLE	1992	3	0.3	0.3	0.3				
		1992	2	5.5	5.5	6	0.2	0.2	0.2	
		1994	2	0	0	0				
		1994	1	4	4	4				
		1993	4	0	0	0				
		1993	3	0.1	0.1	0.1				
36691	SAMPLE	1993	1	0.8	0.8	0.8				
		1992	3	0.3	0.3	0.3				
		1992	2	5.5	5.5	6	1	1	1	Next month
		1994	2	0	0	0				
		1994	1	0.8	0.8	0.8				
		1993	4	0.2	0.2	0.2				
36991	WLM	1993	3	0.1	0.1	0.1				
		1993	2	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
37191	SAMPLE	1994	2	0	0	0				
		1994	1	2.6	2.6	2.6				
		1993	4	0	0	0				
		1993	3	0.3	0.3	0.3				
		1993	2	0.4	0.4	0.4				
		1992	3	0.4	0.4	0.4				
37591	SAMPLE	1992	2	4.5	4.5	7.5	0.4	0.4	0.4	
		1994	2	0	0	0				
		1994	1	5.6	5.6	5.6				
		1993	3	0.1	0.1	0.1				
		1993	2	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
1992	2	0.4	0.4	0.4						

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS											
Well ID	Status	Year	Qtr	Survey Results						COMMENTS	
				At Opening			After Venting				
				BG	BZ	WH	BG	BZ	WH		
37691	SAMPLE	1994	2	0	0	0					
		1994	1	1	1	1					
		1993	4	0.2	0.2	0.2					
		1993	3	0.2	0.2	0.2					
		1993	2	0.2	0.2	0.2					
		1992	3	0.4	0.4	0.4					
37791	SAMPLE	1992	2	5.4	5.4	5.4					
		1994	2	0	0	0					
		1994	1	3.5	3.5	3.5					
		1993	4	0.2	0.2	0.2					
		1993	3	0.3	0.3	0.3					
		1993	1	0.3	0.3	0.3					
37891	SAMPLE	1992	3	0.4	0.4	0.4					
		1992	2	0.3	0.3	0.3					
		1994	2	0	0	0					
		1994	1	1	1	1					
		1993	3	1	1	1					
		1993	2	0.2	0.2	0.2					
37991	SAMPLE	1993	1	0.8	0.8	0.8					
		1992	3	0.4	0.4	0.4					
		1992	2	4.5	4.5	1.9					
		1994	2	0	0	0					
		1994	1	1	1	1					
		1993	4	0.9	0.9	0.9					
38191	SAMPLE	1993	3	0.2	0.2	0.2					
		1993	2	0.2	0.2	0.2					
		1993	1	0.4	0.4	0.4					
		1992	3	0.4	0.4	0.4					
		1992	2	0.4	0.4	0.4					
		1992	2	0.4	0.4	0.4					
38291	SAMPLE	1994	2	0	0	0					
		1992	3	0.4	0.4	0.9	0.3	0.3	0.3		
		1992	2	4.5	4.5	9	0.4	0.4	3		
38591	SAMPLE	1994	2	0	0	0					
		1994	1	1.9	1.9	1.9					
		1993	4	0	0	0					
		1993	3	0.4	0.4	0.4					
		1993	1	0.9	0.8	0.8					
		1992	3	0.3	0.3	0.3					
38891	SAMPLE	1992	2	0.4	0.4	0.4					
		1994	2	0	0	0					
		1994	1	2.8	2.8	2.8					
		1992	3	0.6	0.6	0.6					
38991	SAMPLE	1992	2	0.2	0.2	0.2					
		1994	2	0	0	0					
		1994	1	2.8	2.8	2.8					
		1993	2	0.1	0.1	0.1					
39191	SAMPLE	1992	3	0.6	0.6	0.6					
		1992	2	4.5	4.5	5.5	0.2	0.2	0.2		
		1994	2	0	0	0					
		1994	1	0.2	0.2	0.2					
		1993	4	0.3	0.3	0.3					
		1993	3	0.2	0.2	0.2					

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING H₂O READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
39291	SAMPLE	1993	1	0.4	0.4	0.4				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1993	2	0.1	0.1	0.1				
39691	SAMPLE	1992	3	0.6	0.6	0.6				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	9	9	9				
		1993	4	0.2	0.2	0.2				
40491	WLM	1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1992	3	0.4	0.4	0.4				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
40791	WLM	1992	2	0.4	0.4	0.6	0.4	0.4	0.4	
		1992	3	0.2	0.2	0.4	7.9	7.9	7.9	
		1994	2	0	0	0				
		1992	3	0.1	0.1	0.1				
		1992	2	0.3	0.3	0.3				
40991	WLM	1994	2	0	0	0				
		1992	3	0.5	0.5	0.5				
		1992	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	2	2	2				
41091	SAMPLE	1993	4	0.3	0.3	0.3				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0	0	0				
		1992	3	0.4	0.4	0.4				
41491	SAMPLE	1992	2	0.4	0.4	1	0.5	0.5	0.5	
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
41591	SAMPLE	1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.2	0.2	0.2				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
41691	SAMPLE	1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
		1992	3	0.3	0.3	0.3				
		1992	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.6	0.6	0.6				
		1992	3	0.2	0.2	0.2				
		1992	2	0.4	0.4	0.4				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
45391	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
03092	ND	1994	2	0	0	0				
03192	ND	1994	2	0	0	0				
10092	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1992	3	0.6	0.6	0.6				
10192	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1992	3	0.6	0.6	0.6				
10292	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1992	3	0.6	0.6	0.6				
10392	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
		1992	3	0.6	0.6	0.8	0.4	0.4	0.4	
10492	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.3	0.3	0.3				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.3	0.3	0.3				
		1992	3	0.6	0.6	0.6				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.6	0.6	0.6				
10592	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.6	0.6	0.6				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1993	1	0.3	0.3	0.3				
		1992	3	0.6	0.6	0.8	0.4	0.4	0.4	
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.6	0.6	0.6				
10692	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.6	0.6	0.6				
		1993	3	0.2	0.2	0.2				
		1993	2	0.1	0.1	0.1				
		1993	1	0.3	0.3	0.3				
		1992	3	0.4	0.6	0.6	0.4	0.4	0.4	
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.6	0.6	0.6				
10792	SAMPLE	1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.1	0.1	0.1				
		1993	1	0.3	0.3	0.3				
		1992	3	0.4	0.6	0.6	0.4	0.4	0.4	
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				
10892	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.2	0.2	0.2				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
10992	SAMPLE	1992	3	0.6	0.6	0.8	0.4	0.4	0.4	No venting data
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.5	0.5	0.5				
		1993	3	0.2	0.2	0.2				
		1993	2	0.1	0.1	0.1				
		1993	1	0.3	0.3	0.3				
11092	SAMPLE	1992	3	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.6	0.6	0.6				
		1993	3	0.4	0.4	0.4				
		1993	2	0.2	0.2	0.2				
		1993	1	0.2	0.2	0.2				
43392	SAMPLE	1992	3	0.6	0.6	0.4				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0	0	0				
		1993	3	0.3	0.3	0.3				
43492	SAMPLE	1993	1	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	4	0.2	0.2	0.2				
46192	SAMPLE	1993	3	0.2	0.2	0.2				
		1993	1	1.2	1.2	1.2				
		1994	2	0	0	0				
		1994	1	0.1	0.1	0.1				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1992	1	0.2	0.2	0.3				
46292	SAMPLE	1992	3	2.9	2.9	2.9				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	0.6	0.6	0.6				
		1993	3	0.2	0.2	0.2				
		1993	2	4.8	4.8	4.8				
		1993	1	0.2	0.2	0.2				
		1992	3	3.4	3.4	3.4				
46392	SAMPLE	1994	2	0	0	0				
		1994	1	0.1	0.1	0.1				
		1993	4	0.3	0.3	0.3				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1992	3	2.5	2.5	2.5				
46492	SAMPLE	1994	2	0	0	0				
		1994	1	7.2	7.2	7.2				
		1993	4	0.2	0.2	0.2				
		1993	3	0.4	0.4	0.4				
		1993	2	4.8	4.8	4.8				
		1992	3	2.9	2.9	2.9				
46692	SAMPLE	1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	3	0.4	0.4	0.4				
		1993	2	0.4	0.4	0.4				
		1993	1	0.5	0.5	0.5				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING H ₂ O READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
46792	SAMPLE	1992	3	1.2	1.2	1.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	1	1	1				
		1993	2	0.4	0.4	0.4				
46892	SAMPLE	1992	3	1.2	1.2	1.2				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	4	3.5	3.5	3.5				
		1993	2	0.4	0.4	0.4				
49192	SAMPLE	1992	3	2.8	2.8	2.8				
		1992	2	2	2	2				
		1994	2							
		1994	1	0.7	0.7	0.7				
		1993	4	2.5	2.5	2.5				
49292	SAMPLE	1993	3	0.2	0.2	0.2				
		1993	2	0.3	0.3	0.3				
		1994	1	0.7	0.7	0.7				
		1993	4	0	0	0				
		1993	3	0.2	0.2	0.2				
50092	SAMPLE	1993	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	0.3	0.3	0.3				
		1993	4	0.1	0.1	0.1				
		1993	3	0.1	0.1	0.1				
50192	ND	1994	2	0	0	0				
50292	ND	1993	2	0.3	0.3	0.3				
		1994	2	0	0	0				
75092	SAMPLE	1993	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	5	5	5				
		1993	4	0.1	0.1	0.1				
		1993	3	0.2	0.2	0.2				
75292	SAMPLE	1993	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	2.5	2.5	2.5				
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
75892	ND	1993	2	0.4	0.4	0.4				
75992	SAMPLE	1994	2	0	0	0				
		1994	2	0	0	0				
		1994	1	0.2	0.2	0.2				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
76192	ND	1993	2	0.2	0.2	0.2				
76292	SAMPLE	1994	2	0	0	0				
		1994	2	0	0	0				
		1994	1	4.3	4.3	4.3				
		1993	4	1	1	1				
		1993	3	0.3	0.3	0.3				
76792	ND	1993	2	0.2	0.2	0.2				
		1993	1	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	2	0	0	0				
		1994	2	0	0	0				
77192	ND	1994	2	0	0	0				
77392	ND	1994	2	0	0	0				

TABLE E-2
ROCKY FLATS GROUNDWATER SAMPLING H₂O READINGS

ROCKY PLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
77492	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.5	0.5	0.5				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
00193	ND	1994	2	0	0	0				
00293	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
00393	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
00493	ND	1994	2	0	0	0				
		1994	1	0	0	0				
05093	SAMPLE	1994	2	0	0	0				
		1993	4	0.5	0.5	0.5				
		1993	3	0.3	0.3	0.3				
		1993	2	0.1	0.1	0.1				
		1994	1	0	0	0				
05193	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	4	0.5	0.5	0.5				
		1993	3	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				
05293	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
05393	ND	1994	2	0	0	0				
22093	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	3	0.2	0.2	0.2				
22193	SAMPLE	1994	2	0	0	0				
		1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1994	1	1	1	1				
22293	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	2	0.2	0.2	0.2				
		1993	3	0.4	0.4	0.4				
22393	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
22593	SAMPLE	1994	2	0	0	0				
		1993	3	0.2	0.2	0.2				
		1994	1	1	1	1				
23193	SAMPLE	1994	2	0	0	0				
		1994	1	1	1	1				
		1993	0.2	0.2	0.2					
23293	ND	1994	2	0	0	0				
40193	WLM	1994	2	0	0	1.1	0	0	0	
40293	WLM	1994	2	0	0	0				
		1994	1	10.8	10.8	10.8				
40393	WLM	1994	2	0	0	0				
40593	WLM	1994	2	0	0	0				
41193	WLM	1994	2	0	0	0				
41693	WLM	1994	2	0	0	0				
41993	WLM	1994	2	0	0	0				
42393	WLM	1994	2	0	0	0				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

ROCKY FLATS GROUNDWATER SAMPLING HNU READINGS										
Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
42993	WLM	1994	2	0	0	0				
43293	WLM	1994	2	0	0	0				
43593	WLM	1994	2	0	0	0				
43893	WLM	1994	2	0	0	0				
43993	WLM	1994	2	0	0	0				
44893	WLM	1994	2	0	0	0				
44993	WLM	1994	2	0	0	0				
45093	WLM	1994	2	0	0	0				
		1994	1	11	11	11				
45293	WLM	1994	2	0	0	0				
45393	WLM	1994	2	0	0	0				
		1994	1	4.8	4.8	4.8				
45593	WLM	1994	2	0	0	0				
45693	WLM	1994	2	0	0	0				
45793	WLM	1994	2	0	0	0				
45893	WLM	1994	2	0	0	0				
45993	WLM	1994	2	0	0	0				
46093	WLM	1994	2	0	0	0				
		1994	1	0.6	0.6	0.6				
46193	WLM	1994	2	0	0	0				
46293	WLM	1994	2	0	0	0				
46393	WLM	1994	2	0	0	2.1	0	0	0	
46493	WLM	1994	2	0	0	0				
		1994	1	11	11	11				
51193	SAMPLE	1994	2	0	0	0				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1992	1	0.4	0.4	0.4				
		1994	2	4.2	4.2	4.2				
58793	SAMPLE	1994	2	0	0	0				
		1994	1	2	2	2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
59093	ND	1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
59393	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
59493	SAMPLE	1994	2							
		1994	1	1	1	1				
		1993	3	0.1	0.1	0.1				
		1993	2	0.1	0.1	0.1				
59593	SAMPLE	1994	2	0	0	0				
		1994	1	1	1	1				
		1993	3	0.2	0.2	8	0.1	0.1	0.1	Dissipated rapidly
		1993	2	0.2	0.2	500				Vented before purging
		1994	1	1	1	1				
		1993	3	0.1	0.1	0.1				
59793	ND	1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
61293	ND	1994	2	0	0	0				
		1993	2	0.2	0.2	0.2				
63093	SAMPLE	1994	2	0	0	0				
		1994	1	0	0	0				
		1993	2	0.2	0.2	0.2				
70093	SAMPLE	1994	2	0	0	0				

TABLE E-2

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
70193	SAMPLE	1994	1	5.1	5.1	5.1				
		1993	3	0.1	0.1	0.1				
		1993	2	0.1	0.1	0.1				
		1994	2	0	0	0				
		1994	1	5	5	5				
70293	SAMPLE	1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	2.8	2.8	2.8				
		1993	4	1.1	1.1	1.1				
70393	SAMPLE	1993	3	0.2	0.2	0.2				
		1993	2	0.4	0.4	0.4				
		1994	2	0	0	0				
		1994	1	2.6	2.6	2.6				
		1993	3	0.2	0.2	0.2				
70493	SAMPLE	1993	2	0.6	0.6	0.6				
		1993	2	0.4	0.4	0.75				
		1994	2	0	0	0				
		1994	1	2.8	2.8	2.8				
		1993	2	0.6	0.6	6				
70593	SAMPLE	1993	4	1.1	1.1	3.4				
		1993	3	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	2	2.5	2.5	2.5				
		1993	4	1.1	1.1	1.1				
70693	SAMPLE	1993	3	0.2	0.2	0.2				
		1993	2	0.8	0.8	0.8				
		1994	2	0	0	0				
		1994	1	5.1	5.1	5.1				
		1993	3	0.2	0.2	0.2				
70893	SAMPLE	1993	2	0.3	0.3	0.3				
		1994	2	0	0	0				
		1994	1	1	1	1				
		1993	3	0.2	0.2	0.2				
		1993	2	0.6	0.6	0.6				
71193	SAMPLE	1994	2	0	0	0				
		1994	1	2.6	2.6	2.4				
		1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
71493	SAMPLE	1994	2	0	0	0				
		1994	1	2.2	2.2	2.2				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1994	2	0	0	0				
71693	SAMPLE	1994	1	2.4	2.4	2.8	0	0	0	
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	2.6	2.6	0.26				
71893	SAMPLE	1993	4	0.4	0.4	0.4				
		1993	3	0.2	0.2	0.2				
		1993	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	2.6	2.6	0.26				
72093	SAMPLE	1993	2	0.2	0.2	0.2				
		1994	2	0	0	0				
		1994	1	0	0	0				

ROCKY FLATS GROUNDWATER SAMPLING HNu READINGS

Well ID	Status	Year	Qtr	Survey Results						COMMENTS
				At Opening			After Venting			
				BG	BZ	WH	BG	BZ	WH	
72293	SAMPLE	1993	3	0.2	0.2	4				No venting data
		1993	2	0.6	0.6	0.8				
		1994	2	0	0	0				
		1994	1	2.4	2.4	6	0	0	0	
72393	SAMPLE	1993	3	0.2	0.2	1.2				
		1993	2	0.2	0.2	1.8				
		1994	2	0	0	0				
		1994	1	1.2	1.2	1.2				
72493	ND	1993	4	5.8	5.8	5.8				
		1993	2	0.6	0.6	0.6				
		1994	2	0	0	0				
		1994	1	0.08	0.09	0.08				
		1993	4	0.3	0.3	0.3				
		1993	2	0.2	0.2	0.2				

TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
0586	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.6	0.6	0.6	0	0				0	0	
		1993	4	1.2	1.2	3	0	1.8	0.2	0.2	0.2	0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
0786	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	10.8	10.8	10.8	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.8	0.8	0.8	0	0				0	0	
		1992	3	0.2	0.2	0.2	0	0				0	0	
		1992	2	1.4	1.4	3.2	0	1.8	0.5	0.5	0.5	0	0	
		1992	1	0.3	0.2	0.2	-0.1	-0.1				0	0	
1386	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1994	1	6.7	6.7	6.7	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.2	0.2	0.4	0	0.2	0.4	0.4	0.4	0	0	
		1992	2	0.4	0.4	0.3	0	-0.1	0.8	0.8	0.8	0	0	
		1992	1	0.3	0.3	0.3	0	0				0	0	
1486	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2.4	2.4	2.4	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.4	0.4	0.4	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.2	0.2	0.4	0	0.2	0.1	0.1	0.1	0	0	
		1992	2	0.4	0.4	0.3	0	-0.1				0	0	
		1992	1	0.3	0.2	0.2	-0.1	-0.1				0	0	
1886	WLM	1994	2	0	0	0	0	0				0	0	
		1994	1	5.8	5.9	5.9	0.1	0.1				0	0	No Venting data
		1993	2	0.1	0.1	0.1	0	0				0	0	
		1992	3	0.3	0.3	0.4	0	0.1	0.6	0.6	0.4	0	-0.2	
		1992	2	0.4	0.4	0.4	0	0				0	0	
		1992	1	0.3	0.2	0.2	-0.1	-0.1				0	0	
		1991	4	0.3	0.3	0.3	0	0				0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	
1986	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0	0	0	0	0				0	0	
		1993	4	0.4	0.4	0.4	0	0				0	0	
		1993	2	0.1	0.1	0.1	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
		1992	1	0.4	0.4	0.4	0	0				0	0	
		1991	4	0.4	0.4	0.9	0	0.5	0.2	0.2	0.2	0	0	
2486	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.5	0.5	0.5	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
		1992	1	0.2	0.2	0.2	0	0				0	0	
		1991	4	0.4	0.4	0.8	0	0.4	0	0	0	0	0	
3686	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	5.5	5.6	5.7	0.1	0.2				0	0	No venting data
		1993	3	0.1	0.1	0.1	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.2	0.2	0.2	0	0				0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	
		1992	1	0.2	0.2	0.2	0	0				0	0	
3886	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	5.9	6	6.2	0.1	0.3				0	0	No venting data
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.1	0.1	0.1	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1993	1	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.2	0.2	0.2	0	0				0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	
5486	WLM	1994	2	0	0	0	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1992	3	1.6	1.6	1.8	0	0.2	0.4	0.4	0.4	0	0	
		1992	2	0.8	0.8	0.8	0	0				0	0	
		1992	1	0.2	0.2	0.2	0	0				0	0	
		1991	4	0.2	0.2	0.4	0	0.2	0	0	0	0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	
		1991	2	0.4	0.4	0.4	0	0				0	0	

TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS	
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff		
B405586 =5586	WLM	1994	2	0	0	0	0	0					0	0	
		1993	2	0.1	0.1	0.1	0	0					0	0	
		1993	1	0.4	0.4	0.4	0	0					0	0	
		1992	3	1.8	2.8	3.2	1	1.4	0.4	0.4	0.4		0	0	
		1992	2	0.8	0.8	0.8	0	0					0	0	
		1992	1	0	0	0	0	0					0	0	
		1991	4	0.2	0.2	0.2	0	0					0	0	
		1991	2	0.1	0.1	0.1	0	0					0	0	
5786	SAMPLE	1994	2	0	0	0	0	0					0	0	
		1994	1	1	1	1	0	0					0	0	
		1993	2	0.8	0.8	0.8	0	0					0	0	
		1993	1	0.2	0.2	0.2	0	0					0	0	
		1992	3	0.6	0.6	0.5	0	-0.1					0	0	
		1992	2	0.7	0.7	0.6	0	-0.1					0	0	
		1992	1	0.2	0.2	0.2	0	0					0	0	
		1991	4	0	0.1	0.1	0.1	0.1	0.3	0.3	0.3		0	0	
5886	WLM	1994	2	0	0	0	0	0					0	0	
		1993	2	0.4	0.4	0.4	0	0					0	0	
		1992	3	0.6	0.6	0.5	0	-0.1					0	0	
		1992	2	0.7	0.7	0.7	0	0					0	0	
		1992	1	0.2	0.2	0.2	0	0					0	0	
		1991	4	0.2	0.2	0.2	0	0					0	0	
		1991	3	0.3	0.3	0.3	0	0					0	0	
		1991	2	0.3	0.3	0.3	0	0					0	0	
1187	SAMPLE	1994	2	0	0	0	0	0					0	0	
		1994	1	0.2	0.2	0.2	0	0					0	0	
		1993	3	0.2	0.2	0.2	0	0					0	0	
		1993	2	0.2	0.2	0.2	0	0					0	0	
		1993	1	0.2	0.2	0.2	0	0					0	0	
		1992	3	0.4	0.4	0.4	0	0					0	0	
		1992	2	4	4	5	0	1	0.4	0.4	0.4		0	0	
		1992	1	0.3	0.3	0.3	0	0	0.3	0.3	0.3		0	0	
1287	SAMPLE	1994	2	0	0	0	0	0					0	0	
		1994	1	9	9	9	0	0					0	0	
		1993	3	0	0.4	0.8	0.4	0.8					0	0	No venting data
		1993	2	0.3	0.3	0.3	0	0					0	0	
		1992	3	0.2	0.2	0.3	0	0.1	0.4	0.4	1.2		0	0.8	Day 2
		1992	2	0.4	0.4	1.2	0	0.8	0.3	0.3	0.4		0	0.1	Day 2
		1992	1	0.1	0.1	0.4	0	0.3	0.3	0.3	0.3		0	0	
		1991	4	0.1	0.1	0.2	0	0.1	0.3	0.3	0.3		0	0	
1587	SAMPLE	1994	2	0	0	0	0	0	2.5	2.5	2.5		0	0	
		1994	1	1.4	1.4	3	0	1.6					0	0	
		1993	4	0.2	0.2	0.2	0	0					0	0	
		1993	3	0.2	0.2	0.2	0	0					0	0	
		1993	2	0.4	0.4	0.4	0	0					0	0	
		1993	1	0.5	0.5	0.5	0	0					0	0	
		1992	3	0.4	0.4	0.4	0	0					0	0	
		1992	2	0.2	0.4	0.4	0.2	0.2	4	4	4		0	0	
1687BR	SAMPLE	1994	2	0	0	0	0	0					0	0	
		1994	1	1	1	1	0	0					0	0	
		1993	4	0.3	0.3	0.3	0	0					0	0	
		1993	3	0.1	0.1	0.1	0	0					0	0	
		1993	2	0.2	0.2	0.2	0	0					0	0	
		1993	1	0.3	0.3	0.3	0	0					0	0	
		1992	3	0.4	0.4	0.4	0	0					0	0	
		1992	2	0.2	0.4	0.4	0.2	0.2	3.8	3.8	3.8		0	0	
1987	SAMPLE	1994	2	0	0	0	0	0					0	0	
		1994	1	8.5	8.5	8.5	0	0					0	0	
		1993	3	0.2	0.2	0.2	0	0					0	0	
		1993	2	0.4	0.4	0.4	0	0					0	0	
		1992	3	0.3	0.3	0.3	0	0					0	0	
		1992	2	0.2	0.2	0.4	0	0.2	0.1	0.1	0.2		0	0.1	Day 2
		1992	1	0.4	0.4	1.4	0	1					0	0	No venting data
		1991	3	0.2	0.3	0.3	0.1	0.1	0.3	0.3	0.3		0	0	
2787	WLM	1994	2	0	0	0	0	0					0	0	
		1994	1	0.8	0.8	0.8	0	0					0	0	
		1993	2	0.3	0.3	0.3	0	0					0	0	
		1992	3	0.3	0.3	0.2	0	-0.1					0	0	
		1992	2	0.6	0.6	0.9	0	0.3	0.4	0.4	0.4		0	0	
		1992	1	0.1	0.1	0.2	0	0.1	0.9	0.5	0.5	-0.4	-0.4	0	
		1991	4	0.2	0.2	0.2	0	0					0	0	
		1991	3	0.2	0.2	0.2	0	0					0	0	
2987	SAMPLE	1994	2	0	0	0	0	0					0	0	
		1994	1	5	5	6	0	1					0	0	No venting data
		1993	3	0.3	0.3	0.3	0	0					0	0	
		1993	2	0.1	0.1	0.1	0	0					0	0	
		1993	1	0.4	0.4	0.4	0	0					0	0	
		1992	3	0.3	0.3	0.3	0	0					0	0	
		1992	2	0.5	0.5	0.5	0	0					0	0	
		1992	1	0.1	0.1	0.1	0	0					0	0	

**TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS**

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
3587	WLM	1994	2	0	0	0	0	0				0	0	
		1994	1	11.2	11.2	11.2	0	0				0	0	
		1992	3	0.2	0.2	0.1	0	-0.1				0	0	
		1992	2	0.2	0.2	19.5	0	19.3				0	0	No venting data
		1992	1	0.2	0.2	0.2	0	0				0	0	
		1991	4	0.3	0.3	0.3	0	0				0	0	
		1991	3	0.1	0.1	0.1	0	0				0	0	
		1991	2	0.3	0.3	5.3	0	5				0	0	No venting data
3687BR	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2.5	2.5	2.5	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.4	0.4	0.4	0	0				0	0	
		1993	2	0.1	0.1	0.1	0	0				0	0	
		1993	1	0.5	0.5	0.5	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.2	0.2	2.4	0	2.2				0	0	No venting data
4387	WLM	1994	2	0	0	0	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1992	1	0.1	0.1	0.1	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.5	0.5	250	0	249.5				0	0	No venting data
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.3	0.3	0.3	0	0				0	0	
		1991	2	0.4	0.4	0.8	0	0.4	0.2	0.2	0.2	0	0	
4487	WLM	1994	2	0	0	0	0	0				0	0	
		1994	1	5.5	5.5	5.5	0	0				0	0	
		1992	3	0.2	0.2	0.2	0	0				0	0	
		1992	2	4	4	17	0	13	0.6	0.6	0.6	0	0	
		1992	1	0.2	0.2	0.2	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.1	0.1	0.1	0	0				0	0	
		1991	2	0.4	0.4	0.4	0	0				0	0	
4587BR	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2.8	2.8	2.8	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	4	4	4.5	0	0.5	0.2	0.2	0.2	0	0	
		1992	1	0.2	0.2	0.2	0	0				0	0	
5087	WLM	1994	2	0	0	0	0	0				0	0	
		1994	1	5.2	5.2	5.2	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	4	4	4.5	0	0.5				0	0	No venting data
		1992	1	0.1	0.1	0.1	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.1	0.2	0.2	0.1	0.1				0	0	No venting data
		1991	2	2.4	2.4	2.4	0	0				0	0	
5187	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	3.6	3.6	3.6	0	0				0	0	
		1993	1	0.7	0.7	1	0	0.3	0	0	0	0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
		1992	1	0.1	0.1	0.1	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	
5487	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	1.2	1.2	1.2	0	0				0	0	
		1993	3	0.1	0.1	0.1	0	0				0	0	
		1993	2	0.6	0.6	17	0	16.4	0.4	0.4	10	0	9.6	2nd day
		1991	2	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.3	0.3	0.2	0	-0.1				0	0	
		1992	2	0.4	0.4	0.3	0	-0.1				0	0	
		1992	1	0.1	0.1	0.1	0	0				0	0	
5587	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	5.6	5.6	5.6	0	0				0	0	
		1993	3	0.02	0.02	1	0	0.98	0	0	0	0	0	
		1993	2	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.3	0.3	0.2	0	-0.1				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
		1992	1	0.1	0.1	0.1	0	0				0	0	
		1991	4	0.1	0.1	0.1	0	0				0	0	
5887	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.3	0.3	0.3	0	0				0	0	
		1993	4	0.3	0.3	0.4	0	0.1	0.5	0.5	0.5	0	0	1% LEL
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.3	0.3	0.3	0	0				0	0	
		1993	1	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.2	0.2	0.2	0	0				0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	

**TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS**

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
6087	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	1	1	1	0	0				0	0	
		1993	4	0.5	0.5	0.5	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.5	0.5	0.5	0	0				0	0	
		1992	3	0.1	0.1	0.1	0	0				0	0	
		1992	2	1.4	1.4	3.8	0	2.4	0.2	0.2	0.2	0	0	
		1992	1	0.3	0.2	0.1	-0.1	-0.2				0	0	
6187	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	1	1	1	0	0				0	0	
		1993	4	0	0.2	0.2	0.2	0.2				0	0	1% EXP
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.2	0.6	0.6	0.4	0.4				0	0	
		1992	3	0.1	0.1	0.1	0	0				0	0	
		1992	2	1.2	1.2	1.2	0	0				0	0	
6287	WLM	1994	2	0	0	0	0	0				0	0	
		1993	1	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.1	0.1	0.3	0	0.2	0.3	0.3	0	0	-0.3	
		1992	2	1.2	1.2	3.8	0	2.6	0.2	0.2	0.2	0	0	
		1992	1	0.2	0.2	0.1	0	-0.1				0	0	
		1991	4	0.3	0.3	0.3	0	0				0	0	
		1991	3	0.4	0.4	0.4	0	0				0	0	
		1991	2	1.5	1.5	1.4	0	-0.1				0	0	
B400489	WLM	1994	2	0	0	0	0	0				0	0	
		1993	2	0	0	0	0	0				0	0	
		1993	1	0.4	0.4	0.4	0	0				0	0	
		1992	3	3	3	3.6	0	0.6	0.2	0.2	0.2	0	0	
		1992	2	0.5	0.5	0.5	0	0				0	0	
		1992	1	0	0	0	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	
B201189	WLM	1994	2	0	0	0	0	0				0	0	
		1993	1	0.8	0.8	2.5	0	1.7	0.5	0.5	0.5	0	0	
		1992	3	2	2	2	0	0				0	0	
		1992	2	0.8	0.8	100	0	99.2	0.8	0.8	0.8	0	0	
		1992	1	0	0	0	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	
		1991	2	2	2	2	0	0				0	0	
B201589	WLM	1994	2	0	0	0	0	0				0	0	
		1993	1	0.2	0.2	0.2	0	0				0	0	
		1992	3	2.4	2.4	2.4	0	0				0	0	
		1992	2	2	2	150	0	148	0.2	0.2	0.2	0	0	
		1992	1	0	0	0	0	0				0	0	
		1991	4	0	0	0	0	0				0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	
		1991	2	2	2	2	0	0				0	0	
B202589	WLM	1994	2	0	0	0	0	0				0	0	
		1993	1	0.3	0.3	0.5	0	0.2	0.4	0.4	0.4	0	0	
		1992	3	2.4	2.4	2.4	0	0				0	0	
		1992	2	1.2	1.2	4	0	2.8	0.5	0.5	0.5	0	0	
		1992	1	0	0	0	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.2	0.2	0.3	0	0.1				0	0	No venting data
		1991	2	0.2	0.2	0.2	0	0				0	0	
B302789	WLM	1994	2	0	0	0	0	0				0	0	
		1993	1	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.2	0.2	2.8	0	2.6	0.2	0.2	0.3	0	0.1	Day 2
		1992	2	0.4	0.4	0.4	0	0				0	0	
		1992	1	0	0	0	0	0				0	0	
		1991	4	0.15	0.15	0.15	0	0				0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	
		1991	2	0.2	0.2	0	0	-0.2				0	0	
B302989	WLM	1994	2	0	0	0	0	0				0	0	
		1992	3	2.8	2.8	2.8	0	0				0	0	
		1992	2	0.7	0.7	0.6	0	-0.1				0	0	
		1992	1	0	0	0	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.3	0.3	0.3	0	0				0	0	
		1991	2	0.3	0.3	0.3	0	0				0	0	
		1991	1	0.2	0.3	0.3	0.1	0.1				0	0	No venting data
B203189	WLM	1994	2	0	0	0	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1993	1	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.7	0.7	0.7	0	0				0	0	
		1992	1	0.6	0.6	0.7	0	0.1	0.2	0.2	0.2	0	0	
		1991	4	0.3	0.3	0.3	0	0				0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	

**TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS**

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
B203489	WLM	1994	2	0	0	0	0	0					0	
		1993	2	0.3	0.3	0.3	0	0					0	
		1993	1	0.2	0.2	0.7	0	0.5	0.2	0.2	0.2		0	
		1992	3	2	2	2	0	0					0	
		1992	2	0.4	0.4	0.4	0	0					0	
		1992	1	0.4	0.4	0.4	0	0					0	
		1991	4	0.3	0.3	0.3	0	0					0	
		1991	3	0.2	0.2	0.2	0	0					0	
B203589	WLM	1994	2	0	0	0	0	0					0	
		1993	2	0.6	0.6	0.6	0	0					0	
		1993	1	0.2	0.2	0.2	0	0					0	
		1992	3	1.8	1.8	1.8	0	0					0	
		1992	2	1.7	1.7	150.2	0	148.5	0.2	0.2	0.2		0	
		1992	1	0.4	0.4	0.4	0	0					0	
		1991	4	0.3	0.3	0.3	0	0					0	
		1991	3	0.4	0.4	0.4	0	0					0	
B203889	WLM	1994	2	0	0	0	0	0					0	
		1993	2	0.6	0.6	0.6	0	0					0	
		1993	1	0.2	0.2	0.2	0	0					0	
		1992	3	1.8	1.8	1.8	0	0					0	
		1992	2	1.7	1.7	2.1	0	0.4	0.3	0.3	0.3		0	
		1992	1	0.2	0.2	0.2	0	0					0	
		1991	4	0.3	0.3	0.3	0	0					0	
		1991	3	0.2	0.2	0.2	0	0					0	
B203989	WLM	1994	2	0	0	0	0	0					0	
		1994	1	0	0	0	0	0					0	
		1993	1	0.4	0.4	0.4	0	0					0	
		1992	3	1.9	1.9	1.9	0	0					0	
		1992	2	0.15	1.5	2	1.35	1.85	0.3	0.3	0.3		0	
		1992	1	0	0	0	0	0					0	
		1991	4	0.2	0.4	0.4	0.2	0.2					0	No venting data
		1991	3	0.2	0.2	0.2	0	0					0	
B204089	WLM	1994	2	0	0	0	0	0					0	
		1994	1	6.8	6.8	6.8	0	0					0	
		1993	1	0.3	0.3	0.3	0	0					0	
		1992	3	0.5	0.5	0.5	0	0					0	
		1992	2	1	1	1.2	0	0.2	0.4	0.4	0.4		0	
		1992	1	4	4	4.8	0	0.8	0.3	0.3	0.3		0	
		1991	4	0.3	0.3	0.3	0	0					0	
		1991	3	0.2	0.2	0.4	0	0.2					0	
B204189	WLM	1994	2	0	0	0	0	0					0	
		1994	1	8	8	8	0	0					0	
		1993	1	0.5	0.5	0.5	0	0					0	
		1992	3	0.5	0.5	0.5	0	0					0	
		1992	2	1	1.2	0.8	0.2	-0.2	0.4	0.4	0.4		0	
		1992	1	4	4	5	0	1	0.3	0.3	0.3		0	
		1991	4	0.3	0.3	0.3	0	0					0	
		1991	3	0.2	0.2	0.2	0	0					0	
B405289	WLM	1994	2	0	0	0	0	0					0	
		1993	2	0.2	0.2	0.2	0	0					0	
		1993	1	0.2	0.2	0.2	0	0					0	
		1992	3	3.4	3.4	3.6	0	0.2	0.2	0.2	0.2		0	
		1992	2	0.7	0.7	0.6	0	-0.1					0	
		1992	1	0.4	0.4	0.4	0	0					0	
		1991	4	0.1	0.1	0.1	0	0					0	
		1991	3	0.2	0.2	0.2	0	0					0	
B405489	WLM	1994	2	0	0	0	0	0					0	
		1993	2	0.3	0.3	0.3	0	0					0	
		1993	1	0.2	0.2	0.2	0	0					0	
		1992	3	2.6	3	4.2	0.4	1.6	0.2	0.2	0.2		0	
		1992	2	0.3	0.3	0.3	0	0					0	
		1992	1	0	0	0	0	0					0	
		1991	4	0.2	0.2	0.2	0	0					0	
		1991	3	0.1	0.1	0.1	0	0					0	
B405689	WLM	1994	2	0	0	0	0	0					0	
		1993	2	0.3	0.3	0.3	0	0					0	
		1993	1	0.8	0.8	0.8	0	0					0	
		1992	3	2.2	2.2	2.8	0	0.6	0.2	0.1	0.1	-0.1	-0.1	
		1992	2	1.2	1.2	0.8	0	-0.4					0	
		1992	1	0	0	0	0	0					0	
		1991	4	0.2	0.1	0.1	-0.1	-0.1					0	
		1991	3	0.2	0.2	0.2	0	0					0	
B405989	WLM	1994	2	0	0	0	0	0					0	
		1993	1	0.2	0.2	0.2	0	0					0	
		1992	3	1.8	1.8	1.8	0	0					0	
		1992	2	0.7	0.7	0.5	0	-0.2					0	
		1992	1	0.4	0.4	0.4	0	0					0	
		1991	4	0.1	0.2	0.1	0.1	0	0.3	0.2	0.2	-0.1	-0.1	
		1991	3	0.2	0.2	0.2	0	0					0	
		1991	2	0.3	0.3	0.3	0	0					0	

TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
B106089	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2.1	2.1	2.1	0	0				0	0	
		1993	4	0.3	0.3	0.3	0	0				0	0	
		1993	3	0	0	0	0	0				0	0	
		1993	2	0.3	0.3	0.3	0	0				0	0	
		1993	1	0.2	0.2	0.3	0	0.1				0	0	No venting data
		1992	3	0.1	0.1	0.1	0	0				0	0	
		1992	2	0.4	0.4	0.3	0	-0.1				0	0	
B206289	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	4.5	4.5	5	0	0.5				0	0	no venting data
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.3	0.3	0.3	0	0				0	0	
		1993	1	0.2	0.4	0	0.2	-0.2				0	0	
		1992	3	0.1	0.1	0.1	0	0				0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	
B206589	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	5.5	5.5	5.3	0	-0.2				0	0	
		1993	3	0	0	0	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.3	0.3	0.4	0	0.1				0	0	No venting data
		1992	3	0.1	0.1	0.1	0	0				0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	
		1992	1	0.3	0.2	0.2	-0.1	-0.1				0	0	
B206789	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.02	0.02	0.02	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.1	0.1	0.1	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.8	0.8	12	0	11.2				0	0	no venting data
		1992	3	0.2	0.2	0.2	0	0				0	0	
		1992	2	1.6	1.6	1.6	0	0				0	0	
B206889	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.3	0.3	0.3	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.5	0.5	0.5	0	0				0	0	
		1992	3	0.2	0.2	0.2	0	0				0	0	
		1992	2	1.6	1.6	100.4	0	98.8	0.3	0.3	0.3	0	0	
		1992	1	0.3	0.3	0.2	0	-0.1				0	0	
B207289	WLM	1994	2	0	0	0	0	0				0	0	
		1994	1	0.09	0.09	0.09	0	0				0	0	
		1993	1	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	1.6	1.6	6.3	0	4.7				0	0	No venting data
		1992	1	0.2	0.2	0.2	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	
P207389	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.3	0.3	0.3	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
		1991	4	0.2	0.2	0.3	0	0.1	0.2	0.2	0.2	0	0	
P209289	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0	0	0	0	0				0	0	
		1993	4	0.3	0.3	0.3	0	0				0	0	
		1993	3	0.1	0.1	0.1	0	0				0	0	
		1993	2	0.6	1	200	0.4	199.4	0.4	0.4	0.4	0	0	
		1993	1	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
P209589	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
		1992	1	0.3	0.3	0.3	0	0				0	0	
		1991	4	0.4	0.4	0.8	0	0.4	0.2	0.2	0.2	0	0	
P209789	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0	0	0	0	0				0	0	
		1993	4	0.6	0.6	0.6	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.4	0.4	2	0	1.6				0	0	No venting data
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
		1992	1	0.1	0.1	0.1	0	0				0	0	

TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
P210189	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.04	0.04	0.04	0	0				0	0	
		1993	4	0.5	0.5	0.04	0	-0.46				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.6	0.6	4	0	3.4	0.5	0.5	1	0	0.5	
		1993	1	0.4	0.4	1	0	0.6				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.3	0.3	0.5	0	0.2				0	0	No venting data
B410589	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.7	0.7	1	0	0.3	0.3	0.3	0.3	0	0	
		1992	1	0.3	0.3	0.3	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.2	0.2	0.2	0	0				0	0	
		1991	2	0.4	0.4	0.4	0	0				0	0	
		1991	1	0.2	0.2	0.2	0	0				0	0	
B410689	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.8	0.8	0.7	0	-0.1				0	0	
		1992	1	0.3	0.3	0.3	0	0				0	0	
		1991	4	0.3	0.3	0.3	0	0				0	0	
		1991	3	0.2	0.2	0.3	0	0.1	0.2	0.2	0.2	0	0	
		1991	2	0.3	0.4	0.4	0.1	0.1	0.4	0.4	0.4	0	0	
		1991	1	0	0	0	0	0				0	0	
B213789	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	5.5	5.6	5.8	0.1	0.3				0	0	no venting data
		1993	4	0.4	0.4	0.4	0	0				0	0	
		1992	3	0	0	0	0	0				0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	
B315289	WLM	1994	2	0	0	0.1	0	0.1				0	0	No venting data
P115589	SAMPLE	1994	2	0	0	2.1	0	2.1	0	0	0	0	0	
		1994	1	3	3	3	0	0				0	0	
		1993	4	0.8	0.8	0.8	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.4	0.4	0.5	0	0.1				0	0	No venting data
P115689	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2	2	4.9	0	2.9	0.7	0.7		0	-0.7	
		1993	4	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.5	0.5	0.5	0	0				0	0	
P416889	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.33	0.33	0.35	0	0.02	2.8	2.8	2.8	0	0	
		1993	4	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	
B218789	WLM	1994	2	0	0	0	0	0				0	0	
		1992	3	0.1	0.1	0.1	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
		1992	1	0.3	0.3	0.3	0	0				0	0	
		1991	4	0.2	0.2	0.2	0	0				0	0	
		1991	3	0.1	0.1	0.1	0	0				0	0	
		1991	2	0.4	0.4	2.2	0	1.8	0.4	0.4	0.6	0	0.2	
		1993	2	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	5.2	5.2	5.8	0	0.6	0.8	0.8	0.8	0	0	
00191	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	1.2	1.2	1.2	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0	0.02	0.02	0.02	0.02				0	0	No venting data
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1993	1	0.5	0.5	1	0	0.5				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	
00391	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.1	0.1	0.1	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.4	0.4	1	0	0.6				0	0	No venting data
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.2	0.2	0.4	0	0.2				0	0	No venting data
00691	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	6	6	6	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.6	0.6	0.6	0	0				0	0	
		1992	2	4.8	4.8	5.4	0	0.6				0	0	No venting data
00791	WLM	1994	2	0	0	0	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	5.2	5.2	6	0	0.8	0.2	0.2	0.2	0	0	
00991	WLM	1994	2	0	0	0	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	4	4	9	0	5				0	0	No venting data
		1992	1	8	8	20	0	12				0	0	No venting data

TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
01291	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	5.8	5.8	5.8	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.4	0.4	0.6	0	0.2				0	0	No venting data
		1992	1	7.2	7.2	9	0	1.8				0	0	No venting data
01391	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2.8	2.8	2.8	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.6	0.6	0.6	0	0				0	0	
		1993	1	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
01991	SAMPLE	1994	2	0.2	0.2	0.3	0	0.1				0	0	No venting data
		1994	1	1	1	1	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.3	0.3	0.3	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	2	4.8	4.8	5	0	0.2				0	0	No venting data
02091	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	4.2	4.2	8.4	0	4.2				0	0	No venting data
		1993	4	2.6	2.6	9.2	0	6.6				0	0	No venting data
		1993	3	0.2	0.2	25	0	24.8				0	0	Rapid dissipation
		1993	1	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.2	0.2	0.2	0	0				0	0	
02191	WLM	1994	2	0	0	0	0	0				0	0	
		1994	1	1.6	1.6	2.4	0	0.8				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.4	0.4	0.4	0	0				0	0	
		1993	2	0.2	0.2	6.5	0	6.3				0	0	No venting data
		1993	1	1.5	1.8	5	0.3	3.5				0	0	No venting data
		1991	4	4.1	4.1	4.1	0	0				0	0	
02291	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.4	0	0.2				0	0	No venting data
		1993	4	0.2	0.2	22	0	21.8	0.2	0.2	20	0	19.8	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.5	0.5	2	0	1.5	0.5	0.5	0.5	0	0	1 Min. venting
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.5	0.5	2	0	1.5	1	1	1	0	0	
02491	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	2.2	2.2	2.2	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.5	0.5	0.5	0	0				0	0	
		1992	1	1.5	1.5	14	0	12.5	8.2	8.2	8.2	0	0	
02591	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	3.5	3.5	3.5	0	0				0	0	
		1993	4	2	2	2	0	0				0	0	
		1993	3	0.1	0.1	0.1	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1993	1	0.7	0.7	0.7	0	0				0	0	
		1992	3	0.1	0.1	0.1	0	0				0	0	
02691	SAMPLE	1994	2	4.8	4.8	6.6	0	1.8	0.4	0.4	0.4	0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.9	0.9	0.9	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.8	0.8	0.8	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
02791	WLM	1994	2	0.4	0.5	1.5	0.1	1.1	0.5	0.5	0.5	0	0	
		1994	1	0	0	0	0	0				0	0	
		1993	3	0.1	0.1	0.1	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	2.8	2.8	6	0	3.2				0	0	No venting data
		1992	2	0	0	0	0	0				0	0	
		1992	1	11	11	11.5	0	0.5				0	0	No venting data
02891	WLM	1994	2	0.2	0.2	0.2	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.3	0.3	0.3	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.2	0.2	0.2	0	0				0	0	
		1992	2	0.2	0.2	0.2	0	0				0	0	
02991	SAMPLE	1994	2	0.2	0.2	0.2	0	0				0	0	
		1994	1	8.8	8.8	11.8	0	3				0	0	No venting data

TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
02991	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.2	0.2	0.2	0	0				0	0	
		1992	2	0.2	0.2	0.2	0	0				0	0	
		1992	1	3.8	4.8	4.8	1	1	1.6	1.6	1.6	0	0	
03091	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	1	1	1	0	0				0	0	
		1993	4	2.2	2.2	3	0	0.8				0	0	No venting data
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	0.2	0.2	0.2	0	0				0	0	
03191	WLM	1994	2	0	0	0	0	0				0	0	
		1994	1	11.5	11.5	11.5	0	0				0	0	
		1993	4	0.3	0.3	0.3	0	0				0	0	
		1992	3	1.5	1.5	1.5	0	0				0	0	
		1992	2	0.2	0.2	0.2	0	0				0	0	
		1992	1	8.6	8.6	10.2	0	1.6	0	0	0.2	0	0.2	
		1991	4	1.2	1.2	1.2	0	0				0	0	
		1991	1	0	0	0	0	0				0	0	
03591	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.6	0.6	0.6	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.1	0.1	0.1	0	0				0	0	
		1992	2	0.2	0.2	0.2	0	0				0	0	
		1992	1	7.2	7.2	8.4	0	1.2	0.2	0.2	0.2	0	0	Day 4
03691	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.8	0.8	3.5	0	2.7				0	0	No venting data
		1993	4	0.4	0.4	0.4	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1993	1	0.7	0.7	6	0	5.3				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.2	0.2	0.2	0	0				0	0	
04091	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2.8	2.8	2.8	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.6	0.6	0.6	0	0				0	0	
		1992	2	4	4	5	0	1	4.8	5	5.4	0.2	0.6	Day 2
04291	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.8	0.8	0.8	0	0				0	0	
		1993	4	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.3	0.3	0.4	0	0.1	0.4	0.4	0.4	0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	
		1992	1	4.8	4.8	6.2	0	1.4				0	0	No venting data
		1992	1	7.8	7.8	8	0	0.2	0.2	0.2	0.2	0	0	No venting data
04491	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.8	0.8	0.8	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.03	0.03	0.03	0	0				0	0	
		1992	3	0.9	0.9	0.4	0	-0.5				0	0	
		1992	2	0.4	0.4	0.6	0	0.2	0.2	0.2	0.2	0	0	
		1992	1	7.8	7.8	8	0	0.2				0	0	No venting data
		1992	1	7.8	7.8	8	0	0.2				0	0	No venting data
04891	WLM	1994	2	0	0	0	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.3	0.3	0.3	0	0				0	0	
		1992	1	2	2	2.2	0	0.2	1	1	1	0	0	
		1991	4	0	0	0	0	0				0	0	
		1991	1	0	0	0	0	0				0	0	
		1991	1	0	0	0	0	0				0	0	
04991	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.1	0.1	0.1	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.4	0.4	0.4	0	0				0	0	
		1992	1	4.6	4.6	5	0	0.4	2	2	2	0	0	
05091	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.5	0.5	0.5	0	0				0	0	
		1992	1	0.3	0.9	0.5	0.6	0.2	0.5	0.5	0.5	0	0	

**TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS**

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
05291	ND	1994	2	0	0	0.1	0	0.1	0	0	0	0	0	
		1992	3	0.3	0.3	0.3	0	0						
		1992	2	0.4	0.4	2.8	0	2.4						No venting data
05391	SAMPLE	1994	2	0	0	0	0	0						
		1994	1	0.8	0.8	0.8	0	0						
		1993	3	0.3	0.3	0.3	0	0						
		1993	2	0.2	0.2	0.2	0	0						
		1993	1	0.5	0.5	0.5	0	0						
		1992	3	0.1	0.1	0.1	0	0						
		1992	2	0.2	0.2	0.2	0	0						
		1992	1	6.4	6.4	6.8	0	0.4	0.4	0.4	0.4	0	0	Day 2
		1994	2	0	0	0	0	0						
05691	SAMPLE	1994	1	2.8	2.8	2.8	0	0						
		1993	4	0.3	0.3	0.3	0	0						
		1993	3	0.3	0.3	0.4	0	0.1						No venting data
		1993	2	0.2	0.2	0.2	0	0						
		1993	1	0.6	0.6	0.8	0	0.2						No venting data
		1992	3	0.2	0.2	0.2	0	0						
		1992	2	0.3	0.3	0.3	0	0						
		1994	2	0	0	0.6	0	0.6						No venting data
		1994	1	0.3	0.3	0.3	0	0						
06191	SAMPLE	1993	4	2	2	2	0	0						
		1993	3	0.1	0.1	0.1	0	0						
		1993	2	0.8	0.8	0.8	0	0						
		1993	1	0.7	0.7	0.7	0	0						
		1992	3	0.1	0.1	0.1	0	0						
		1992	2	0.3	0.3	0.3	0	0						
		1994	2	0	0	0	0	0						
		1994	1	0	0	0	0	0						
		1993	4	0.2	0.2	0.2	0	0						
06491	SAMPLE	1993	3	0.3	0.3	0.3	0	0						
		1993	2	0.2	0.2	0.2	0	0						
		1993	1	0.4	0.4	0.6	0	0.2	0.3	0.3	0.3	0	0	
		1992	3	0.2	0.2	0.2	0	0						
		1992	2	11.4	11.4	17.2	0	5.8	0.4	0.4	0.4	0	0	
		1994	2	0	0	0	0	0						
		1994	1	1	1	1	0	0						
		1993	4	0.4	0.4	0.4	0	0						
		1993	3	0.4	0.4	0.4	0	0						
06591	SAMPLE	1993	2	0.2	0.2	0.2	0	0						
		1993	1	0.3	0.3	0.3	0	0						
		1992	3	0.4	0.4	0.3	0	-0.1						
		1992	2	0.2	0.4	0.4	0.2	0.2	5	5	5	0	0	
		1994	2	0	0	0	0	0						
		1994	1	1	1	1	0	0						
		1993	4	0.2	0.2	0.2	0	0						
		1993	3	0.3	0.3	0.3	0	0						
		1993	2	0.1	0.1	0.1	0	0						
06691	SAMPLE	1993	1	0.3	0.3	0.3	0	0						
		1992	3	0.4	0.4	0.9	0	0.5	0.3	0.3	0.3	0	0	
		1992	2	4.8	4.8	15	0	10.2	0.6	0.6	0.6	0	0	2 weeks later
		1994	2	0	0	0	0	0						
		1994	1	1	1	1	0	0						
		1993	4	0.2	0.2	0.2	0	0						
		1993	3	0.3	0.3	0.3	0	0						
		1993	2	0.1	0.1	0.1	0	0						
		1993	1	0.3	0.3	0.3	0	0						
06791	SAMPLE	1992	3	0.4	0.4	0.5	0	0.2	0.3	0.3	0.3	0	0	
		1992	2	5	5	10	0	5	3.6	3.6	4.4	0	0.8	
		1994	2	0	0	0	0	0						
		1994	1	1.8	1.8	1.8	0	0						
		1993	4	0.3	0.3	0.3	0	0						
		1993	3	0.3	0.3	0.3	0	0						
		1993	2	0.4	0.4	0.4	0	0						
		1993	1	0.5	0.5	0.8	0	0.3	0.3	0.3	0.3	0	0	
		1992	3	0.3	0.3	0.5	0	0.2	0.3	0.3	0.3	0	0	
06991	SAMPLE	1992	2	0.2	0.2	1	0	0.8	1	1	1	0	0	Next month
		1994	2	0	0	0	0	0						
		1994	1	4.5	4.5	4.5	0	0						
		1993	4	0.2	0.2	0.2	0	0						
		1993	3	0.2	0.2	0.2	0	0						
		1993	2	0.2	0.2	0.2	0	0						
		1993	1	0.5	0.5	0.5	0	0						
		1992	3	0.3	0.3	0.3	0	0						
		1992	2	0.2	0.2	1	0	0.8	1	1	1	0	0	Next month
07191	SAMPLE	1994	2	0	0	0	0	0						
		1994	1	1.5	1.5	1.8	0	0.3	2.2	2.2	2.8	0	0.6	
		1993	4	0.6	0.6	0.6	0	0						
		1993	3	0.3	0.3	0.3	0	0						
		1993	2	0.1	0.1	0.1	0	0						
		1993	1	0.6	0.6	0.6	0	0						
		1992	3	0.4	0.4	1.2	0	0.8						No venting data
		1992	2	0.8	0.4	1	-0.4	0.2						No venting data
		1994	2	1.5	1.5	5.3	0	3.8						No venting data
07291	SAMPLE	1993	4	0.4	0.4	0.4	0	0						
		1993	3	0.2	0.2	4	0	3.8	0.1	0.1	0.1	0	0	
		1993	2	0.1	0.1	0.1	0	0						
		1993	1	0.5	0.5	0.5	0	0						
		1992	3	0.3	0.3	0.4	0	0.1						
		1992	2	0.2	0.4	0.4	0.2	0.2						

**TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS**

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
07391	SAMPLE	1994	2	0	0	0	0	0						
		1994	1	2.5	2.5	11	0	8.5	1	1	5	0	4	Day 2
		1993	4	0.6	0.6	1.6	0	1	0.4	0.4	1	0	0.6	Day 2
		1993	3	0.2	0.2	0.9	0	0.7	0.2	0.2	50	0	49.8	Day 2
		1993	2	4	4	4.9	0	0.9	0.4	0.4	3.5	0	3.1	Day 2
		1993	1	0.6	0.6	10	0	9.4	0.6	0.6	10	0	9.4	Day 2
		1992	3	0.3	0.3	0.8	0	0.5	0.5	0.5	0.5	0	0	
		1992	2	4	4	35	0	31	0.3	0.3	0.4	0	0.1	Next month
		1992	1	0	0	0	0	0						
07891	SAMPLE	1994	2	0	0	0	0	0						
		1994	1	0.2	0.2	0.2	0	0					0	
		1993	4	0.2	0.2	0.2	0	0					0	
		1993	3	0.3	0.3	0.3	0	0					0	
		1993	1	0.5	0.5	0.5	0	0					0	
		1992	3	0.1	0.1	0.1	0	0					0	
		1992	2	0.2	0.2	1.6	0	1.4	0.5	0.5	0.5	0	0	
07991	SAMPLE	1994	2	0	0	0	0	0						
		1994	1	0.2	0.2	0.2	0	0					0	
		1993	4	0.4	0.4	0.4	0	0					0	
		1993	3	0.3	0.3	0.3	0	0					0	
		1993	2	0.2	0.2	0.2	0	0					0	
		1993	1	0.2	0.2	0.2	0	0					0	
		1992	3	0.4	0.4	0.4	0	0					0	
		1992	2	0.4	0.4	1.8	0	1.4					0	No venting data
08091	SAMPLE	1994	2	0	0	0	0	0						
		1994	1	0.8	0.8	0.8	0	0					0	
		1993	4	0.3	0.3	0.3	0	0					0	
		1993	3	1.4	1.4	1.4	0	0					0	
		1993	1	1.4	1.4	1.4	0	0					0	
		1992	3	0.3	0.3	0.3	0	0					0	
		1992	2	0.4	0.4	0.6	0	0.2	0.6	0.6	0.6	0	0	Next month
		1992	1	5.5	5.5	6.4	0	0.9					0	No venting data
08291	WLM	1994	2	0	0	0	0	0						
		1992	3	0.4	0.5	0.4	0.1	0	0.3	0.3	0.3	0	0	
		1992	2	0.4	0.4	0.6	0	0.2	0.2	0.2	0.2	0	0	Next month
08491	WLM	1994	2	0	0	0	0	0						
		1992	3	0.3	0.3	0.3	0	0					0	
		1992	2	0.4	0.4	1	0	0.6	0.2	0.2	0.2	0	0	Next month
08591	WLM	1994	2	0	0	0	0	0						
		1993	2	0.2	0.2	0.2	0	0					0	
		1993	1	1.4	1.4	1.4	0	0					0	
		1992	3	0.2	0.2	0.2	0	0					0	
		1992	2	0.2	0.4	0.6	0.2	0.4	0.4	0.4	0.4	0	0	
		1992	1	2	2	3	0	1					0	
08891	SAMPLE	1994	2	0	0	0	0	0						
		1994	1	1	3	4	2	3					0	Vented Quickly
		1993	4	0.4	0.4	30	0	29.6					0	No venting data
		1993	3	0.3	0.3	50	0	49.7	0.2	0.2	50	0	49.8	Day 2
		1993	2	0.2	0.2	0.2	0	0					0	
		1993	1	0.5	0.5	12	0	11.5	0.4	0.4	12	0	11.6	Day 2
		1992	3	0.4	0.4	43	0	42.6					0	No venting data
		1992	2	0.6	0.6	0.8	0	0.2					0	No venting data
09691	SAMPLE	1994	2	0	0	0	0	0						
		1994	1	1.2	1.2	1.2	0	0					0	
		1993	4	0.4	0.4	0.4	0	0					0	
		1993	3	0.4	0.4	0.4	0	0					0	
		1993	2	0.3	0.3	0.3	0	0					0	
		1993	1	0.6	0.6	1.4	0	0.8					0	No venting data
		1992	3	0.2	0.2	0.2	0	0					0	
		1992	2	3.8	3.8	5.2	0	1.4	0.7	0.7	0.7	0	0	
11791	SAMPLE	1994	2	0	0	0	0	0						
		1994	1	9	9	9	0	0					0	
		1993	4	0.6	0.6	0.6	0	0					0	
		1993	3	0.1	0.1	0.1	0	0					0	
		1993	2	0.2	0.2	0.2	0	0					0	
		1993	1	0.4	0.4	1	0	0.6					0	No venting data
		1992	3	0.3	0.3	0.3	0	0					0	
		1992	2	0.2	0.2	0.4	0	0.2	0.2	0.2	0.2	0	0	Next month
11891	SAMPLE	1994	2	0	0	0.9	0	0.9						No venting data
		1994	1	2.8	2.8	2.8	0	0					0	
		1993	4	3.2	3.2	3.2	0	0					0	
		1993	3	0.2	0.2	0.2	0	0					0	
		1993	2	0.4	0.4	0.4	0	0					0	
		1993	1	0.7	0.7	0.7	0	0					0	
		1992	3	0.4	0.4	0.4	0	0					0	
		1992	2	0.2	0.2	0.2	0	0					0	

TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
12091	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.6	0.6	0.6	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.5	0.5	1.5	0	1	0.3	0.3	0.3	0	0	Next month
12191	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	1.2	1.2	1.2	0	0				0	0	
		1993	4	2.1	5.2	2.1	3.1	0				0	0	No venting data
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.3	7	0.3	6.7	0	0.8	0.8	2	0	1.2	
		1993	1	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.1	0.1	0.1	0	0				0	0	
12891	WLM	1994	2	0	0	0	0	0				0	0	
		1992	3	0.3	0.3	0.4	0	0.1	0.2	0.2	0.2	0	0	
		1992	2	0.4	0.4	1	0	0.6	0.4	0.4	0.4	0	0	
12991	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.3	0.3	0.3	0	0				0	0	
		1993	1	0.6	0.6	0.6	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
13091	SAMPLE	1994	2	0.4	0.4	1.2	0	0.8	0.3	0.3	0.4	0	0.1	Next month
		1994	1	1.4	1.4	1.4	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
13191	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2.5	2.5	3	0	0.5	1.2	1.2	2	0	0.8	
		1993	4	0.4	0.4	0.4	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1994	4	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.3	0.3	0.7	0	0.4	0.6	0.6	0.6	0	0	
13291	SAMPLE	1994	2	0.2	0.4	0.4	0.2	0.2	0.4	0.4	0.4	0	0	Next month
		1994	1	0.8	0.8	0.8	0	0				0	0	
		1993	4	0.4	0.4	0.4	0	0				0	0	
13491	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	3.1	3.1	3.1	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1993	1	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.1	0.1	0.1	0	0				0	0	
13591	WLM	1994	2	0.6	0.6	1.2	0	0.6	4.4	4.4	4.4	0	0	Next month
		1992	3	0.2	0.2	0.5	0	0.3				0	0	No venting data
		1992	2	3.4	2.4	3.8	-1	0.4	0.4	0.4	0.4	0	0	Next month
30991	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	1	1	1	0	0				0	0	
		1993	4	0.3	0.3	0.3	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.3	0.3	0.3	0	0				0	0	
		1993	1	0.8	0.8	0.8	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
33491	SAMPLE	1994	2	4.5	4.5	5	0	0.5	0.4	0.4	0.4	0	0	Next month
		1994	1	1	1	1	0	0				0	0	
		1993	4	0	0	0	0	0				0	0	
36191	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	4.6	4.6	6	0	1.4	1.2	1.2	1.2	0	0	
		1993	4	0.1	0.1	0.1	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	1	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	5.5	5.5	6	0	0.5	0.2	0.2	0.2	0	0	

TABLE E-3
ROCKY FLATS GROUNDWATER WELLS WITH POSITIVE PID READINGS

Well ID	Status	Year	Qtr	At Opening					After Venting					COMMENTS
				BG	BZ	WH	BZ Diff	WH Diff	BG	BZ	WH	BZ Diff	WH Diff	
36391	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	4	4	4	0	0				0	0	
		1993	4	0	0	0	0	0				0	0	
		1993	3	0.1	0.1	0.1	0	0				0	0	
		1993	1	0.8	0.8	0.8	0	0				0	0	
		1992	3	0.3	0.3	0.3	0	0				0	0	
		1992	2	5.5	5.5	6	0	0.5	1	1	1	0	0	Next month
37191	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2.6	2.6	2.6	0	0				0	0	
		1993	4	0	0	0	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.4	0.4	0.4	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	4.5	4.5	7.5	0	3	0.4	0.4	0.4	0	0	
38291	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1992	3	0.4	0.4	0.9	0	0.5	0.3	0.3	0.3	0	0	
		1992	2	4.5	4.5	9	0	4.5	0.4	0.4	3	0	2.6	
38991	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2.8	2.8	2.8	0	0				0	0	
		1993	2	0.1	0.1	0.1	0	0				0	0	
		1992	3	0.6	0.6	0.6	0	0				0	0	
		1992	2	4.5	4.5	5.5	0	1	0.2	0.2	0.2	0	0	
40491	WLM	1994	2	0	0	0	0	0				0	0	
		1992	2	0.4	0.4	0.6	0	0.2	0.4	0.4	0.4	0	0	
		1992	3	0.2	0.2	0.4	0	0.2	7.9	7.9	7.9	0	0	
41091	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	2	2	2	0	0				0	0	
		1993	4	0.3	0.3	0.3	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0	0	0	0	0				0	0	
		1992	3	0.4	0.4	0.4	0	0				0	0	
		1992	2	0.4	0.4	1	0	0.6	0.5	0.5	0.5	0	0	
10392	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.6	0.6	0.8	0	0.2	0.4	0.4	0.4	0	0	
10592	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0	0	0	0	0				0	0	
		1993	4	0.6	0.6	0.6	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.6	0.6	0.8	0	0.2	0.4	0.4	0.4	0	0	
A6.S1020	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0	0	0	0	0				0	0	
		1993	4	0.6	0.6	0.6	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1993	1	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.6	0.6	0.8	0	0.2	0.4	0.4	0.4	0	0	
10692	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0	0	0	0	0				0	0	
		1993	4	0.6	0.6	0.6	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.1	0.1	0.1	0	0				0	0	
		1993	1	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.4	0.6	0.6	0.2	0.2	0.4	0.4	0.4	0	0	
10792	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	1	1	1	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1993	3	0.3	0.3	0.3	0	0				0	0	
		1993	2	0.1	0.1	0.1	0	0				0	0	
		1993	1	0.3	0.3	0.3	0	0				0	0	
		1992	3	0.2	0.2	0.4	0	0.2	0.4	0.4	0.4	0	0	
10892	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.2	0.2	0.2	0	0				0	0	
		1993	4	0.2	0.2	0.2	0	0				0	0	
		1992	3	0.6	0.6	0.8	0	0.2	0.4	0.4	0.4	0	0	
46192	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	0.1	0.1	0.1	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.2	0.2	0.2	0	0				0	0	
		1992	1	0.2	0.2	0.3	0	0.1				0	0	No venting data
40193	WLM	1994	2	0	0	1.1	0	1.1	0	0	0	0	0	
46393	WLM	1994	2	0	0	2.1	0	2.1	0	0	0	0	0	
59593	SAMPLE	1994	2	0	0	0	0	0				0	0	
		1994	1	1	1	1	0	0				0	0	
		1993	3	0.2	0.2	8	0	7.8	0.1	0.1	0.1	0	0	Dissipated rapidly
		1993	2	0.2	0.2	500	0	499.8				0	0	Vented before purging
		1994	1	1	1	1	0	0				0	0	
70393	SAMPLE	1993	3	0.1	0.1	0.1	0	0				0	0	
		1994	2	0	0	0	0	0				0	0	
		1994	1	2.6	2.6	2.6	0	0				0	0	
		1993	3	0.2	0.2	0.2	0	0				0	0	
		1993	2	0.6	0.6	0.6	0	0				0	0	

APPENDIX F

SPECIAL TASK HEALTH AND SAFETY PLAN

GROUNDWATER MONITORING PROGRAM SUBCONTRACTOR

SPECIAL TASK

HEALTH AND SAFETY PLAN

Page 1 of 14

Revision Level _____

Job No. _____

1. Items 1-9 to be completed by EG&G Special Task Project Manager.

Project Name _____

Task _____

Requested by _____

Proposed Start-Up Date _____ **19** **Project/Task No.** _____

Rev. Level _____

**Prepared by/Reviewed by Groundwater Monitoring Program Subcontractor
Health and Safety Officer**

Printed Name _____

Signature _____ **Date** _____ **19**

Reviewed by Groundwater Monitoring Subcontractor Site Safety Officer

Printed Name _____

Signature _____ **Date** _____ **19**

Approved by EG&G Special Task Project Manager

Printed Name _____

Signature _____ **Date** _____ **19**

Title _____

Note to Project Managers:

A signed and completed copy of the Health and Safety Plan and a signed and completed copy of the safety briefing (p. 14) must be included in the project file.

2. Project Description:

3. Location:

4. Facility/Work Site Description:

5. Proposed Personnel and Tasks:

Project Manager _____

Field Team Leader _____

Proposed Field Team

Job Function/Tasks

6. Confined Space Entry

A confined space is defined as any space not currently used or intended for human occupancy, having a limited means of egress, which is subject to the accumulation of toxic contaminants, a flammable or oxygen deficient atmosphere, or other hazards, such as engulfment, or electrical or mechanical hazards should equipment be inadvertently activated while an employee is in the space. Confined spaces include but are not limited to storage tanks, process vessels, bins, boilers, ventilation or exhaust ducts, air pollution control devices, smoke stacks, underground utility vaults, sewers, septic tanks, and open top spaces more than four feet in depth such as test pits, waste disposal trenches, sumps and vats.

Will this task require entry into any confined or partially confined space? ☐ YES - Describe below
☐ No

7. Cutting and Welding

Will this task involve use of a cutting torch or welding? ☐ YES - Describe below
☐ No

8. Other Potential Hazards

<input type="checkbox"/> Chemical	<input type="checkbox"/> Trips, Slips, Falls
<input type="checkbox"/> Radiological	<input type="checkbox"/> Trenching/Shoring
<input type="checkbox"/> Fire/Explosion	<input type="checkbox"/> Heavy Equipment/Vehicular Traffic
<input type="checkbox"/> Heat Stress	<input type="checkbox"/> Overhead Hazards
<input type="checkbox"/> Electrical	<input type="checkbox"/> Unstable/Uneven Terrain
<input type="checkbox"/> Machinery/Mechanical Equipment	<input type="checkbox"/> Other - Describe below

6,7,8 Description/Other

9. I, _____, attest that this information is accurate to the best of my knowledge and hereby request a Health and Safety Plan for the task(s) designated above.

Signature

Date

Title

10. Chemical/Radiological Hazard Evaluation

Waste Media

- ☐ Airborne Contamination
- ☐ Surface Contamination
- ☐ Contaminated Soil
- ☐ Contaminated Groundwater
- ☐ Contaminated Surface Water
- ☐ Solid Waste
- ☐ Liquid Waste
- ☐ Sludge

Hazardous Characteristics

- ☐ Ignitable
- ☐ Corrosive
- ☐ Reactive
- ☐ Explosive
- ☐ Toxic (non-radiological)
- ☐ Radioactive

Substance

This task will involve the reasonable possibility of exposure to the substances listed below at concentrations or in quantities which may be hazardous to the health of the site personnel.

Primary Hazard (Rate: low, med, high, ext)

Substance	Inhalation of Gases/ Vapors	Inhalation of Dusts/ Mists	Ingestion	Dermal Absorption of Solids/ Liquids and/or Skin Contam.	Dermal Absorption of Gases/ Vapors	Corrosive/ Irritant	Ignit- ability	Reactivity/ Explosion
-----------	-----------------------------------	----------------------------------	-----------	--	---	------------------------	-------------------	--------------------------

Substance	Exposure Limit	IDLH Level	Health Effects
-----------	----------------	------------	----------------

11. Ambient Air/Site Monitoring Procedures

The following instruments shall be used to monitor the work environment and workers' breathing zones prior to site entry and at the specified intervals.

Instrument	Monitoring Frequency				
___ PID (HNU, OVM) w/___eV lamp	Cont.	15min.	30min.	hourly	other _____
___ OVA	Cont.	15min.	30min.	hourly	other _____
___ Combustible Gas Indicator	Cont.	15min.	30min.	hourly	other _____
___ H2S Detector	Cont.	15min.	30min.	hourly	other _____
___ Colorimetric Detector Tubes	Cont.	15min.	30min.	hourly	other _____
___ Other (describe below)	Cont.	15min.	30min.	hourly	other _____

Description/Other:

12. Action Levels

Task personnel shall observe the following Action Levels:

<u>Instrument</u>	<u>Action Level</u>	<u>Specific Action</u>
-------------------	---------------------	------------------------

13. Personal Monitoring

☐ Passive Dosimeter

☐ Personal Air Sampling

☐ Other

Description/Other:

14. Biological Monitoring/Medical Surveillance

☐ This project requires medical surveillance or biological monitoring procedures beyond the provisions of the routine medical surveillance program, see description below

Description:

15. Onsite Control

Control boundaries have been established, and the Exclusion Zone (the contaminated area), Hotline, Decontamination Line, Contamination Control Zone and Support Zone (clean area) have been designated and are identified as follows:

(Name) _____ has been designated to coordinate access control on the work site during this task. No unauthorized person shall be allowed beyond the Contamination Control line.

16. Personal Protective Equipment

Location	Job Function/Task	Initial Level of Protection						
Controlled Zone	_____	B	C	D	1	2	3	other
	_____	B	C	D	1	2	3	other
	_____	B	C	D	1	2	3	other
Decontamination Zone	_____	B	C	D	1	2	3	other
	_____	B	C	D	1	2	3	other
	_____	B	C	D	1	2	3	other

List the specific protective equipment and material (where applicable) for each of the Levels of Protection identified above

Level B _____

- ___ Pressure demand airline
- ___ Pressure demand airline with escape provisions
- ___ Pressure demand SCBA

Level C _____

- ___ Half face Air Purifying Respirator
- ___ Full face Air Purifying Respirator
- ___ Full face canister Air Purifying Respirator
- ___ Standard work clothes
- ___ Hard hat, steel toed boots, safety glasses
- ___ Ear protection during drill rig operation
- ___ Inner latex gloves
- ___ Outer NBR (Nitrile Butyl Rubber) gloves

Level _____

- ___ Standard works clothes
- ___ Hard hat, steel toed boots, safety glasses
- ___ Ear protection during drill rig operation
- ___ Inner latex gloves
- ___ Outer NBR gloves

Level _____

Where air purifying respirators are authorized, _____ are the appropriate canisters/cartridges for use with the specific substances and concentrations anticipated. Cartridges shall be replaced at the start of each work day.

NO CHANGES TO THE SPECIFIED LEVELS OF PROTECTION SHALL BE MADE WITHOUT THE KNOWLEDGE AND APPROVAL OF THE HEALTH AND SAFETY OFFICER AND THE PROJECT MANAGER

17. Decontamination

Personnel and equipment leaving the Controlled Zone shall proceed through the following decontamination stations and procedures from the decontamination zone:

Personnel Decontamination

Station

Procedure

Equipment Decontamination

Station

Procedure

The following decontamination equipment is required:

Emergency decontamination procedures:

18. Confined Entry Procedures ☐ Not Applicable

Yes N/A

☐ ☐ Provide Forced Ventilation

☐ ☐ Test Atmosphere For:

☐ ☐ (a) %O₂

☐ ☐ (b) %LEL

☐ ☐ (c) Other

Descriptions/Other:

Yes N/A

☐ ☐ Refer to Personal Protective Equip. (#16)

☐ ☐ Refer to Emergency Procedures (#29)

☐ ☐ Other Special Procedures

19. Cutting/Welding Procedure ☐ Not Applicable

Yes N/A

☐ ☐ Relocate or Protect Combustibles

☐ ☐ Wet Down or Cover Combustible Floor

☐ ☐ Check Flammable Gas Concentrations (%LEL) in air

☐ ☐ Cover Wall, Floor, Duct and Tank Openings

☐ ☐ Provide Fire Extinguisher

Other Special Instructions:

20. Onsite Organization and Coordination

Project Manager: _____

Field Team Leader: _____

Site Safety Officer: _____

Field Team	Name	Job Function
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

21. Special Instructions

22. Sanitation Requirements

Potable water supply available on work site? ☐ Yes

Portable toilets required on work site? ☐ Yes If Yes, how many? _____
☐ No

Temporary washing/shower facilities required at work site? ☐ Yes If yes, describe below.
☐ No If no, state location
existing facilities.

Description:

23. Field Procedures Change Authorization

Instruction Number _____ Duration of Authorization Requested _____ Date: _____
to be changed ☐ Today only
☐ Duration of Task

Description of Procedures Modification:

Justification:

Person Requesting Change:

Verbal Authorization Received From:

Name

Name

Time

Title

Title

Signature

Approved By

(Signature of person named above to be obtained
within 48 hours of verbal authorization)

24. **Emergency Procedures** This page is to be posted at prominent location on site.

Yes No

_____ _____ On-site Communications Required? Emergency Channel _____

Nearest Telephone _____

Fire and Explosion

In the event of a fire or explosion, if the situation can be readily controlled with available resources without jeopardizing the health and safety of yourself, the public, or other site personnel, take immediate action to do so, otherwise:

1. Notify emergency personnel by calling _____.
2. If possible, isolate the fire to prevent spreading.
3. Evacuate the area

Chemical Exposure

Site workers must notify the site health and safety officer immediately in the event of any injury or any of the signs or symptoms of overexposure to hazardous substances identified below:

Substances Present

Symptoms of Acute Exposure

First Aid

24. Emergency Procedures - Cont'd

On Site Injury Or Illness

In the event of an injury requiring more than minor first aid, or any employee reporting any sign or symptom of exposure to hazardous substances, immediately take the victim to _____ located at _____, phone _____. In the event of life-threatening or traumatic injury, implement appropriate first-aid and immediately call for emergency medical assistance at _____. The nearest designated trauma center is _____ located at _____, phone _____.

Designated Personnel Current in First Aid/CPR (Names)

_____	_____
_____	_____
_____	_____
_____	_____

Designated Back-Up Personnel (Names)

Function

_____	_____
_____	_____
_____	_____
_____	_____

Required Emergency Back-Up Equipment

Emergency Response Authority

_____ is the designated site emergency coordinator and has final authority for first response to on-site emergency situations.

Upon arrival of the appropriate emergency response personnel, the site emergency coordinator shall defer all authority but shall remain on the scene if necessary to provide any and all possible assistance. At the earliest opportunity, the site safety officer or the site emergency coordinator shall contact the project coordinator or health and safety officer.

Project Coordinator _____ Phone (w) _____ (h) _____

Health and Safety _____ Phone (w) _____ (h) _____
Officer

25. Safety Briefing

The following personnel were present at pre-job safety briefing conducted at _____ (time) on _____
_____ (date) at _____ (location), and have read the above plan and are familiar
with its provisions:

Name

Signature

Fully charged ABC Class fire extinguisher available on site?	YES _____
Fully stocked First Aid Kit available on site?	YES _____
All project personnel advised of location of nearest phone?	YES _____
All project personnel advised of location of designated medical facility or facilities?	YES _____

Printed Name of Field Team Leader or Site Safety Officer

Signature

Date

TABLE C-1

ANALYTE CONCENTRATIONS FOR COMBINED OPERABLE UNITS 1-16
AND UPPER AND LOWER SOUTH INTERCEPTOR DITCHES
(Concluded)

Parameter	Groundwater			Surface Water			Soils			Sediments		Potential** ARAR
	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential** ARAR	Maximum ⁺	Minimum ⁺⁺	
POLYCHLORINATED BIPHENYLS (PCBs) (µg/L)												
Aroclor-1254				12	1.0	1.0	440000		0.09	1600000		160

NOTE: Analytical data received prior to October 1988 not subjected to validation procedure. Some of the chemical values reported in this table have not yet been validated, and the analyte list may be changed after the data are validated.

- = Present in laboratory blank
- ** = These are based on human health and environmental risk assessment criteria developed for screening purposes, or applicable state or federal requirements.
- J = Analyzed below detection limit
- BR = Bedrock (including some weathered bedrock)
- + = Maximum concentration may be a one-time measurement. Values compiled from both recent and historic data, checked against Rocky Flats Environmental Data System.
- ++ = Value given is detection or quantitation limit for analysis, in accordance with Statement of Work for General Radiochemistry and Routine Analytical Services Protocol (G.R.R.A.S.P.), v.1.1, 1990, EG&G Rocky Flats Environmental Restoration Program.
- (a) = Plutonium 238 + 239 + 240
- (b) = Radium 226 + 228
- (c) = Ammonia as N
- (d) = Sum of polychlorinated biphenyls (PCBs) in water
- ¹ = Source: U.S. Department of Energy. March 1992. Annual Report for Treatability Studies at Rocky Flats Plant - Fiscal Year 1991.
- Δ = This table was reproduced precisely from a previous report.

TABLE C-1

ANALYTE CONCENTRATIONS FOR COMBINED OPERABLE UNITS 1-16
AND UPPER AND LOWER SOUTH INTERCEPTOR DITCHES
(Concluded)

Parameter	Groundwater			Surface Water			Soils			Sediments		
	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR
N-Nitroso-di-n-Propylamine				5 J	10	10						
N-Nitrosodiphenylamine	162 *	10	10	300	10	10	880 J	330		2000 *	330	
Pentachlorophenol	4.0 J	50	50	20 J	50	50	110 J	1600	200000	350 J	1600	
Phenanthrene				6.0 J	10	10	500 J	330		16000	330	
Phenol	1.0 J	10	10	39	10	10	320 J	330	3000000	660 J	330	
Prometon				0.09	0.03							
Prometryn				0.18	0.06							
Propazine				2.4	0.03							
Pyrene				4 J	10	10	880 J	330		19000	330	
Simazine				330	0.06	4.0						
Simetryn				0.64	0.07							
Terbutylazine				1.4								
1,2,4-Trichlorobenzene				4	10	700				4.0 J	330	

* = Present in laboratory blank

** = These are based on human health and environmental risk assessment criteria developed for screening purposes, or applicable state or federal requirements.

J = Analyzed below detection limit

BR = Bedrock (including some weathered bedrock)

+ = Maximum concentration may be a one-time measurement. Values compiled from both recent and historic data, checked against Rocky Flats Environmental Data System.

++ = Value given is detection or quantitation limit for analysis, in accordance with Statement of Work for General Radiochemistry and Routine Analytical Services Protocol (G.R.R.A.S.P.), v.1.1, 1990, EG&G Rocky Flats Environmental Restoration Program.

(a) = Plutonium 238 + 239 + 240

(b) = Radium 226 + 228

(c) = Ammonia as N

(d) = Sum of polychlorinated biphenyls (PCBs) in water

¹ = Source: U.S. Department of Energy. March 1992. Annual Report for Treatability Studies at Rocky Flats Plant - Fiscal Year 1991.

Δ = This table was reproduced precisely from a previous report.

TABLE C-1

ANALYTE CONCENTRATIONS FOR COMBINED OPERABLE UNITS 1-16
AND UPPER AND LOWER SOUTH INTERCEPTOR DITCHES

(Continued)

Parameter	Groundwater			Surface Water			Soils			Sediments		
	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR
Dichloroprop				1.8	0.65							
Diethyl Phthalate				6.0	J	23000	31	330	6000000	1200	330	
Di-n-Butyl Phthalate	170	J BR	10	20	"	10	3643	J	330	3100	330	
Di-n-Octyl Phthalate	56	J BR	10	24	"	10	370	J	330	2000	330	
2,4-Dimethylphenol				6.0	J	2120						
2,4-Dinitrotoluene				4.0	J	10						
Endosulfan										1600	J	8.0
Ethyl Parathion	0.04			270		0.13						
Fluoranthene	10	10		2.0	J	42	1900	330		16000	330	
Fluorene				3.0	J	10	350	330		2000	J	330
Gamma-BHC (Lindane)										50		8.0
Hexachlorobenzene										440	J	330
Indeno (1,2,3-cd) Pyrene							80	J	330	5000	J	330
Isophorone				1.0	J	10						
2-Methylnaphthalene				21	J	10				350	J	330
2-Methylphenol				43		10				2300		330
4-Methylphenol				160		10				2300		330
Naphthalene				25		10				1100	J	330
2-Nitrophenol	3.0	J	10									
4-Nitrophenol	2.0	J	50				160	J	1600			
4-Nitroaniline										5300	J	1600

* = Present in laboratory blank
 ** = These are based on human health and environmental risk assessment criteria developed for screening purposes, or applicable state or federal requirements.
 J = Analyzed below detection limit
 BR = Bedrock (including some weathered bedrock)
 + = Maximum concentration may be a one-time measurement. Values compiled from both recent and historic data, checked against Rocky Flats Environmental Data System.
 ++ = Value given is detection or quantitation limit for analysis, in accordance with Statement of Work for General Radiochemistry and Routine Analytical Services Protocol (G.R.R.A.S.P.), v.1.1, 1990, EG&G Rocky Flats Environmental Restoration Program.
 (a) = Plutonium 238 + 239 + 240
 (b) = Radium 226 + 228
 (c) = Ammonia as N
 (d) = Sum of polychlorinated biphenyls (PCBs) in water
 1 = Source: U.S. Department of Energy. March 1992. Annual Report for Treatability Studies at Rocky Flats Plant - Fiscal Year 1991.
 A = This table was reproduced precisely from a previous report.

TABLE C-1

ANALYTE CONCENTRATIONS FOR COMBINED OPERABLE UNITS 1-16
AND UPPER AND LOWER SOUTH INTERCEPTOR DITCHES

(Continued)

Parameter	Groundwater			Surface Water			Soils			Sediments		Potential** ARAR
	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential** ARAR	Maximum ⁺	Minimum ⁺⁺	
Benzo (a) Anthracene				2.0 J	10	10	120 J	330	224	7100	330	
Benzo (b) Fluoranthene				3.0 J	10	10	350 J	330		7100	330	
Benzo (k) Fluoranthene				4.0 J	10	10	320 J	330		6300	330	
Benzo (g,h,i) Perylene							50 J	330		5700	330	
Benzo (a) Pyrene				3.0 J	10.0	10	230 J		60.9	6300	330	
Benzo (k) Pyrene							130 J	330				
Benzoic Acid				8.0 J	50		400 J	1600		3300 J	1600	
Benzyl Alcohol				43	10							
Beta-BHC				0.1	0.05	0.05				13000	8.0	
Bis (2-ethylhexyl) Phthalate	100 J BR	10	10	220	10	10	18000 *	330	83000	41	330	
Butyl Benzyl Phthalate	2.0 J	10		3.0 J	10	3000	510 J	330		540 J	330	
4-Chloro-3-methylphenol				1.0 J	10	30	740	330				
4-Chlorophenyl Phenyl Ether							40 J	330				
Chrysene	420	10		2.0 J	10	10	550 J	330		8200	330	
Cyanazine				0.3	0.1							
4,4-DDT				0.06 J	0.1	0.1				95	16	
Delta-BHC				0.02	0.05					3.2 J	8.0	
Dibenzo (a,h) Anthracene										1200	330	
Dibenzofuran				1.0 J						1000 J		
Dicamba				2.1	0.27							
1,4-Dichlorobenzene				4.0 J	10	75						

* = Present in laboratory blank

** = These are based on human health and environmental risk assessment criteria developed for screening purposes, or applicable state or federal requirements.

J = Analyzed below detection limit

BR = Bedrock (including some weathered bedrock)

+ = Maximum concentration may be a one-time measurement. Values compiled from both recent and historic data, checked against Rocky Flats Environmental Data System.

++ = Value given is detection or quantitation limit for analysis, in accordance with Statement of Work for General Radiochemistry and Routine Analytical Services Protocol (G.R.A.S.P.), v.1.1, 1990, EG&G Rocky Flats Environmental Restoration Program.

(a) = Plutonium 238 + 239 + 240

(b) = Radium 226 + 228

(c) = Ammonia as N

(d) = Sum of polychlorinated biphenyls (PCBs) in water

¹ = Source: U.S. Department of Energy. March 1992. Annual Report for Treatability Studies at Rocky Flats Plant - Fiscal Year 1991.

Δ = This table was reproduced precisely from a previous report.

TABLE C-1

ANALYTE CONCENTRATIONS FOR COMBINED OPERABLE UNITS 1-16
AND UPPER AND LOWER SOUTH INTERCEPTOR DITCHES

(Continued)

Parameter	Groundwater			Surface Water			Soils			Sediments		
	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR
Dibromochloromethane				5.0	5.0	6.0						
Ethylbenzene	16	5.0	680	18	5.0	680	780	5.0	8000000	4.0	5.0	
Methylene Chloride	4100	5.0	5.0	340	5.0	5.0	590 BR	5.0	93000	16000	5.0	
Styrene	9	5.0	100	6.0	5.0	100	17 J	5.0	23000	2.0 J	5.0	
Tetrachloroethene	528000	5.0	5.0	280	5.0	5.0	10000	5.0	140000	8.0	5.0	
Toluene	270 J	5.0	1000	94	5.0	1000	860	5.0	20000000	120	5.0	
Trichloroethene	221860	5.0	5.0	2500	5.0	5.0	17000	5.0	64000	39	5.0	
Vinyl Acetate	39 J	10		3.0 J	10							
Vinyl Chloride	930	10	10	25	10	10				57 J	10	
Xylenes (Total)	50 J	5.0	10000	40	5.0	10000	3300	5.0	200000000	7.0 J	5.0	
SEMIVOLATILES (TOTAL) (ug/L)												
				(ug/L)			(ug/kg)			(ug/kg)		
Acenaphthene				5.0 J	10	520	57 J	330		2400 J	330	
Acenaphthylene										450 J	330	
Aldrin				0.06	0.05	0.05						
Alpha-BHC				0.01 J	0.05	0.05				4.7 J	8.0	
Alpha-chlordane				2.6	0.5	0.5						
Ametryn				0.18	0.06							
Anthracene				2.0 J	10	10	180 J	330		2900 J	330	
Atrazine				2720.0	0.05	3.0						

• = Present in laboratory blank

** = These are based on human health and environmental risk assessment criteria developed for screening purposes, or applicable state or federal requirements.

J = Analyzed below detection limit

BR = Bedrock (including some weathered bedrock)

+ = Maximum concentration may be a one-time measurement. Values compiled from both recent and historic data, checked against Rocky Flats Environmental Data System.

++ = Value given is detection or quantitation limit for analysis, in accordance with Statement of Work for General Radiochemistry and Routine Analytical Services Protocol (G.R.R.A.S.P.), v.1.1, 1990, EG&G Rocky Flats Environmental Restoration Program.

(a) = Plutonium 238 + 239 + 240

(b) = Radium 226 + 228

(c) = Ammonia as N

(d) = Sum of polychlorinated biphenyls (PCBs) in water

¹ = Source: U.S. Department of Energy. March 1992. Annual Report for Treatability Studies at Rocky Flats Plant - Fiscal Year 1991.

A = This table was reproduced precisely from a previous report.

TABLE C-1

ANALYTE CONCENTRATIONS FOR COMBINED OPERABLE UNITS 1-16
AND UPPER AND LOWER SOUTH INTERCEPTOR DITCHES

(Continued)

Parameter	Groundwater			Surface Water			Soils			Sediments		
	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR
1,1,2-Trichloroethane	14740	5.0	5.0	6.0	5.0	5.0	62	5.0	120000			
1,1,2,2-Tetrachloroethane	15	5.0	5	440	5.0	5.0						
1,2-Dichloroethane	16000	5.0	5	23			120	5.0	7700			
1,2-Dichloroethene (Total)	14000	5.0	100	460	5.0	100	140	5.0				
1,2-Dichloropropane	6	5.0	5	7.0	5.0	5.0	3.0	5.0				
1,3-Dichloropropene	3 J	5.0		7.0	5.0	10	6.0 J	5.0	3900			
2-Butanone	580	10		76	10		530	10.0		12000	10	
2-Chloroethylvinylether				5.0 J			31 J	10.0				
2-Hexanone	975	10		87			41					
4-Methyl-2-Pentanone	35	10.0		32 *	10		120 J	10		220 *	10	
Acetone	4100 J*	10.0	4000	970 *	10	4000	2400 *	10	8000000	7300	10	
Benzene	83 J	5.0	5.0	83	5	5	12 J	10	24000	3.0 J	10	
Bromodichloromethane	1.0 J	5.0	5.0	6.0	5	700						
Bromoform	1.0 J	5.0	5.0	3.0 J	5	700						
Bromomethane	7.0 J	10.0	10	8.0 J	10	48	6.0 J	10	30000			
Carbon Disulfide	28	5.0	4000	29	5.0	4000	150		8000000	13 J	5.0	
Carbon Tetrachloride	28000	5.0	5.0	1005	5.0	5.0	180 *	5.0	5400			
Chlorobenzene	73	5.0		94	5.0	100	150	55	2000000	4.0 J	5.0	
Chloroethane	17	10.0		34	10		50 J	10				
Chloroform	5427	5.0	5.0	84	5.0	5.0	130 J	5.0	110000	18	5.0	
Chloromethane	17	10.0		38	10					60	10	

* = Present in laboratory blank

** = These are based on human health and environmental risk assessment criteria developed for screening purposes, or applicable state or federal requirements.

J = Analyzed below detection limit

BR = Bedrock (including some weathered bedrock)

+ = Maximum concentration may be a one-time measurement. Values compiled from both recent and historic data, checked against Rocky Flats Environmental Data System.

++ = Value given is detection or quantitation limit for analysis, in accordance with Statement of Work for General Radiochemistry and Routine Analytical Services Protocol (G.R.R.A.S.P.), v.1.1, 1990, EG&G Rocky Flats Environmental Restoration Program.

(a) = Plutonium 238 + 239 + 240

(b) = Radium 226 + 228

(c) = Ammonia as N

(d) = Sum of polychlorinated biphenyls (PCBs) in water

¹ = Source: U.S. Department of Energy, March 1992. Annual Report for Treatability Studies at Rocky Flats Plant - Fiscal Year 1991.

A = This table was reproduced precisely from a previous report.

TABLE C-1

ANALYTE CONCENTRATIONS FOR COMBINED OPERABLE UNITS 1-16
AND UPPER AND LOWER SOUTH INTERCEPTOR DITCHES

(Continued)

Parameter	Groundwater			Surface Water			Soils			Sediments		
	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR
Gross Alpha	2000	2.0	7.0	2107	2.0	7.0	480	4.0	5.0	77	4.0	5.0
Gross Beta	1200	4.0	5.0	3800	4.0	5.0	49.9	10	50.0	53	10	50
Plutonium 238	0.040	0.01	0.05	0.031	0.01					0.016	0.03	
Plutonium 239 + 240	8.13	0.01	15(a)	120	0.01	15(a)	180	0.03	0.9	3.3	0.03	0.9
Radium 226	3.54	0.5	5(b)	30	0.5	5(b)	1.9	0.5		1.96	0.5	
Radium 228	13.95	1.0	5(b)	52	0.5	5(b)	2.8	0.5		4.41	0.5	
Strontium 89 + 90	7.52	1.0		4.27	1.0		1.9	1		2.53	1	
Strontium 90	12.4	1.0	8.0	33.34	1.0	8.0	4.57	1		0.99	1	
Tritium	12000	400	500	13000	400	500	3.9	400		580	400	
Uranium 233 + 234	1000	0.6		1050	0.6		3.7	0.3		4.11	0.3	
Uranium 233 + 238 + 239	16.9	0.6		14.31	0.6					3.32	0.3	
Uranium 235	47	0.6		65.5	0.6		1.01	0.3		1.34	0.3	
Uranium 235 + 236	6.90	0.6		47.5	0.6					0.15		
Uranium 238	750	0.6		1211	0.6		3.9	0.3		3.82	0.3	
Uranium (Total)	63.7	0.6	5	1023	0.6	5.0	4.0 BR	0.3		4.8	0.3	
VOLATILES (ug/L)												
				(ug/L)				(ug/kg)				
1,1-Dichloroethane	344	5.0		50	5.0		49	5				
1,1-Dichloroethene	48000	5.0	7	143	5.0	7.0	110	5	12000	5.0 J	5.0	
1,1,1-Trichloroethane	30250	5.0	200	42	5.0	200	290	5.0	7000000	3.0 J	5.0	

• = Present in laboratory blank

** = These are based on human health and environmental risk assessment criteria developed for screening purposes, or applicable state or federal requirements.

J = Analyzed below detection limit

BR = Bedrock (including some weathered bedrock)

+ = Maximum concentration may be a one-time measurement. Values compiled from both recent and historic data, checked against Rocky Flats Environmental Data System.

++ = Value given is detection or quantitation limit for analysis, in accordance with Statement of Work for General Radiochemistry and Routine Analytical Services Protocol (G.R.R.A.S.P.), v.1.1, 1990, EG&G Rocky Flats Environmental Restoration Program.

(a) = Plutonium 238 + 239 + 240

(b) = Radium 226 + 228

(c) = Ammonia as N

(d) = Sum of polychlorinated biphenyls (PCBs) in water

¹ = Source: U.S. Department of Energy. March 1992. Annual Report for Treatability Studies at Rocky Flats Plant - Fiscal Year 1991.

A = This table was reproduced precisely from a previous report.

TABLE C-1

ANALYTE CONCENTRATIONS FOR COMBINED OPERABLE UNITS 1-16
AND UPPER AND LOWER SOUTH INTERCEPTOR DITCHES

(Continued)

Parameter	Groundwater			Surface Water			Soils			Sediments		
	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR
Selenium	100.3	0.005	0.010	0.55	0.005	0.005	6.5	1.0		21.3	1.0	
Silicon	56.4	0.010		44	0.010					2470	4.6	
Silver	0.217	0.010	0.050	0.148	0.010	0.010	40.9	2.0	200	411	2.0	
Sodium	4447	5.000		9080	5.000		44000	2000		1480	2000	
Strontium	82.4	0.200		11.9	0.200		1030	40		1230	40	
Thallium	0.544	0.050		0.029	0.050	0.050	5.74	2.0		90	2.0	
Tin	1.121	0.200		1.53	0.200		382	40		1080	40	
Vanadium	0.85	0.050	0.1	1.65	0.050		2590	10		90.4	10	
Zinc	5.0	0.020	2.0	28.7	0.020	0.110	487	4.0		735	4.0	
ANIONS (mg/L)												
	(mg/L)			(mg/L)			(mg/kg)			(mg/kg)		
Ammonia				65	0.5	0.5						
Chloride	1100	5.0	250	1200	5.0	230	20			210		
Cyanide	3.8	0.01	0.2	0.6	0.01	0.01	19.8			1.0		
Fluoride	8.2	5.0	5.0	7.7	5.0	5.0						
Nitrate as N	1450	5.0	10.0	1186	5.0	10.0	4.3			35.86		
RADIONUCLIDES (TOTAL AND DISSOLVED) (pCi/L)												
	(pCi/L)			(pCi/L)			(pCi/g)			(pCi/g)		
Americium 241	9.68	0.01		90	0.01	30	22	0.02		1.467	0.02	
Cesium 137	7.72	1.0		12	1.0		4.7	0.1		3.2	0.1	

* = Present in laboratory blank

** = These are based on human health and environmental risk assessment criteria developed for screening purposes, or applicable state or federal requirements.

J = Analyzed below detection limit

BR = Bedrock (including some weathered bedrock)

+ = Maximum concentration may be a one-time measurement. Values compiled from both recent and historic data, checked against Rocky Flats Environmental Data System.

++ = Value given is detection or quantitation limit for analysis, in accordance with Statement of Work for General Radiochemistry and Routine Analytical Services Protocol (G.R.R.A.S.P.), v.1.1, 1990, EG&G Rocky Flats Environmental Restoration Program.

(a) = Plutonium 238 + 239 + 240

(b) = Radium 226 + 228

(c) = Ammonia as N

(d) = Sum of polychlorinated biphenyls (PCBs) in water

¹ = Source: U.S. Department of Energy. March 1992. Annual Report for Treatability Studies at Rocky Flats Plant - Fiscal Year 1991.

Δ = This table was reproduced precisely from a previous report.

TABLE C-1

ANALYTE CONCENTRATIONS FOR COMBINED OPERABLE UNITS 1-16
AND UPPER AND LOWER SOUTH INTERCEPTOR DITCHES¹

Parameter	Groundwater			Surface Water			Soils			Sediments		
	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR	Maximum ⁺	Minimum ⁺⁺	Potential ^{**} ARAR
METALS (TOTAL AND DISSOLVED) (mg/L)												
Aluminum	37.7	0.200	0.2	293	0.200	0.200	70600	40		33900	40	
Antimony	0.628	0.060		0.643	0.060	0.060	57	12	30	69.7	12	
Arsenic	3.0	0.010	0.05	1.03	0.010	0.05	64	2.0		49.2	2	
Barium	0.943	0.200	1.0	11600	0.200	1.0	1899	40	4000	706	40	
Beryllium	0.04	0.005	0.1	0.170	0.005	0.005	18.3	1.0	0.143	15.5	1.0	
Boron	0.218	5.0	5.0									
Cadmium	0.0352 BR	0.005	0.005	25	0.005	0.005	119	1.0		19.5	1.0	
Calcium	99.9 BR	5.000		1590	5.000		254000	2000		132000	2000	
Cesium	0.4	1.000		12	1.000		2410	200		700		
Chromium	0.172 BR	0.010	0.05	0.298	0.010	0.05	781	2.0	8000(III)	64	2.0	
Cobalt	0.22	0.050	0.05	0.489	0.050		88.9	10		43.3	10	
Copper	3.13	0.025	0.2	0.908	0.025	0.025	73.6	5.0		275	5.0	
Iron	76.6	0.100	0.3	3220	0.100	0.30	75900	20		33300	20	
Lead	2.8	0.005	0.05	0.950	0.005	0.005	86.9	1.0		255	1.0	
Lithium	1.79	0.100	2.5	85.2	0.100		100	20		958	20	
Magnesium	788	5.000		391	5.000		23300	2000		103000	2000	
Manganese	11.34	0.015	0.05	27.7	0.015	0.050	3540	3.0		1950	3.0	
Mercury	0.013	0.0002	0.002	3.97	0.0002	0.0002	114	0.2		1.5	0.2	
Molybdenum	1.92 BR	0.200		0.680	0.200		38.65	40		177	40	
Nickel	11.7	0.040	0.2	0.82	0.040	0.4	543	8.0	2000	89.2	8.0	
Phosphorus	1.210	0.040		12	0.040					655	200	
Potassium	7050	5.000		4260	5.000		8020	2000		67000	2000	

* = Present in laboratory blank

** = These are based on human health and environmental risk assessment criteria developed for screening purposes, or applicable state or federal requirements.

J = Analyzed below detection limit

BR = Bedrock (including some weathered bedrock)

+ = Maximum concentration may be a one-time measurement. Values compiled from both recent and historic data, checked against Rocky Flats Environmental Data System.

++ = Value given is detection or quantitation limit for analysis, in accordance with Statement of Work for General Radiochemistry and Routine Analytical Services Protocol (G.R.R.A.S.P.), v.1.1, 1990, EG&G Rocky Flats Environmental Restoration Program.

(a) = Plutonium 238 + 239 + 240








(b) = Radium 226 + 228

(c) = Ammonia as N


(d) = Sum of polychlorinated biphenyls (PCBs) in water

¹ = Source: U.S. Department of Energy. March 1992. Annual Report for Treatability Studies at Rocky Flats Plant - Fiscal Year 1991.

Δ = This table was reproduced precisely from a previous report.

 Paved roads
 Unimproved dirt roads
 Streams, Ditches, and other drainage features
 Rocky Flats Environmenta Technology Site boundary
 1994
 Ponds/Lakes
 1994
 Buildings or Structures

401789 RCRA Alluvial well
 250159 RCRA Bedrock well
 2780 RCRA Characterization wells
 5386 CERCLA Alluvial wells
 02891 CERCLA Bedrock wells
 40091 CERCLA Alluvial/Bedrock wells
 5586 Background Alluvial wells
 405489 Background Bedrock wells
 12147 Boundary Alluvial wells
 22147 Boundary Bedrock wells
 25147 Boundary Alluvial/Bedrock wells
 0590 Special Purpose Alluvial wells
 5466 Special Purpose Bedrock wells
 10894 Special Purpose Alluvial/Bedrock wells



Mapscale = 1 : 6000
1 inch = 500 feet



State Plane Coordinate Projection
Zone 3476

Prepared By:



Rocky Flats Environmental Technology Site
P.O. Box 464
Golden Colorado 80402-0464

Date August 30, 1994

Figure 3-2

[illegible]

1	11/17/94	ADDED 4xx94 AND 6xx94 WELLS	RLB	LC
REV	DATE	DESCRIPTION	DR	BY

C:\ACAD\TEMP\27155022 Tue Apr 4 15:45:13 1995 Plotted from Machine Shannons

Job No / Dwg No: 2715E022
Last Update: 1-4-95